Rick Mystrom, Mayor

MOA Street Sediment Loading Assessment Data Report

Document No. WMP APr97001

MUNICIPALITY OF ANCHORAGE
WATERSHED MANAGEMENT PROGRAM

February 1997

WATERSHED MANAGEMENT

Department of Public Works

MOA Street Sediment Loading Assessment Data Report

Document No.: WMP APr97001

WMS Project No.: 95003

Prepared for:

Watershed Management Section
Project Management and Engineering
Department of Public Works
Municipality of Anchorage

Prepared by:

Montgomery Watson
4100 Spenard Road
Anchorage, Alaska 99517

Contributors:

Principal Author: Chris Brown, Montgomery Watson Chemist
Contributing Author: Eric Gropp, Montgomery Watson Engineer

Reviewers: Scott R. Wheaton, WMS Watershed Engineer
Brett Jokela, Montgomery Watson Principal Engineer

TABLE OF CONTENTS

1. INTRODUCTION 1-1

2. EXPLANATION OF DATA SUBMITTAL ELEMENTS 2-1

3. PROJECT SUMMARY 3-1
   3.1 PROJECT SUMMARY 3-1
   3.2 VARIATIONS FROM DESIGN 3-3
      3.2.1 Spatial Network Variations 3-3
      3.2.2 Temporal Network Variations 3-3
      3.2.3 Sampling Procedure Variations 3-4
   3.3 NOTABLE FIELD OBSERVATIONS 3-4
   3.4 DATA VALIDATION 3-5
      3.4.1 On-site Inspections 3-5
      3.4.2 Review of Field and Sieve Analysis Data 3-6

4. PROJECT DATA SUMMARY 4-1
   4.1 HEPA AND WET/DRY VACUUM DATA CORRELATION 4-1
   4.2 DATA TRENDS 4-1
   4.3 DATA SUMMARIES BY PARTICLE SIZE CLASSIFICATION 4-2

5. REFERENCES 5-1

6. LIST OF PREPARERS 6-1

LIST OF FIGURES

1 Sampling Site Locations
2 Sampling Site Diagram
3 Field Observations
4 Correlation Analysis Between Results from Wet/Dry Vacuum and HEPA Vacuum

LIST OF TABLES

1 Sampling Site Locations and Dates
2 Correlation Analysis Between Results from Wet/Dry Vacuum and HEPA Vacuum
3 Total Sediment Unit Loads Summary
4 Air Suspendable Sediment Unit Loads Summary
5 Summary of Total Sediment Unit Loads (Wet/Dry Vacuum)
6 Summary of Air-Suspendable Sediment Unit Loads (Wet/Dry Vacuum)
7 Summary of OGS Treatable Sediment Unit Loads (Wet/Dry Vacuum)
8 Summary of Non-OGS Treatable Sediment Unit Loads (Wet/Dry Vacuum)
9 Summary of Total Sediment Unit Loads (HEPA Vacuum)
10 Summary of Air-Suspendable Sediment Unit Loads (HEPA Vacuum)

APPENDICES

Field Logs and Sediment Analysis Data
Chain of Custody Reports

1. INTRODUCTION

The Municipality of Anchorage (MOA), Watershed Management Section (WMS), is currently studying oil and grit separators (OGS) to determine the feasibility of using these devices for removing coarse sediments, oily sheen, and free-phase oil from storm-water discharges at municipal outfalls. The goal of the current OGS study is to extrapolate pollutant mobilization predictions to all basins in the Anchorage bowl so feasibility of this type of urban storm-water treatment can be assessed area wide (Wheaton et al 1995). MOA street sediment loading rates are basic data for OGS assessment: direct measurement of street sediment loads is necessary for predictive model development.

The Air Quality Section (AQS) of the MOA Department of Health and Human Services has indicated that street sediment loading information would also be useful to them for producing an air quality emissions inventory and identifying specific sources of air particulate in the Anchorage area. Currently, the municipality estimates road silt emissions by applying a United States Environmental Protection Agency (USEPA) estimation method and non-MOA loading rates (USEPA 1995). The method requires, as base information, surface loading on trafficked parts of paved roads. Because street sediment loading rates for cities in more moderate climates are believed to be significantly lower than for Anchorage, loading data specific to MOA are necessary for accurate emission calculations.

Because of their shared interest, WMS and AQS worked jointly to design a street sediment loads assessment project [*MOA Street Sediment Loading Assessment Design* (Wheaton et al 1997)]. Montgomery Watson implemented this assessment project in 1996.

This report contains project data and associated documentation generated for the street sediment loads assessment effort. Individual results are included with limited tabular and graphical summaries.

2. EXPLANATION OF DATA SUBMITTAL ELEMENTS

This data submittal is divided into the following elements:

- Summary information about the field phase of the project are contained in Section 3.0, including a project summary, variations from the project design, notable field observations, and a data validation summary.
- Graphical and tabular summaries of the data are presented in Section 4.0 with brief descriptions.
- References are contained in Section 5.0.
- Sample analysis results and other primary documentation are contained in Appendices A and B. All project data have been entered into a project database which accompanies this document on a CD ROM. The database is composed of related tables: a parent table containing sampling site information (ROADSITE.DBF), and two child tables containing data for individual analyses (SEDDATA.DBF and AQDATA.DBF) and a look-up table defining terms (STRATA.DBF). Hardcopy printouts of each of these tables and definitions of each field are contained in Appendix A. Additional documentation including field note forms (primary field data), and chain-of-custody documentation are compiled in Appendix B.

All tables and figures identified in the text are presented immediately after Section 5.0.

3. PROJECT SUMMARY

The following sections present a project summary, variations from the project design, and results of data validation. These sections are intended to:

- Provide context for the reported data by summarizing assumptions and methods underlying the data collection effort.
- List and explain variations from planning documents.
- Document field observations that may be helpful in understanding project data.
- Identify data that do not meet project objectives.

Detailed descriptions of the project approach and sampling methods, and other project requirements may be found in the project design document.

3.1 Project Summary

The Street Sediment Loading Assessment was initiated to answer questions posed by AQS and WMS managers about the mass, character, spatial and temporal distribution, and sources of sediment on MOA streets. These data are necessary as input for modeling of OGS and air particulate emissions, and for refinement of street sweeping practices (Wheaton et al 1997).

Winter street sanding and vehicle trackout from unpaved alleys were identified in the project design as the major contributors to street sediment build-up to be studied. Based on MOA sanding practices, 33 sampling sites were selected at 18 controlled intersections to represent four major road types (Figure 1). The road types were derived from USEPA classifications based on average daily traffic (ADT) volume: local, collector, minor arterial, and major arterial/freeway. These categories are based on ADTs of ≤2,000; 2,000 - 10,000; 10,000 - 20,000; and ≥20,000, respectively. To assess sediment trackout from unpaved alleys, five "trackout" sites were identified where unpaved alleys intersected paved streets.

Sites located at controlled intersections were divided into "intersection" and "non-intersection" areas (Figure 2). Intersection areas include all street surfaces within 100 feet (30.5 meters) of the crossing street. Non-intersection areas include all surfaces from 100 to 200 feet (61 meters) of the crossing street. Trackout sites represent street surfaces on sampled roadways within a 30 feet (9 meter) zone centered about the intersecting unpaved alley. Near each trackout site, a "non-trackout" site was selected to provide control data for assessment of trackout effects. Non-trackout site dimensions were identical to the corresponding trackout sites but were located away from areas directly impacted by trackout sediment and street sand applied to controlled intersections.

Each street area (intersection, non-intersection, trackout) was divided into pavement strata representing "gutter" and "non-gutter" areas (Figure 2). Gutters were measured two feet into the street from the back of the raised curb, including the gutters created by raised medians. Non-gutter strata include all other street surfaces, excluding the tops of raised medians.

Three transects were established each intersection, non-intersection, and trackout area (Figure 2). Transects were typically six inches wide (0.15 meters) and extended gutter-to-gutter across the street. A single gutter and non-gutter sample was composited from the three transects within each area during each sampling round.

Samples for OGS assessment were collected from all sites using a wet/dry shop vacuum with a paper filter-bag. Samples used for air particulate emission calculations were sampled from non-gutter strata only at a selected subset of sites using a high efficiency (HEPA) vacuum (Table 1). The HEPA vacuum used quartz-fiber filters rated to capture ≥99% of 0.0003 mm particles (determined by ASTM Method 2986). Collection of HEPA samples was necessary because of concerns that small particulate would pass through the wet/dry vacuum paper filter. HEPA samples serve as a basis for determining the correlation between data generated by the two sampling methods. Method correlation allows for the use of the larger wet/dry sample dataset in air quality calculations. Data correlation results are presented in Section 4.0.

Samples were collected in the early spring before street sweeping, mid to late spring immediately after street sweeping, and mid-summer (Table 1). Because determination of street sweeping efficiency is a project objective, sampling sites identified in the design document were excluded from the project if they were swept before sampling. Where possible, similar sites were substituted. The second sampling round occurred as soon as possible after street sweeping.

At the request of AQS, samples of dirt were collected from a trackout alley. Two wet/dry vacuum samples and one HEPA vacuum sample were collected from the unpaved alley adjacent to 15th east of Columbine by brushing the vacuum head lightly over the road surface. Only one transect across the entire alley was sampled.

All samples were analyzed for particle size distribution (sieve analysis) using ASTM method C136 with a wet wash (sieve sizes 38.1 mm, 19.0 mm, 9.5 mm, 4.76 mm, 2.00 mm, 0.84 mm, 0.42 mm, 0.149 mm, 0.105 mm, and 0.074 mm).. Air quality samples were split prior to analysis and the unanalyzed portion was returned to AQS for further chemical/physical testing. Sediment loadings were calculated from transect area and sieve analysis data for the following sediment size classes:

- Total sediment load;
- OGS treatable load (≥0.10 mm);
- OGS non-treatable load (<0.10 mm); and
- Air-suspendable load (≤0.075 mm).

As noted above, hardcopy sieve analysis results are presented in Appendix A, with a digital copy of the data contained in the attached CD ROM. Data for samples collected using the HEPA vacuum are listed in the AQDATA database. Wet/dry vacuum collected samples are contained in the SEDDATA database. Site survey sketches for each sampling site and field notes for each sampling episode are contained in Appendix B. These field data are summarized in the ROADSITE database.

Data for the three alley dirt samples are presented as hard copy sieve analysis plots only (Appendix A).

3.2 VARIATIONS FROM DESIGN

Due to unforeseen circumstances, several aspects of the original project design were changed to meet field conditions. These variations include changes in where (spatial network), when (temporal network), and how (sampling procedures) samples were collected. The following sections itemize these changes.

3.2.1 Spatial Network Variations

Originally, 62 sites were selected for sample collection. Adjacent to 13 of these sites, trackout areas were selected for measurement of sediments transported to paved roads from adjacent unpaved alleys.

During the first sampling round, ice and water at many of the sampling sites prevented routine sample collection, increasing the time required at each site. In contrast, streets were rapidly swept by MOA street maintenance crews without regard to snow and ice. As a result, many of the sites originally identified in the design document were swept before sampling. Because pre-street sweeping data is critical to project objectives, those streets that were swept prior to sampling were eliminated from the assessment project. Where possible, similar unswept streets were substituted.

In all, 33 sites were selected (not including 36th east of New Seward which was inadvertently sampled). Five of the selected sites contain trackout areas (Table 1).

3.2.2 Temporal Network Variations

Five sampling periods were selected in the project design to measure end-of-winter sediment loads, street sweeping effects, summer sediment build-up rates, and periods of historically high air suspended particulate (Wheaton et al 1997):

- Pre-street sweeping (March 30 - April 10);
- Post-street sweeping (April 10 - early May);
- Early summer (late May to late June);
- Mid-summer (starting August 1); and
- Freeze-up (mid-October).

Due to budget limitations, the early summer round was eliminated. Because of early season snowfall, the mid-October sampling round was canceled.

Because of the project requirement for repeated sampling at established locations, only those sites sampled in round one were considered for sampling during subsequent rounds. The following bullets summarize exceptions to this requirement:

- In an effort to maximize the amount of data collected, ten sites were added during the third sampling round. Due to budget constraints, only gutters were sampled. These sites are identified in the NOTES field of the ROADSITE database.
- Because the adjacent unpaved alleys were frozen and therefore not contributing sediment to the street, trackout sites were not sampled during round one. Sampling at these sites occurred only during the third sampling round.
- At the following three sites, samples were not collected during all rounds:
  - King St. at Dimond Blvd. was not sampled during round one because of snow and ice cover.
  - 21st. Ave. and Blueberry was swept ahead of schedule, prior to the planned pre-sweep sampling date. The site was sampled during subsequent sampling rounds because it is part of a larger MOA sediment washoff data collection project requiring street sediment load data.
  - Northern Lights at Spenard was not sampled during round two. Because project objectives required sampling as soon as possible after street sweeping, field crews postponed sampling in anticipation that the site would be swept some time during the round two time frame. However, the second street sweeping event did not occur until the round three time frame.
  - 36th west of New Seward was not sampled during round one due to time constraints.

3.2.3 Sampling Procedure Variations

During round one, significant standing water and mud were encountered at 16 gutter sampling locations (eight sites). At sites with standing water, a square end shovel was used to scoop the sample into plastic garbage bags. Similarly, sites with dense mud were sampled with a broom and shovel. These alternate collection methods were used because paper filters were used in the wet/dry vacuum to trap the sample, and because the vacuum strength was not sufficient to effectively remove wet, sticky sediment from the road surface. Samples collected using these methods are identified in the “Notes” field of the project database. A list of the affected samples and the implications of these variant sampling methods are presented in Section 3.4.

3.3 Notable Field Observations

During sample collection, field crews observed several phenomena that influenced sediment distributions on the street surface. These observations are described below:

- Street sediment tends to concentrate in less traveled areas of the street. This process results in higher sediment loads in gutters, medians, and between lanes than in regions of the street that are directly traveled (Figure 3, Photo1). Sediment load stratification was noted in street gutters during all sampling rounds, but was present on the trafficking surface primarily during round one.

- During street sweeping, municipal crews were required to sweep around parked cars, resulting in incomplete removal of street sediment in or near the gutter (Figure 3, Photo 2). Parked cars were most common in residential areas.
- An evenly distributed layer of fine sediment was noticeable on the trafficking surface after street sweeping and periods of moderate to strong wind. The sediment layer remaining after street sweeping tended to be most evident within approximately five to eight feet of the gutter (Figure 3, Photo 3). Wind transported particles formed an even layer over all surfaces (Figure 3, Photo 4).

3.4 Data Validation

Project data were validated to ensure consistency with the type, quality, and quantity of information identified in planning documents. Methods for validation include on-site inspections of field procedures and a comprehensive review of field and sieve analysis data.

3.4.1 On-site Inspections

Two on-site inspections were conducted by the project scientist on 3/21/96 (at Old Seward and 36th) and 4/16/96 (at 36th and New Seward) to assess compliance with approved sampling and documentation procedures. In both cases, simple observation of sampling techniques and documentation practices was used to verify compliance. Additionally, periodic spot checks of field data were performed as an on-going documentation check.

With the exception of the modified sampling procedures noted above and environmental complications encountered during round one (described below), no anomalies were either observed during the on-site audits or noted from field data reviews.

Standing water and ice were encountered at 16 gutter sampling locations during round one. Because normal sampling methods were not suitable for these conditions, sediment was collected using a shovel or broom and shovel. Some particle size data from these 16 samples are assumed to be biased low. This conclusion is based on the observation that a portion of the finer sediment remains in standing water or stuck to the asphalt after sampling with a shovel or broom. Although data collected from these sites is probably biased low, the effect of this bias on summary statistics and conclusions derived from the whole data set is believed to be negligible. Similarly, field observations suggest that a majority of the sample was collected, and the larger particle sizes may have been almost entirely recovered. Consequently, these results have been qualified, but not removed from the database. Samples collected using the modified sampling procedures are listed below and identified in the “Notes” field of the SEDDATA database.

Site	Road Type	Pavement Strata	Sample Date	Collection Method
13th east of Karluk	Local	IG, NIG	4/5/96	Shovel
15th east of Columbine	Local	IG, NIG	4/10/96	Shovel
16th east of Columbine	Local	IG, NIG	4/2/96	Shovel
9th east of Karluk	Collector	IG, NIG	4/5/96	Broom
Columbine north of 16th	Local	IG, NIG	4/2/96	Shovel
Columbine south of 15th	Local	IG, NIG	4/10/96	Broom
Karluk north of 13th	Collector	IG, NIG	4/5/96	Shovel
Karluk north of 9th	Collector	IG, NIG	4/5/96	Broom

IG - Intersection Gutter

NIG - Non-intersection Gutter

During sampling round one, gutter ice, damp street surfaces, and large sediment loads complicated sample collection. These complications included difficulty in chipping ice away from the sampling transects, recovering light to moderately wet sediment from the pavement surface, and overloading of the HEPA vacuum. Although these conditions were widely encountered, they generally did not preclude reasonable sample collection. However, when compared to the two subsequent sampling rounds, data from round one exhibits both increased variability and lower correlation between co-collected HEPA and wet/dry vacuum sample data. These data effects (described more fully in Section 4.0) are believed to be due largely to the environmental conditions encountered in round one. Because these conditions are inherent to sampling street sediment loads in the early spring, the data are considered less comparable than rounds two and three, but still valid.

3.4.2 Review of Field and Sieve Analysis Data

A comprehensive field data review was performed at the end of each sampling round by field crews. These reviews included verification of field notes and the accuracy of data transcription to the project database. At the conclusion of the field phase, the transfer of field data to the database was independently validated by an engineer not previously involved in the project.

Primary review of digital sieve analysis data was performed by the geotechnical laboratory, Rodney P. Kinney and Associates (RPKA) of Eagle River, Alaska. Although hardcopy sieve plots were provided by RPKA for some round one data, most data were requested and provided only in digital form. To validate the sieve data, sieve plots were created for those results transmitted only in digital form, and then all plots were reviewed to verify that the data were reasonable.

The possibility of erroneous data was also investigated by a review of field notes, site photos, and graphical displays of the data. Although some data points are outlyers (they do not fit the overall distribution of the data), none have been determined to be erroneous. It is important to note that the statistical tools used to summarize the data are non-parametric (e.g., medians), and therefore robust against the disproportionate influence of outlyers. Consequently, outlyers were not excluded from the dataset.

While coordinating sample collection dates and locations with DPW street maintenance, MOA street sweeping records were obtained and archived for future use in determining the elapsed time between street sweeping and sampling. Upon entering these data into the project database, it became apparent that the records were incomplete for some sampling locations. To fill these data gaps, missing street sweeping dates were estimated by Montgomery Watson based on best professional judgment. These estimated dates are qualified in the ROADSITE database with an "E" qualifier.

During review of the sieve analysis plots, it was noted that results were not received for the non-intersection, non-gutter sample collected 3/21/96 from 36th Ave. west of Old Seward (Sample 36NING032196). Conversations with the project laboratory indicated that the sample was lost during analysis. Data for all other requested sample analyses were received.

4. PROJECT DATA SUMMARY

Project data have been graphically and tabularly summarized to provide basic interpretive information about the sediment loads present on MOA streets during the spring and summer of 1996. Further data analysis is beyond the scope of this data report. The following sections describe basic sediment characteristics and their changes over time and space during the sample collection period. Referenced tables and graphs follow Section 5.0, References.

4.1 HEPA and Wet/Dry Vacuum Data Correlation

As noted in Section 3.0, the efficiency of air suspendable sediment recovery by the wet/dry vacuum was not known prior to the street sediment loads field effort. In the anticipation that data from the less expensive wet/dry vacuum sample collection may be used for air pollution modeling, samples were collected using both HEPA and wet/dry vacuums from side-by-side transect at approximately 25% of the sites to provide the basis for determining a method correlation. The correlation between the HEPA and wet/dry vacuums is graphically presented in Figure 4 for both total sediment and the air suspendable fraction (≤0.075 mm) of the sample. Table 2 presents the data used to determine the correlation, segregated by sampling round, and the resultant least squares regression curve fit.

Correlation analysis indicates that the HEPA vacuum was generally less efficient in collecting the air suspendable fraction (ASF) than the wet/dry vacuum, as shown by slopes of less than 1 (Table 2). With the exception of the ASF collected during round one, the correlation coefficients for all comparisons indicate a highly linear relationship ($r \geq 0.90$) between the HEPA and conventionally collected samples (Table 2). This linear relationship coupled with the correlation data suggest that the HEPA data may used with other project data to assess street sediment loads after adjustment to account for the lower collection efficiency.

4.2 Data Trends

This section presents data trend summaries for total and air-suspendable sediment collected by the wet/dry vacuum. Total loads are presented for entire road surface (gutter and non-gutter areas). Air suspendable loads are presented for only the trafficking surface because sediment in the gutter is considered by USEPA protocols to be unavailable for air suspension. Graphical and tabular summaries are shown for changes in sediment loads by sampling round (temporal change), road type and trackout area (spatial change), and street surface (spatial change).

<u>Total Sediment Load (Table 3)</u>

For total particulate unit loads decrease from sampling round one to three for all road types. Results also suggest that unit loads increase with increasing ADT for round one; however, this trend is not present for rounds two and three.

Trackout data suggest a significant increase in sediment contribution from unpaved alleys (99.6 g/m^2) when compared to non-trackout areas (27.5 g/m^2).

Intersection areas appear to have higher unit loads (418.7 g/m^2) than non-intersection areas (310.9 g/m^2) for round one data. This trend does not hold for rounds two and three.

Air-suspendable Load (Table 3)

Air-suspendable load differences between rounds one and two are relatively small for local streets (18.4 g/m^2 vs. 15.3 g/m^2) and collectors (9.4 g/m^2 v.s. 10.7 g/m^2). Differences between rounds one and two are more pronounced for high ADT streets (6.7 g/m^2 v.s. 1.3 g/m^2 for minor arterials and 20.4 g/m^2 v.s. 3.7 g/m^2 for major arterials). Round three loads are lower than round two for all road types. Trackout areas contained a higher air-suspendable load (6.9 g/m^2) than non-trackout areas (3.1 g/m^2).

Intersection areas (13.8 g/m^2) appear to have higher air-suspendable unit loads than non-intersection areas (4.7 g/m^2) for round one data. No clear trend emerges, however, for rounds two and three.

4.3 Data Summaries By Particle Size Classification

Tables 5 through 10 present median unit sediment loads by round and road type for all pavement strata (gutter and non-gutter areas), street surfaces (intersection and non-intersection areas), and track out areas. These data are presented in separate tables for each of the different particle size classes that have been identified as critical to the OGS assessment project and AQS: total (all particle sizes); air suspendable (≤0.074 mm); OGS treatable (≥0.10 mm); and OGS non-treatable (≤0.10 mm). Data from HEPA and wet/dry vacuum collected samples are segregated.

To provide a measure of variability and statistical reliability, the upper and lower quartiles, and number of data points used to determine each median are also listed.

Note that during sample analysis, a portion of the total sample was typically entrained in the wet/dry vacuum filter bag. This fraction was assumed to be ≤0.074 mm and was included in air-suspendable, total sediment, and OGS-nontreatable load calculations.

5. REFERENCES

Wheaton, Scott R., Chris Brown, and Bill Spencer. 1995. *Design for Assessment of Oil and Grit Separators* (Final Draft). Prepared by Montgomery Watson. WMS Document Number APd95001. July. Amended January 1997.

Wheaton, Scott R., Chris Brown, and Eric Gropp. 1997. *MOA Street Sediment Loading Assessment Design* (Draft). Prepared by Montgomery Watson. WMS Document Number APd96001. January.

U.S. Environmental Protection Agency. 1995. *Compilation of Air Pollution Emissions Factors*, USEPA Report AP-42, Office of Air Quality Planning and Standards, Washington, D.C.

6. LIST OF PREPARERS

Prepared by:	Chris Brown, Chemist Montgomery Watson (907) 266-1134
	Eric Gropp, Civil Engineer Montgomery Watson (907) 266-1136
Reviewed by:	Scott R Wheaton, Watershed Scientist Watershed Management Section (907) 343-8117
	Brett Jokela, Principal Engineer Montgomery Watson (907) 266-1112

DATE: 2-13-97



MONTGOMERY WATSON
Anchorage, Alaska

FIGURE 1

MOA DEPARTMENT OF PUBLIC WORKS
STREET SEDIMENT LOADING ASSESSMENT
(DOCUMENT WMP APr97001)

SAMPLING SITE LOCATIONS



MONTGOMERY WATSON
Anchorage, Alaska

FIGURE 2
MOA DEPARTMENT OF PUBLIC WORKS
STREET SEDIMENT LOADING ASSESSMENT
(DOCUMENT WMP APr97001)

SAMPLING SITE DIAGRAM

Photo 1 - 36th and Old Seward, 3/21/96.
Note sediment concentrated in gutter, median, and between lanes.



Photo 2 - 16th and Columbine, 4/23/96. Note unswept area due to parked cars.



Photo 3 - 9th Ave., 4/18/96.
Note sampling transect visible in street sweeping residue.

Photo 4 - Columbine and 15th, 4/25/96.
Note sampling transect visible due to fine layer of wind blown dust.

MONTGOMERY WATSON
Anchorage, Alaska

FIGURE 3

MOA Department of Public Works
Street Sediment Loading Assessment
(Document WMP APr97001)

Field Observations

Figure 4: Correlation Analysis Between Results from Wet/Dry Vacuum and HEPA Vacuum





Table 1: Sampling Site Locations and Dates

Sampling Site Location	Road Type	Sample Collection Dates (1996) Round 1	Round 2	Round 3	Comments
12th east of N Street	Local	3/26	4/26	7/8	
13th east of Karluck	Local	4/5	4/24	7/9	08/08/1996 Trackout sampling.
15th east of Columbine	Local	**4/10**	**4/25**	**8/6**	08/06/1996 Trackout sampling.
16th east of Columbine	Local	4/2	**4/23**	8/6	08/06/1996 Trackout sampling.
21st and Blueberry	Local		5/22	8/12	Not sampled during round 1.
Columbine north of 16th	Local	4/2	**4/23**	8/6	
Columbine south of 15th	Local	**4/10**	**4/25**	**8/6**	
Iowa north of Spenard	Local			7/24	Only gutters sampled.
N st. south of 12th	Local	3/26	4/26	7/8	
20th west of Lake Otis	Collector			8/7	Only gutters sampled.
9th east of Karluck	Collector	4/5	4/18	8/8	
Denali south of Northern Lights	Collector			7/26	Only gutters sampled.
E street north of 15th	Collector	3/27	4/25	8/7	
Karluck north of 13th	Collector	4/5	4/24	7/9	
Karluck north of 9th	Collector	4/5	4/18	8/8	08/08/1996 Trackout sampling.
King north of Dimond	Collector		**4/25**	7/16	Not sampled during round 1.
Reeve north of 5th	Collector	**3/27**	4/19	7/17	
15th east of E Street	Minor Arterial	3/27	4/25	8/7	
36th east of Old Seward	Minor Arterial		4/24		Sampled by mistake.
36th west of New Seward	Minor Arterial		4/16	7/16	Assume site swept three times.
36th west of Old Seward	Minor Arterial	**3/21**	**4/24**	**7/17**	Round 2 HEPA sampling on 04/25/96.
Old Seward south of 36th	Minor Arterial	**3/21**	**4/24**	**7/17**	Round 2 HEPA sampling on 04/25/96.
Old Seward south of Dowling	Minor Arterial	**4/16**	**5/30**	**7/17**	
Spenard east of Iowa	Minor Arterial			7/24	Only gutters sampled.
5th east of Reeve	Major Arterial	**3/27**	4/19	7/17	
6th west of A	Major Arterial			7/24	Only gutters sampled.
A street south of 6th	Major Arterial			**7/26**	Only gutters sampled. 07/26/96 Trackout sampling.
Debarr west of Muldoon	Major Arterial			7/24	Only gutters sampled.
Dimond west of King	Major Arterial	3/22	**4/19**	7/16	
Lake Otis north of 20th	Major Arterial			8/7	Only gutters sampled.
Muldoon south of Debarr	Major Arterial			7/24	Only gutters sampled.
New Seward north of 36th	Major Arterial	3/20	4/16	7/16	
Northern Lights east of Denali	Major Arterial			7/26	Only gutters sampled.
Northern Lights east of Spenard	Major Arterial	**3/22**		**7/26**	Not sampled during round 2.

Note: Bolded dates indicate HEPA sampling in the trafficking areas coincidental with wet/dry sample collection.

Table 2: Correlation Analysis Between Results from Wet/Dry Vacuum and HEPA Vacuum

Values are g/m^2

Round 1				Round 2				Round 3			
Total		Air Suspendable		Total		Air Suspendable		Total		Air Suspendable	
Wet/Dry Vac	HEPA	Wet/Dry Vac	HEPA	Wet/Dry Vac	HEPA	Wet/Dry Vac	HEPA	Wet/Dry Vac	HEPA	Wet/Dry Vac	HEPA
6.7	6.7	0.9	0.5	2.2	1.9	0.5	0.5	0.8	1.4	0.1	0.5
15.3	7.4	1.4	0.4	3.6	3.6	0.6	1.0	2.2	1.3	0.3	0.7
53.8	48.9	2.9	2.9	9.6	5.8	1.2	1.4	2.9	2.7	0.6	0.5
77.3	91.1	2.9	5.5	11.5	12.8	1.5	1.7	3.7	3.0	0.7	0.7
85.8	50.6	3.6	7.8	16.3	19.6	3.1	2.6	5.9	4.7	1.0	0.8
86.8	10.2	8.5	9.7	17.8	11.9	4.3	2.4	7.6	4.9	1.1	0.9
104.4	47.0	8.8	1.0	18.0	14.0	4.8	5.7	10.5	9.7	1.9	1.0
109.9	76.6	9.5	4.5	21.4	13.8	5.7	4.4	12.1	9.3	2.8	1.8
110.2	71.6	10.2	8.9	24.0	23.6	7.6	1.1	14.5	11.1	2.9	3.4
111.4	95.8	10.9	12.4	27.6	31.6	8.0	11.6	15.4	13.6	3.0	1.3
131.1	88.0	10.9	11.2	49.0	42.3	10.8	6.7	16.1	6.3	3.0	3.1
140.7	83.4	13.4	6.5	62.6	50.4	12.9	19.2	18.2	12.1	4.2	4.4
190.9	131.5	15.7	9.8	63.5	43.0	16.3	13.1	18.6	10.5	4.2	3.3
209.9	109.9	16.3	6.6	77.5	74.8	20.2	18.4	23.5	19.6	4.5	5.0
270.1	171.0	23.5	15.0	87.8	134.8	29.5	18.4	30.8	9.5	6.9	4.8
363.2	200.9	36.5	15.3	88.2	64.9	30.9	22.9	77.3	36.9	13.4	8.4
				89.6	86.8	33.0	24.8				
				117.0	130.7	34.2	35.7				
Slope	0.558	Slope	0.396	Slope	1.069	Slope	0.811	Slope	0.449	Slope	0.637
Y-Int	8.490	Y-Int	3.048	Y-Int	-4.190	Y-Int	0.504	Y-Int	2.495	Y-Int	0.532
r^2	0.870	r^2	0.571	r^2	0.875	r^2	0.870	r^2	0.875	r^2	0.890
Correl. Coeff.	0.933	Correl. Coeff.	0.756	Correl. Coeff.	0.936	Correl. Coeff.	0.933	Correl. Coeff.	0.935	Correl. Coeff.	0.943

All Rounds		
	Total	Air Suspendable
Slope	0.608	0.691
Y-Int	6.378	0.778
r^2	0.850	0.792
Correl. Coeff.	0.922	0.890

Table 3: Total Sediment Unit Loads Summary (Median Values)

Values are in g/m²

Road Type	Sampling Round 1	2	3	TO	All Roads
1	262.7 (7)	111.8 (8)	61.6 (8)		115.9 (23)
2	387.9 (5)	136.4 (6)	46.0 (6)		175.7 (17)
3	515.1 (4)	86.7 (6)	74.4 (5)		136.5 (15)
4	814.3 (4)	115.9 (3)	104.4 (5)		162.3 (12)
Track Out				99.6 (5)	99.6 (5)
Non Track Out				27.5 (5)	27.5 (5)
All Rounds	431.1 (20)	109.5 (23)	65.2 (24)		136.5 (67)



Summary Table (All Street Areas and Street Surfaces)

Sampling Round	Inter-section	Non-Inters.	TO	All Roads
1	418.7 (20)	310.9 (18)		431.1 (20)
2	106.7 (23)	131.5 (23)		109.5 (23)
3	65.2 (23)	68.6 (23)		65.2 (24)
Track Out			99.6 (5)	99.6 (5)
Non Track Out			27.5 (5)	27.5 (5)
All Rounds	128.3 (66)	132.6 (64)		136.5 (67)

Note:

Road Types:

1 Local
2 Collector
3 Minor Aterial
4 Major Arterial
TO Track Out / Non-track Out

Numbers in parentheses are the number of data points used to calculate the median values
Track out and non-track out data are not included in the median values summarizing all road types and rounds.

Table 4: Air Suspendable Sediment (<74μm) Unit Loads Summary (Median Values)

Values are in g/m²

Summary Table (Trafficked Areas Only)

Road Type	Sampling Round 1	2	3	TO	All Roads
1	18.4 (7)	15.3 (8)	4.7 (8)		10.5 (23)
2	9.4 (5)	10.7 (6)	2.9 (6)		6.9 (17)
3	6.7 (4)	1.3 (6)	1.1 (5)		1.5 (15)
4	20.4 (4)	3.7 (3)	2.6 (5)		4.7 (12)
Track Out				6.9 (5)	6.9 (5)
Non Track Out				3.1 (5)	3.1 (5)
All Rounds	10.1 (20)	7.0 (23)	3.4 (24)		5.7 (67)



Summary Table (Trafficked Areas Only)

Sampling Round	Inter-section	Non-Inters.	TO	All Roads
1	13.8 (20)	4.7 (18)		10.1 (20)
2	7.6 (23)	7.3 (23)		7.0 (23)
3	2.8 (23)	3.0 (23)		3.4 (24)
Track Out			6.9 (5)	6.9 (5)
Non Track Out			3.1 (5)	3.1 (5)
All Rounds	7.3 (66)	4.4 (64)		5.7 (67)

Note:

<u>Road Types:</u>
1 Local
2 Collector
3 Minor Aterial
4 Major Arterial
TO Track Out / Non-track out

Numbers in parentheses are the number of data points used to calculate the median values
Track out and non-track out data are not included in the median values summarizing all road types and rounds.

Table 5: Summary of Sediment Unit Loads by Particle Size Classification, All Particle Sizes

(Wet/Dry Vacuum Samples)

(grams per square meter)
Lower Quartile / Median / Upper Quartile (Number of Data Points)

Road Type	Round	All Areas Gutter Only	All Areas Traffic Surface	All Areas Gutters and Traffic Surface	Intersection Traffic Surface	Intersection Gutters and Traffic Surface	Non Intersection Traffic Surface	Non Intersection Gutters and Traffic Surface
1	1	883.9 1161.3 1630.9 (7)	140.7 190.2 211.0 (7)	252.6 262.7 470.7 (7)	169.6 253.9 316.7 (7)	261.5 314.4 544.1 (7)	98.0 137.0 150.8 (7)	220.4 256.4 355.6 (7)
1	2	252.2 528.9 596.7 (8)	39.1 57.4 71.6 (8)	84.5 111.8 159.2 (8)	38.0 54.1 83.5 (8)	70.3 113.1 151.3 (8)	38.3 58.0 61.2 (8)	78.7 120.7 177.6 (8)
1	3	288.1 365.3 442.2 (9)	19.3 26.7 37.8 (8)	54.8 61.6 74.6 (8)	12.9 21.1 32.3 (8)	30.7 40.8 78.8 (8)	18.2 29.6 38.1 (8)	56.6 68.6 79.9 (8)
2	1	1699.8 1932.1 2141.7 (5)	133.2 164.3 255.1 (5)	231.4 387.9 435.5 (5)	209.9 250.2 366.5 (5)	296.3 483.5 544.6 (5)	53.8 75.0 115.1 (5)	179.4 288.9 322.4 (5)
2	2	360.8 967.3 1870.1 (6)	24.7 67.5 98.7 (6)	48.9 136.4 308.8 (6)	23.0 44.5 87.8 (6)	50.5 142.4 214.7 (6)	26.5 43.0 117.0 (6)	48.9 126.6 418.5 (6)
2	3	199.3 616.8 1395.0 (8)	4.1 17.7 29.9 (6)	26.4 46.0 126.4 (6)	3.9 14.5 26.8 (6)	16.6 53.6 87.3 (6)	4.4 13.9 29.2 (6)	11.7 44.2 146.0 (6)
3	1	2583.8 2823.2 7713.1 (4)	47.6 65.9 106.4 (4)	361.5 515.1 758.4 (4)	68.1 94.4 121.2 (4)	262.4 336.8 741.9 (4)	22.5 29.7 58.3 (3)	452.7 647.7 1977.8 (4)
3	2	563.3 941.2 1431.4 (6)	6.8 8.4 18.5 (6)	66.9 86.7 136.8 (6)	9.6 11.7 17.4 (6)	62.7 64.4 128.3 (6)	2.2 5.3 10.4 (6)	70.7 106.1 145.4 (6)
3	3	205.4 662.4 1654.0 (6)	2.4 4.5 23.1 (5)	39.9 74.4 136.5 (5)	2.2 5.9 16.1 (5)	34.5 74.3 162.1 (5)	2.6 2.9 3.8 (5)	46.1 74.5 87.7 (5)
4	1	3315.9 4680.8 8066.7 (4)	94.7 303.6 722.9 (4)	333.0 814.3 1242.4 (4)	147.6 322.9 722.9 (4)	376.5 826.7 1242.4 (4)	6.7 58.3 109.9 (2)	176.3 305.2 434.1 (2)
4	2	1114.5 1181.0 1256.5 (3)	30.1 42.2 144.1 (3)	112.7 115.9 248.2 (3)	30.3 42.5 202.0 (3)	99.7 109.4 340.8 (3)	29.8 41.8 93.5 (3)	127.2 131.5 170.3 (3)
4	3	266.2 409.5 779.3 (10)	14.5 14.5 15.7 (5)	68.5 104.4 120.0 (5)	10.4 14.1 41.0 (4)	80.5 87.8 276.5 (5)	9.8 16.2 38.9 (4)	58.4 103.8 131.3 (5)

Area	Traffic Surface	Gutters and Traffic Surface
Non Trackout	10.4 12.3 14.5 (5)	25.5 27.5 31.2 (5)
Trackout	18.6 21.1 57.9 (5)	90.2 99.6 166.2 (5)

Notes: "All Areas" group includes trackout and non trackout area data
Road Type 1: Local — Road Type 3: Minor Arterial
Road Type 2: Collector — Road Type 4: Major Arterial / Freeway

Table 6: Summary of Sediment Unit Loads by Particle Size Classification, Air Suspendable Particles (<0.074 mm)

(Wet/Dry Vacuum Samples)

(grams per square meter)
Lower Quartile / Median / Upper Quartile (Number of Data Points)

Road Type	Round	All Areas Gutter Only	All Areas Traffic Surface	All Areas Gutters and Traffic Surface	Intersection Traffic Surface	Intersection Gutters and Traffic Surface	Non Intersection Traffic Surface	Non Intersection Gutters and Traffic Surface
1	1	105.7 150.1 239.8 (7)	10.7 18.4 24.3 (7)	27.0 37.1 57.8 (7)	12.7 18.7 30.0 (7)	25.4 40.4 66.6 (7)	8.8 13.4 21.1 (7)	27.0 37.2 48.8 (7)
1	2	108.9 144.7 199.7 (8)	8.8 15.3 26.1 (8)	27.7 31.3 56.8 (8)	7.7 14.7 28.3 (8)	23.0 32.1 54.0 (8)	9.7 15.8 24.2 (8)	27.7 35.6 59.5 (8)
1	3	74.9 84.8 105.8 (9)	3.5 4.7 8.8 (8)	13.2 14.9 18.5 (8)	2.8 3.4 9.4 (8)	7.2 11.1 15.9 (8)	4.2 4.9 6.1 (8)	13.1 17.2 23.7 (8)
2	1	125.0 196.3 202.2 (5)	8.1 9.4 17.3 (5)	23.1 29.3 31.6 (5)	11.9 15.7 24.9 (5)	21.6 25.4 35.5 (5)	2.9 4.0 9.0 (5)	24.9 27.7 37.4 (5)
2	2	95.9 177.9 265.3 (6)	6.0 10.7 14.1 (6)	13.6 26.9 40.2 (6)	7.0 8.8 14.4 (6)	16.3 28.0 34.8 (6)	4.1 8.9 12.9 (6)	10.9 24.1 50.0 (6)
2	3	41.7 128.2 207.0 (8)	1.4 2.9 4.9 (6)	3.4 9.1 20.6 (6)	1.4 2.8 5.9 (6)	4.0 8.3 14.4 (6)	0.9 2.3 6.2 (6)	2.2 10.8 30.5 (6)
3	1	378.3 412.7 936.8 (4)	2.7 6.7 9.8 (4)	47.0 71.0 95.1 (4)	4.6 9.7 10.9 (4)	34.0 47.8 88.9 (4)	0.9 1.4 5.1 (3)	58.0 78.9 270.0 (4)
3	2	97.1 128.9 197.2 (6)	0.9 1.3 3.2 (6)	11.2 14.3 18.3 (6)	1.2 1.5 3.7 (6)	8.8 12.3 15.6 (6)	0.5 0.8 1.5 (6)	10.4 17.4 22.7 (6)
3	3	37.1 107.5 205.4 (6)	0.5 1.1 2.4 (5)	6.6 12.5 20.8 (5)	0.6 1.1 1.9 (5)	5.8 11.6 19.2 (5)	0.8 1.0 1.0 (5)	7.5 13.4 13.6 (5)
4	1	407.5 473.0 917.0 (4)	5.3 20.4 49.1 (4)	29.0 62.6 119.0 (4)	9.8 21.9 49.1 (4)	23.7 61.7 119.0 (4)	0.9 2.3 3.6 (2)	29.1 32.0 34.9 (2)
4	2	182.9 195.3 259.3 (3)	3.6 3.7 30.3 (3)	15.9 18.7 60.2 (3)	3.2 3.3 36.0 (3)	13.7 15.3 74.8 (3)	4.1 4.3 25.5 (3)	18.5 22.6 47.4 (3)
4	3	63.5 72.6 132.0 (10)	1.9 2.6 5.7 (5)	6.3 19.2 30.3 (5)	1.2 2.1 7.0 (4)	9.1 11.0 72.5 (5)	1.2 2.4 8.3 (4)	6.3 28.4 39.1 (5)

Area	Traffic Surface	Gutters and Traffic Surface
Non Trackout	3.0 3.1 4.5 (5)	7.4 7.9 9.2 (5)
Trackout	4.0 6.9 12.4 (5)	22.5 26.3 36.5 (5)

Notes: "All Areas" group includes trackout and non trackout area data
Road Type 1: Local — Road Type 3: Minor Arterial
Road Type 2: Collector — Road Type 4: Major Arterial / Freeway

Table 7: Summary of Sediment Unit Loads by Particle Size Classification, OGS Treatable Particles (> 0.10 mm)

(Wet/Dry Vacuum Samples)

(grams per square meter)
Lower Quartile / Median / Upper Quartile (Number of Data Points)

Road Type	Round	All Areas Gutter Only	All Areas Traffic Surface	All Areas Gutters and Traffic Surface	Intersection Traffic Surface	Intersection Gutters and Traffic Surface	Non Intersection Traffic Surface	Non Intersection Gutters and Traffic Surface
1	1	774.6 940.9 1253.0 (7)	124.2 171.4 194.4 (7)	212.3 244.0 383.0 (7)	155.7 246.4 286.3 (7)	231.1 296.7 462.0 (7)	83.5 121.4 133.4 (7)	191.9 214.4 300.4 (7)
1	2	138.2 324.4 389.4 (8)	25.2 36.8 46.5 (8)	50.7 77.9 92.5 (8)	28.4 32.0 52.2 (8)	48.6 68.1 95.8 (8)	24.2 34.8 41.8 (8)	44.8 80.5 107.8 (8)
1	3	183.1 279.1 345.2 (9)	13.1 21.8 29.2 (8)	37.1 42.2 59.7 (8)	9.5 14.0 24.4 (8)	21.1 27.8 60.1 (8)	13.1 20.6 31.3 (8)	35.3 41.6 63.7 (8)
2	1	1540.8 1714.8 1907.2 (5)	121.8 154.5 234.4 (5)	206.5 352.7 397.8 (5)	191.0 235.6 337.6 (5)	267.2 456.4 502.5 (5)	50.3 70.2 104.8 (5)	153.1 245.3 289.2 (5)
2	2	244.7 729.8 1523.3 (6)	17.3 48.1 79.7 (6)	32.2 101.8 256.1 (6)	14.6 29.6 76.5 (6)	30.6 105.5 168.1 (6)	20.1 32.2 100.5 (6)	34.9 95.6 317.8 (6)
2	3	149.2 449.2 1096.7 (8)	3.2 13.5 21.3 (6)	18.0 36.8 89.0 (6)	2.9 11.3 18.9 (6)	11.7 42.5 68.1 (6)	3.5 11.2 21.4 (6)	9.2 31.5 105.1 (6)
3	1	2168.0 2352.8 6604.2 (4)	44.2 57.8 94.0 (4)	308.6 433.3 646.7 (4)	62.5 82.3 107.2 (4)	224.8 283.3 625.7 (4)	21.3 29.1 52.4 (3)	386.3 559.5 1670.7 (4)
3	2	362.4 732.7 1272.9 (6)	5.5 6.9 12.5 (6)	45.5 67.7 107.9 (6)	7.8 9.9 13.0 (6)	44.8 50.5 102.2 (6)	1.9 4.1 9.3 (6)	46.3 83.2 121.7 (6)
3	3	170.1 522.3 1200.4 (6)	1.8 3.3 20.3 (5)	31.4 58.3 102.6 (5)	1.9 4.6 13.9 (5)	27.0 59.0 134.7 (5)	1.6 1.9 2.7 (5)	36.4 57.6 70.4 (5)
4	1	2807.7 4099.5 7012.8 (4)	87.6 277.6 660.1 (4)	296.6 734.3 1099.5 (4)	134.8 295.0 660.1 (4)	346.2 748.0 1099.5 (4)	5.6 55.0 104.3 (2)	141.9 265.4 388.8 (2)
4	2	792.5 908.2 997.5 (3)	25.4 37.1 109.7 (3)	90.6 97.1 181.1 (3)	26.2 37.9 159.9 (3)	81.0 92.3 253.2 (3)	24.5 36.2 65.7 (3)	101.2 102.3 117.2 (3)
4	3	181.8 254.3 672.5 (10)	7.7 12.1 12.6 (5)	59.2 82.1 83.8 (5)	8.9 11.6 31.3 (4)	64.4 74.7 179.3 (5)	8.3 13.3 29.5 (4)	51.3 56.0 102.0 (5)

Area	Traffic Surface	Gutters and Traffic Surface
Non Trackout	7.8 8.8 10.9 (5)	12.0 16.7 21.0 (5)
Trackout	10.2 16.6 43.8 (5)	59.9 73.6 122.3 (5)

Notes: "All Areas" group includes trackout and non trackout area data
Road Type 1: Local   Road Type 3: Minor Arterial
Road Type 2: Collector   Road Type 4: Major Arterial / Freeway

Document Number WMP APr97001

12 February 1997

Table 8: Summary of Sediment Unit Loads by Particle Size Classification, Non-OGS Treatable Particles (< 0.10mm)

(Wet/Dry Vacuum Samples)

(grams per square meter)

Lower Quartile / Median / Upper Quartile (Number of Data Points)

Road Type	Round	All Areas Gutter Only	All Areas Traffic Surface	All Areas Gutters and Traffic Surface	Intersection Traffic Surface	Intersection Gutters and Traffic Surface	Non Intersection Traffic Surface	Non Intersection Gutters and Traffic Surface
1	1	114.0 162.1 248.7 (7)	12.2 18.8 26.6 (7)	30.0 40.5 61.2 (7)	13.8 20.9 31.1 (7)	28.1 43.7 70.9 (7)	9.7 15.6 23.5 (7)	30.3 42.0 51.1 (7)
1	2	124.1 174.1 237.8 (8)	10.1 18.1 30.4 (8)	32.5 37.4 66.7 (8)	9.2 17.8 33.6 (8)	27.9 38.2 63.4 (8)	11.0 18.3 27.7 (8)	32.7 41.3 68.4 (8)
1	3	97.0 104.7 158.4 (9)	4.3 5.7 10.0 (8)	16.2 18.1 21.3 (8)	3.4 4.2 10.8 (8)	8.7 13.9 18.7 (8)	5.1 5.8 7.3 (8)	16.2 21.0 27.3 (8)
2	1	158.9 217.4 234.6 (5)	9.8 11.3 20.7 (5)	24.9 35.2 37.7 (5)	14.6 18.9 28.9 (5)	27.1 29.1 42.1 (5)	3.5 4.8 10.3 (5)	26.3 33.2 43.6 (5)
2	2	116.1 237.6 346.8 (6)	7.5 13.8 19.0 (6)	16.7 34.6 52.8 (6)	8.4 11.7 17.8 (6)	19.9 36.9 46.6 (6)	5.6 11.2 16.4 (6)	14.1 31.0 62.7 (6)
2	3	50.1 167.6 298.3 (8)	1.4 3.7 6.1 (6)	4.0 11.4 29.2 (6)	1.6 3.3 7.9 (6)	4.9 11.2 19.1 (6)	0.9 2.7 7.7 (6)	2.5 12.6 40.9 (6)
3	1	415.9 470.4 1109.0 (4)	3.5 8.3 12.4 (4)	52.9 81.8 111.7 (4)	5.6 12.0 14.0 (4)	37.6 53.6 116.2 (4)	1.2 1.7 6.4 (3)	66.3 88.1 307.1 (4)
3	2	137.7 179.7 279.2 (6)	1.3 1.5 4.6 (6)	15.9 19.1 24.4 (6)	1.7 1.9 4.4 (6)	11.2 17.3 22.2 (6)	0.6 0.9 1.7 (6)	14.8 23.1 28.5 (6)
3	3	44.3 140.1 299.0 (6)	0.6 1.2 2.8 (5)	8.5 16.1 29.6 (5)	0.7 1.3 2.1 (5)	7.5 15.4 27.4 (5)	1.0 1.0 1.1 (5)	9.6 16.9 17.3 (5)
4	1	508.2 581.3 1053.9 (4)	7.1 26.0 62.8 (4)	36.3 80.0 142.9 (4)	12.8 27.9 62.8 (4)	30.3 78.8 142.9 (4)	1.1 3.3 5.6 (2)	34.4 39.8 45.3 (2)
4	2	259.0 272.7 321.9 (3)	4.7 5.1 34.4 (3)	22.1 25.4 70.3 (3)	4.1 4.6 42.1 (3)	18.6 20.1 89.1 (3)	5.3 5.6 27.8 (3)	26.0 31.3 54.2 (3)
4	3	84.5 98.2 196.5 (10)	2.4 3.1 6.8 (5)	9.2 22.4 36.2 (5)	1.6 2.6 9.7 (4)	13.1 16.2 97.1 (5)	1.4 2.9 9.6 (4)	8.0 29.3 47.8 (5)

Area	Traffic Surface	Gutters and Traffic Surface
Non Trackout	3.5 3.5 5.4 (5)	8.3 10.2 10.8 (5)
Trackout	4.5 8.3 14.1 (5)	26.0 30.2 42.3 (5)

Notes: "All Areas" group includes trackout and non trackout area data
Road Type 1: Local — Road Type 3: Minor Arterial
Road Type 2: Collector — Road Type 4: Major Arterial / Freeway

Table 9: Summary of Sediment Unit Loads by Particle Size Classification, All Particle Sizes

(HEPA Samples)

(grams per square meter)
Lower Quartile / Median / Upper Quartile (Number of Data Points)

Road Type	Round	All Areas Traffic Surface	Intersection Traffic Surface	Non Intersection Traffic Surface
1	1	120.8 123.0 125.2 (2)	170.6 185.4 200.2 (2)	50.1 60.6 71.1 (2)
1	2	35.6 51.0 65.5 (4)	30.8 58.4 80.4 (4)	36.6 46.1 57.3 (4)
1	3	9.7 13.4 17.0 (2)	8.4 10.3 12.3 (2)	11.1 14.6 18.2 (2)
2	1	79.8 79.8 79.8 (1)	109.8 109.8 109.8 (1)	48.7 48.7 48.7 (1)
2	2	133.1 133.1 133.1 (1)	134.6 134.6 134.6 (1)	130.4 130.4 130.4 (1)
3	1	35.4 45.8 65.7 (3)	89.3 90.9 93.2 (3)	8.7 10.0 46.5 (3)
3	2	5.0 5.7 13.8 (3)	9.2 12.6 15.0 (3)	2.7 3.5 16.3 (3)
3	3	2.3 3.5 5.5 (3)	2.7 4.5 5.2 (3)	1.8 2.5 5.7 (3)
4	1	27.0 66.0 105.1 (2)	46.8 89.0 131.2 (2)	6.5 41.5 76.5 (2)
4	2	12.9 12.9 12.9 (1)	13.8 13.8 13.8 (1)	11.8 11.8 11.8 (1)
4	3	3.5 5.7 8.0 (2)	4.4 4.4 4.4 (1)	2.5 2.5 2.5 (1)

Area	Traffic Surface
Non Trackout	7.5 8.9 10.2 (2)
Trackout	8.4 21.8 35.1 (2)

Notes: "All Areas" group includes trackout and non trackout area data
Road Type 1: Local — Road Type 3: Minor Arterial
Road Type 2: Collector — Road Type 4: Major Arterial / Freeway

Table 10: Summary of Sediment Unit Loads by Particle Size Classification, Air Suspendable Particles (<0.074 mm)

(HEPA Samples)

(grams per square meter)
Lower Quartile / Median / Upper Quartile (Number of Data Points)

Road Type	Round	All Areas Traffic Surface	Intersection Traffic Surface	Non Intersection Traffic Surface
1	1	10.3 10.3 10.3 (2)	14.5 14.6 14.6 (2)	6.0 6.1 6.1 (2)
1	2	9.8 17.6 25.0 (4)	11.6 18.0 26.6 (4)	8.4 17.7 23.4 (4)
1	3	1.6 2.4 3.2 (2)	0.9 1.5 2.1 (2)	2.3 2.7 3.0 (2)
2	1	6.4 6.4 6.4 (1)	9.8 9.8 9.8 (1)	2.8 2.8 2.8 (1)
2	2	14.1 14.1 14.1 (1)	11.4 11.4 11.4 (1)	18.9 18.9 18.9 (1)
3	1	3.7 4.7 6.6 (3)	10.3 11.1 11.6 (3)	0.6 0.9 3.0 (3)
3	2	1.0 1.1 4.3 (3)	1.4 1.6 3.1 (3)	0.7 1.0 6.6 (3)
3	3	0.4 0.6 0.7 (3)	0.5 0.7 0.7 (3)	0.4 0.6 0.7 (3)
4	1	2.4 5.3 8.2 (2)	4.4 6.5 8.7 (2)	0.3 4.0 7.7 (2)
4	2	2.4 2.4 2.4 (1)	2.5 2.5 2.5 (1)	2.3 2.3 2.3 (1)
4	3	0.2 1.5 2.8 (2)	0.2 0.2 0.2 (1)	0.2 0.2 0.2 (1)

Area	Traffic Surface
Non Trackout	2.2 2.5 2.8 (2)
Trackout	2.7 4.6 6.6 (2)

Notes: "All Areas" group includes trackout and non trackout area data
Road Type 1: Local — Road Type 3: Minor Arterial
Road Type 2: Collector — Road Type 4: Major Arterial / Freeway

ROADSITE.DBF

Field Summary, Legend, and Hardcopy Printout

The following Table describes the fields included in the ROADSITE.DBF database.

ROADSITE.DBF Field Summary and Legend

Field Name	Data Type	Size	Field Description
SITE_NAME	Character	43	Sampling site location name.
SITE_ID	Character	5	Site name abbreviation. Primary key for relation to SEDDATA.DBF and AQDATA.DBF databases.
ROAD_TYPE	Numeric	1	Numerical identifier for road type (1-4). 1=local, 2=collector, 3=minor arterial, 4=major arterial/freeway
TYPE_NAME	Character	25	Road type description. Local, collector, minor arterial, major arterial/freeway.
ROUND_1	Date	8	Date of first sampling round (MMDDYY).
ROUND_2	Date	8	Date of second sampling round (MMDDYY).
ROUND_3	Date	8	Date of third sampling round (MMDDYY).
SWEEP_1	Date	8	Date of first street sweeping event (MMDDYY).
SWEEP_1Q	Character	1	Estimated date qualifier. E indicates the date is an estimate.
SWEEP_2	Date	8	Date of second street sweeping event (MMDDYY).
SWEEP_2Q	Character	1	Estimated date qualifier. E indicates the date is an estimate.
SWEEP_3	Date	8	Date of third street sweeping event (MMDDYY).
SWEEP_3Q	Character	1	Estimated date qualifier. E indicates the date is an estimate.
NOTES	Character	60	Notes

Sampling Site Database (ROADSITE.DBF) - Street Sediment Loads Assessment Project

02/13/97

Site Name	Site ID	Type Name	Sampling Dates Round 1	Round 2	Round 3	Street Sweeping Dates Sweep 1	Sweep 2	Sweep 3	Notes
15th east of Columbine	15A	local	04/10/96	04/25/96	08/06/96	04/18/96	05/02/96	07/01/96 E	Assume site swept three times.
Columbine north of 16th	CO	local	04/02/96	04/23/96	08/06/96	04/18/96	05/02/96	07/01/96 E	Assume site swept three times.
Columbine south of 15th	COL	local	04/10/96	04/25/96	08/06/96	04/18/96	05/02/96	07/01/96 E	Assume site swept three times.
Iowa north of Spenard	IOW	local	/ /	/ /	07/24/96	04/01/96 E	04/21/96	07/01/96 E	Assume site swept three times. Only gutters sampled.
N st. south of 12th	N ST	local	03/26/96	04/26/96	07/08/96	04/15/96	07/01/96 E	/ /	Assume site was swept twice.
12th east of N Street	s12	local	03/26/96	04/26/96	07/08/96	04/15/96	07/01/96 E	/ /	Assume site was swept twice.
13th east of Karluck	s13	local	04/05/96	04/24/96	07/09/96	04/16/96	05/02/96	07/02/96	
13th east of Karluck	s13	local	/ /	/ /	08/08/96	04/16/96	05/02/96	07/02/96	Track out sampling.
16th east of Columbine	s16	local	04/02/96	04/23/96	08/06/96	04/18/96	05/02/96	07/01/96 E	Assume site swept three times.
21st and Blueberry	s21	local	/ /	05/22/96	08/12/96	04/18/96	06/01/96 E	07/01/96 E	OGS site. Assume site swept three time.
Denali south of Northern Lights	DEN	collector	/ /	/ /	07/26/96	03/28/96	04/05/96	07/01/96 E	Assume site swept three times. Only gutters sampled.
E street north of 15th	E ST	collector	03/27/96	04/25/96	08/07/96	04/08/96	05/04/96	07/01/96 E	Assume site swept three times.
Karluck north of 13th	KA	collector	04/05/96	04/24/96	07/09/96	04/16/96	05/02/96	07/02/96	
Karluck north of 9th	KB	collector	04/05/96	04/18/96	08/08/96	04/16/96	05/02/96	07/02/96	
King north of Dimond	KING	collector	/ /	04/25/96	07/16/96	04/05/96	04/27/96	07/01/96 E	Assume site swept three times.
Reeve north of 5th	RV	collector	03/27/96	04/19/96	07/17/96	04/10/96 E	06/01/96 E	07/01/96 E	Assume site swept three times.
20th west of Lake Otis	s20	collector	/ /	/ /	08/07/96	05/01/96 E	06/01/96 E	07/01/96 E	Assume site swept three times. Only gutters sampled.
9th east of Karluck	s9	collector	04/05/96	04/18/96	08/08/96	04/16/96	05/02/96	07/02/96	
36th west of New Seward	36B	minor arterial	/ /	04/16/96	07/16/96	03/25/96	04/05/96	07/03/96	Assume site swept three times.
36th east of Old Seward	36E	minor arterial	/ /	04/24/96	/ /	03/25/96	04/05/96	07/03/96	Sampled by mistake. Assume site swept three times.
Old Seward south of 36th	OS	minor arterial	03/21/96	04/24/96	07/17/96	03/25/96	04/06/96	07/03/96	
Old Seward south of 36th	OS	minor arterial	/ /	04/25/96	/ /	03/25/96	04/06/96	07/03/96	HEPA sampling.
Old Seward south of Dowling	OSD	minor arterial	04/16/96	05/30/96	07/17/96	05/27/96	/ /	/ /	Site swept once.
Old Seward bus stop south of Dowling	OSDBS	minor arterial	04/16/96	/ /	/ /	05/27/96	/ /	/ /	Site swept once.
Spenard east of Iowa	SP	minor arterial	/ /	/ /	07/24/96	03/18/96	04/21/96	07/01/96 E	Assume site swept three times. Only gutters sampled.
15th east of E Street	s15	minor arterial	03/27/96	04/25/96	08/07/96	04/08/96	05/04/96	07/01/96 E	Assume site swept three times.
36th west of Old Seward	s36	minor arterial	03/21/96	04/24/96	07/17/96	03/25/96	04/05/96	07/03/96	
36th west of Old Seward	s36	minor arterial	/ /	04/25/96	/ /	03/25/96	04/05/96	07/03/96	HEPA sampling.
A street south of 6th	A	major arterial/freeway	/ /	/ /	07/26/96	03/18/96 E	04/04/96	07/01/96 E	Assume site swept three times. Only gutters sampled.
Debarr west of Muldoon	DEB	major arterial/freeway	/ /	/ /	07/24/96	04/01/96 E	04/21/96	07/22/96	Only gutters sampled.
Dimond west of King	DM	major arterial/freeway	03/22/96	04/19/96	07/16/96	03/27/96	04/27/96	07/10/96	
Lake Otis north of 20th	LKOT	major arterial/freeway	/ /	/ /	08/07/96	03/11/96	06/01/96 E	07/01/96 E	Assume site swept three times. Only gutters sampled.
Muldoon south of Debarr	MUL	major arterial/freeway	/ /	/ /	07/24/96	04/01/96 E	04/21/96	07/22/96	Only gutters sampled.
Northern Lights east of Spenard	N LTS	major arterial/freeway	03/22/96	/ /	07/26/96	03/23/96	07/01/96 E	/ /	OGS site. Assume site swept twice.
Northern Lights east of Denali	NLTB	major arterial/freeway	/ /	/ /	07/26/96	03/22/96	05/01/96 E	07/01/96 E	Assume site swept three times. Only gutters sampled.
New Seward north of 36th	NS	major arterial/freeway	03/20/96	04/16/96	07/16/96	03/21/96	03/29/96 E	04/06/96	
5th east of Reeve	s5	major arterial/freeway	03/27/96	04/19/96	07/17/96	04/10/96 E	06/01/96 E	07/12/96	Assume site swept three times.
6th west of A	s6	major arterial/freeway	/ /	/ /	07/24/96	03/18/96 E	04/10/96	07/01/96 E	Assume site swept three times. Only gutters sampled.

Key:
E - Estimated date

SEDDATA.DBF and AQDATA.DBF

Field Summary, Legend, and Hardcopy Printout

The following tables describe the fields included in the SEDDATA.DBF and AQDATA.DBF databases.

SEDDATA.DBF and AQDATA.DBF Field Summary and Legend

Field Name	Unit	Data Type	Size	Field Description
ROUND		Numeric	20	Sampling round number (1 - 3)
SITE_ID		Character	5	The site from which the sample was taken. See site ID legend.
SAMPCODE		Character	5	The sample collection method (W/D: Wet/Dry Vacuum ; HEPA: HEPA Vacuum)
ANALCODE		Character	9	The analysis method used for determining the particle size distribution
TO		Logical	1	Whether the sample was taken to assess trackout area loadings
STRATA		Character	5	The strata or portion of the street from which the sample was taken. See strata legend
SAMPDATE		Date	1	Date the sample was collected
TRANSWIDTH	m	Numeric	20	Width of the sampled transect
TRANSLENG	m	Numeric	20	Length of the sampled transect
TRANSAREA	m^2	Numeric	20	Street surface area that was sampled
TOTDRYWT	g	Numeric	20	The total dry weight of the sample
S38_1MM	%	Numeric	20	Percent passing the 38.1mm seive
S19_0MM	%	Numeric	20	Percent passing the 19.0mm seive
S9_5MM	%	Numeric	20	Percent passing the 9.5mm seive
S4_76MM	%	Numeric	20	Percent passing the 4.76mm seive
S2_00MM	%	Numeric	20	Percent passing the 2.00mm seive
S0_84MM	%	Numeric	20	Percent passing the 0.84mm seive
S0_42MM	%	Numeric	20	Percent passing the 0.42mm seive
S0_149MM	%	Numeric	20	Percent passing the 0.149mm seive
S0_105MM	%	Numeric	20	Percent passing the 0.105mm seive
S0_074MM	%	Numeric	20	Percent passing the 0.074mm seive
PCTRETAIN	%	Numeric	20	Amount retained in vacuum bag expressed as a percent of the total dry weight of the sample
BAGWT	g	Numeric	20	Tare weight of vacuum bag plus the weight of material retained in the bag
BAGTARE	g	Numeric	20	Tare weight of vacuum bag
RETAINED	g	Numeric	20	Weight of material retained in vacuum bag
OGS	g/m^2	Numeric	20	OGS treatable loading
AIRSUSP	g/m^2	Numeric	20	Loading for particles of 10 microns or less
TOTLOAD	g/m^2	Numeric	20	Total particulate loading
NOTES		Character	25	Notes

Site ID Legend

Site ID	Site Description	Road Type
15A	15th east of Columbine	1
36B	36th west of New Seward	3
36E	36th east of Old Seward	3
A	A street south of 6^{th}	4
CO	Columbine north of 16^{th}	1
COL	Columbine south of 15^{th}	1
DEB	Debarr west of Muldoon	4
DEN	Denali south of Northern Lights	2
DM	Dimond west of King	4
E ST	E street north of 15^{th}	2
IOW	Iowa north of Spenard	1
KA	Karluck north of 13^{th}	2
KB	Karluck north of 9^{th}	2
KING	King north of Dimond	2
LKOT	Lake Otis north of 20^{th}	4
MUL	Muldoon south of Debarr	4
N LTS	Northern Lights east of Spenard	4
N ST	N st. south of 12^{th}	1
NLTB	Northern Lights east of Denali	4
NS	New Seward north of 36^{th}	4
OS	Old Seward south of 36^{th}	3
OSD	Old Seward south of Dowling	3
OSDBS	Old Seward bus stop south of Dowling	3
RV	Reeve north of 5^{th}	2
SP	Spenard east of Iowa	3
s12	12th east of N Street	1
s13	13th east of Karluck	1
s15	15th east of E Street	3
s16	16th east of Columbine	1
s20	20th west of Lake Otis	2
s21	21st and Blueberry	1
s36	36th west of Old Seward	3
s5	5th east of Reeve	4
s6	6th west of A	4
s9	9th east of Karluck	2

Wet/Dry Vacuum Samples

February 13, 1997

											Percent Passing Sieve (mm)														Loadings (g/m²)			
round	site_id	sample	to	strata	sampdate	transwidth	transleng	transarea	totdrywt	analysis	38.1	19.0	9.5	4.76	2.00	0.84	0.42	0.149	0.105	0.074	bagwt	pctretain	bagtare	retained	ogs	airsusp	totload	notes
1	15A	W/D	F	NING	4/10/96	0.15	29.26	4.46	338.8	ASTM C136	100.0	100.0	100.0	92.3	63.3	41.5	32.7	15.9	9.4	8.5	109.80	12.9	66.00	43.80	68.83	16.28	86	
1	15A	W/D	F	ING	4/10/96	0.15	29.26	4.46	1525.8	ASTM C136	100.0	100.0	99.8	89.0	34.1	18.9	14.8	8.2	5.1	4.5	160.00	6.2	66.00	94.00	324.71	36.48	363	
1	15A	W/D	F	NIG	4/10/96	0.20	3.66	0.74	2152.6	ASTM C136	100.0	88.1	80.6	75.4	69.7	63.0	56.1	36.9	28.2	24.4	0.00	0.0	0.00	0.00	2,079.54	706.70	2896	Sampled with shovel
1	15A	W/D	F	IG	4/10/96	0.20	3.66	0.74	969.3	ASTM C136	100.0	91.7	88.6	80.2	65.6	56.3	49.6	34.2	28.4	25.4	0.00	0.0	0.00	0.00	933.79	331.26	1304	Sampled with shovel
1	CO	W/D	F	NING	4/2/96	0.20	29.26	5.95	1449.5	ASTM C136	100.0	100.0	100.0	94.3	73.2	55.2	41.3	24.5	19.4	17.9	93.80	1.9	66.00	27.80	196.49	48.31	248	
1	CO	W/D	F	ING	4/2/96	0.20	31.09	6.32	3169.0	ASTM C136	100.0	100.0	100.0	89.4	52.5	39.2	30.4	17.6	13.8	12.7	90.20	0.8	66.00	24.20	432.40	67.54	505	
1	CO	W/D	F	NIG	4/2/96	0.20	3.66	0.74	524.8	ASTM C136	100.0	100.0	99.1	94.3	82.8	72.2	56.9	23.1	10.7	10.2	0.00	0.0	0.00	0.00	630.56	72.02	706	Sampled with shovel
1	CO	W/D	F	IG	4/2/96	0.20	3.66	0.74	976.4	ASTM C136	100.0	100.0	99.7	85.4	51.7	44.1	34.7	14.9	9.3	7.6	0.00	0.0	0.00	0.00	1,191.56	99.84	1314	Sampled with shovel
1	COL	W/D	F	NING	4/10/96	0.15	29.26	4.46	448.2	ASTM C136	100.0	100.0	100.0	89.3	60.5	35.3	21.8	8.0	4.1	3.7	109.10	9.6	66.00	43.10	96.39	13.38	110	
1	COL	W/D	F	ING	4/10/96	0.15	29.26	4.46	1139.7	ASTM C136	100.0	100.0	99.8	86.3	32.0	17.3	12.8	6.7	3.6	3.5	130.90	5.7	66.00	64.90	246.37	23.50	270	
1	COL	W/D	F	NIG	4/10/96	0.20	3.66	0.74	1651.6	ASTM C136	100.0	100.0	98.5	92.6	80.3	67.7	54.1	24.8	11.3	11.1	0.00	0.0	0.00	0.00	1,971.10	246.66	2222	Sampled with broom
1	COL	W/D	F	IG	4/10/96	0.20	3.66	0.74	2143.8	ASTM C136	100.0	100.0	98.7	88.1	64.4	51.3	40.4	19.9	10.5	10.2	0.00	0.0	0.00	0.00	2,581.59	294.21	2884	Sampled with broom
1	DM	W/D	F	ING	3/22/96	0.20	57.61	11.71	5297.0	ASTM C136	100.0	100.0	99.9	92.9	52.7	32.6	23.4	11.8	8.8	6.9	95.00	0.5	66.00	29.00	412.69	33.70	455	Two Transects (T 5, T100)
1	DM	W/D	F	IG	3/22/96	0.18	6.10	1.09	11308.0	ASTM C136	100.0	100.0	99.1	94.0	75.0	58.4	42.5	18.1	12.7	11.0	290.80	2.0	66.00	224.80	9,051.10	1,346.57	10574	
1	E ST	W/D	F	NING	3/27/96	0.20	27.43	5.57	76.9	ASTM C136	100.0	100.0	100.0	97.9	86.7	52.3	27.4	3.1	1.0	0.3	67.50	2.0	66.00	1.50	13.66	0.31	14	
1	E ST	W/D	F	ING	3/27/96	0.20	29.87	6.07	86.5	ASTM C136	100.0	100.0	100.0	97.3	65.5	29.8	12.7	0.9	0.0	0.0	67.40	1.6	66.00	1.40	14.25	0.23	14	
1	E ST	W/D	F	NIG	3/27/96	0.20	3.66	0.74	966.3	ASTM C136	100.0	100.0	98.7	86.8	63.1	44.5	29.0	11.1	7.8	6.9	154.80	9.2	66.00	88.80	1,198.73	209.19	1420	
1	E ST	W/D	F	IG	3/27/96	0.20	3.66	0.74	1736.1	ASTM C136	100.0	100.0	99.7	88.5	59.5	45.6	30.0	13.8	4.5	3.7	146.80	4.7	66.00	80.80	2,230.79	195.14	2445	
1	KA	W/D	F	NING	4/5/96	0.15	37.49	5.71	636.4	ASTM C136	100.0	100.0	100.0	88.9	46.2	29.1	20.5	9.0	5.9	4.8	87.10	3.3	66.00	21.10	104.81	9.04	115	
1	KA	W/D	F	ING	4/5/96	0.15	40.54	6.18	2348.5	ASTM C136	100.0	100.0	99.9	89.7	40.3	25.8	19.7	10.0	6.8	5.4	159.30	1.2	132.00	27.30	354.29	24.95	385	
1	KA	W/D	F	NIG	4/5/96	0.20	3.66	0.74	2346.1	ASTM C136	100.0	100.0	96.1	87.7	63.9	52.3	45.9	32.0	26.2	24.2	0.00	0.0	0.00	0.00	2,329.61	763.91	3157	Sampled with shovel
1	KA	W/D	F	IG	4/5/96	0.20	3.66	0.74	3138.8	ASTM C136	100.0	97.2	96.4	77.3	25.9	16.9	14.1	9.1	7.5	6.7	0.00	0.0	0.00	0.00	3,906.47	282.96	4223	Sampled with shovel
1	KB	W/D	F	NING	4/5/96	0.15	37.49	5.71	422.6	ASTM C136	100.0	100.0	100.0	87.2	45.8	28.0	18.8	7.5	5.1	4.1	71.80	1.4	66.00	5.80	70.19	4.05	75	
1	KB	W/D	F	ING	4/5/96	0.15	39.01	5.95	1474.4	ASTM C136	100.0	100.0	100.0	87.6	33.0	19.4	14.3	7.0	5.0	3.9	79.30	0.9	66.00	13.30	235.57	11.91	250	
1	KB	W/D	F	NIG	4/5/96	0.20	3.66	0.74	1437.0	ASTM C136	100.0	100.0	98.4	86.7	59.0	45.6	36.5	22.2	17.7	15.2	0.00	0.0	0.00	0.00	1,591.24	293.89	1933	Sampled with broom
1	KB	W/D	F	IG	4/5/96	0.20	3.66	0.74	1746.6	ASTM C136	100.0	100.0	99.3	81.3	29.8	18.9	14.6	7.7	5.4	4.2	0.00	0.0	0.00	0.00	2,223.13	98.70	2350	Sampled with broom
1	N LTS	W/D	F	NING	3/22/96	0.20	108.02	21.95	130.5	ASTM C136	100.0	100.0	98.2	93.9	78.2	46.1	29.3	9.9	6.1	3.8	81.60	12.0	66.00	15.60	5.58	0.94	7	
1	N LTS	W/D	F	ING	3/22/96	0.20	49.07	9.97	1001.3	ASTM C136	100.0	100.0	99.9	98.8	88.4	58.9	36.9	9.1	8.1	5.5	105.40	3.9	66.00	39.40	92.28	9.47	104	
1	N LTS	W/D	F	NIG	3/22/96	0.20	4.88	0.99	3825.2	ASTM C136	100.0	100.0	99.9	96.6	86.0	68.2	49.8	24.0	18.1	15.0	140.00	1.9	66.00	74.00	3,160.41	653.48	3934	North gutter only
1	N LTS	W/D	F	IG	3/22/96	0.20	2.44	0.50	1729.3	ASTM C136	100.0	100.0	97.2	89.7	69.0	46.3	27.1	7.4	4.0	3.1	89.30	1.3	66.00	23.30	3,352.62	155.32	3539	North gutter only
1	N ST	W/D	F	NING	3/26/96	0.20	27.43	5.57	758.6	ASTM C136	100.0	100.0	98.3	90.0	57.6	26.8	11.5	1.8	0.9	0.7	85.80	2.6	66.00	19.80	134.87	4.50	140	
1	N ST	W/D	F	ING	3/26/96	0.20	28.04	5.70	1426.9	ASTM C136	100.0	100.0	99.8	87.3	28.8	10.6	5.7	1.6	1.0	0.6	85.90	1.4	66.00	19.90	247.93	5.00	254	
1	N ST	W/D	F	NIG	3/26/96	0.20	3.66	0.74	500.8	ASTM C136	100.0	100.0	92.8	80.4	63.7	51.0	41.1	16.8	10.1	9.6	113.50	9.5	66.00	47.50	605.76	128.60	738	
1	N ST	W/D	F	IG	3/26/96	0.20	3.66	0.74	535.9	ASTM C136	100.0	100.0	97.3	80.2	40.5	27.3	20.4	9.6	7.0	5.9	108.20	7.9	66.00	42.20	670.57	99.32	778	

Street Sediment Sample Database (SEDDATA.DBF)

Wet/Dry Vacuum Samples

February 13, 1997

											Percent Passing Sieve (mm)														Loadings (g/m²)			
round	site_id	sample	to	strata	sampdate	transwidth	transleng	transarea	totdrywt	analysis	38.1	19.0	9.5	4.76	2.00	0.84	0.42	0.149	0.105	0.074	bagwt	pctretain	bagtare	retained	ogs	airsusp	totload	notes
1	NS	W/D	F	ING	3/20/96	0.20	34.44	7.00	6934.0	ASTM C136	100.0	100.0	100.0	96.1	74.3	45.3	29.6	11.9	8.4	6.5	0.00	0.0	0.00	0.00	907.57	64.40	991	One Transect (T 5) Only
1	NS	W/D	F	IG	3/20/96	0.20	3.66	0.74	2103.0	ASTM C136	100.0	100.0	99.1	93.9	77.7	61.6	47.7	22.1	15.5	12.6	0.00	0.0	0.00	0.00	2,390.98	356.52	2830	One Transect (T 5) Only
1	OS	W/D	F	NING	3/21/96	0.20	45.72	9.29	792.5	ASTM C136	100.0	100.0	100.0	95.6	74.0	55.1	38.7	15.8	11.1	8.6	84.90	1.8	71.00	13.90	75.84	8.83	87	
1	OS	W/D	F	ING	3/21/96	0.20	51.51	10.47	790.4	ASTM C136	100.0	100.0	100.0	98.8	80.8	55.7	39.4	15.9	11.2	8.9	89.90	2.4	71.00	18.90	67.05	8.53	77	
1	OS	W/D	F	NIG	3/21/96	0.20	7.32	1.49	4479.0	ASTM C136	100.0	100.0	99.6	98.2	85.9	65.6	47.2	18.9	12.7	9.9	239.30	3.8	71.00	168.30	2,630.54	411.53	3126	
1	OS	W/D	F	IG	3/21/96	0.20	6.10	1.24	3101.0	ASTM C136	100.0	100.0	100.0	97.0	77.5	58.1	41.1	16.0	10.5	8.9	302.00	7.4	71.00	231.00	2,241.12	409.39	2691	
1	OSD	W/D	F	NING	4/16/96	0.30	62.79	19.14	280.4	ASTM C136	100.0	100.0	100.0	99.2	87.1	51.9	31.0	11.6	7.5	5.0	78.40	4.4	66.00	12.40	13.55	1.38	15	
1	OSD	W/D	F	ING	4/16/96	0.15	70.71	10.78	1175.4	ASTM C136	100.0	100.0	100.0	97.1	78.2	56.6	41.1	17.3	10.5	7.8	91.50	2.2	66.00	25.50	97.62	10.87	111	
1	OSD	W/D	F	NIG	4/16/96	0.15	8.53	1.30	15805.0	ASTM C136	100.0	100.0	98.2	96.0	88.0	72.3	52.8	23.2	12.3	11.7	166.50	0.2	132.00	34.50	10,657.02	1,448.27	12178	Outlier
1	OSD	W/D	F	IG	4/16/96	0.15	6.10	0.93	11989.0	ASTM C136	100.0	100.0	98.8	96.1	89.2	73.6	54.9	24.5	15.6	11.1	169.80	0.3	132.00	37.80	10,891.68	1,473.12	12946	Outlier
1	RV	W/D	F	NING	3/27/96	0.20	53.95	10.96	579.2	ASTM C136	100.0	100.0	99.7	93.3	50.9	26.0	17.3	7.4	4.8	3.6	76.60	1.8	66.00	10.60	50.30	2.87	54	
1	RV	W/D	F	ING	3/27/96	0.20	55.78	11.33	2301.0	ASTM C136	100.0	100.0	100.0	88.9	34.4	22.9	17.8	9.0	5.9	4.3	144.50	3.4	66.00	78.50	191.04	15.66	210	
1	RV	W/D	F	NIG	3/27/96	0.20	3.66	0.74	519.8	ASTM C136	100.0	100.0	88.4	55.2	10.4	6.1	5.1	2.5	2.0	1.9	67.80	0.3	66.00	1.80	685.40	15.71	702	
1	RV	W/D	F	IG	3/27/96	0.20	3.66	0.74	1144.2	ASTM C136	100.0	96.9	92.3	67.3	24.2	18.0	15.4	9.0	7.2	6.5	121.10	4.8	66.00	55.10	1,428.66	174.20	1614	
1	s12	W/D	F	NING	3/26/96	0.20	27.43	5.57	727.4	ASTM C136	100.0	100.0	100.0	98.0	79.3	47.2	29.5	11.5	7.0	4.7	102.30	5.0	66.00	36.30	121.36	12.65	137	
1	s12	W/D	F	ING	3/26/96	0.20	28.04	5.70	681.1	ASTM C136	100.0	100.0	100.0	92.3	47.7	26.8	20.5	10.2	7.5	6.1	116.60	7.4	66.00	50.60	110.57	16.17	128	
1	s12	W/D	F	NIG	3/26/96	0.20	3.66	0.74	595.9	ASTM C136	100.0	92.3	80.9	66.3	50.4	33.1	23.4	10.9	8.3	7.5	164.20	16.5	66.00	98.20	735.23	192.26	934	
1	s12	W/D	F	IG	3/26/96	0.20	3.66	0.74	922.3	ASTM C136	100.0	100.0	96.4	75.0	36.8	27.0	20.5	10.1	7.6	6.3	175.80	11.9	66.00	109.80	1,146.63	225.91	1389	
1	s13	W/D	F	NING	4/5/96	0.15	37.49	5.71	429.6	ASTM C136	100.0	100.0	99.3	91.1	60.1	35.3	23.6	9.5	6.1	5.0	72.40	1.5	66.00	6.40	70.60	4.88	76	
1	s13	W/D	F	ING	4/5/96	0.15	32.92	5.02	1042.2	ASTM C136	100.0	100.0	99.8	90.1	33.8	16.9	11.4	5.1	3.3	3.0	81.00	1.4	66.00	15.00	200.89	9.22	211	
1	s13	W/D	F	NIG	4/5/96	0.20	3.66	0.74	650.2	ASTM C136	100.0	93.6	81.9	71.6	63.4	54.1	44.5	25.0	18.2	15.8	0.00	0.0	0.00	0.00	715.62	138.22	875	Sampled with shovel
1	s13	W/D	F	IG	4/5/96	0.20	3.66	0.74	357.6	ASTM C136	100.0	100.0	97.3	52.2	39.5	31.3	14.6	9.5	8.0	7.8	80.30	4.0	66.00	14.30	442.65	56.77	500	Sampled with shovel
1	s15	W/D	F	NING	3/27/96	0.20	29.26	5.95	175.8	ASTM C136	100.0	100.0	100.0	100.0	88.5	45.5	22.0	3.2	1.7	0.9	65.00	0.6	64.00	1.00	29.06	0.43	30	
1	s15	W/D	F	ING	3/27/96	0.20	33.53	6.81	397.0	ASTM C136	100.0	100.0	100.0	97.6	56.6	23.0	9.7	1.2	0.6	0.3	69.90	1.0	66.00	3.90	57.92	0.75	59	
1	s15	W/D	F	NIG	3/27/96	0.20	3.66	0.74	2444.0	ASTM C136	100.0	100.0	99.3	94.5	74.4	54.3	37.9	17.0	12.8	12.0	115.80	2.0	66.00	49.80	2,867.46	461.61	3355	
1	s15	W/D	F	IG	3/27/96	0.20	3.66	0.74	1059.9	ASTM C136	100.0	100.0	99.4	86.4	57.0	39.7	29.2	12.5	8.8	7.9	153.60	8.3	66.00	87.60	1,300.59	230.53	1544	
1	s16	W/D	F	NING	4/2/96	0.20	29.26	5.95	923.2	ASTM C136	100.0	97.9	96.4	88.1	61.4	45.2	35.2	20.2	15.0	12.4	106.10	4.3	66.00	40.10	131.98	26.00	162	
1	s16	W/D	F	ING	4/2/96	0.20	30.94	6.29	758.4	ASTM C136	100.0	100.0	99.7	91.4	57.1	40.0	31.8	19.8	14.9	13.0	84.70	2.5	66.00	18.70	102.66	18.66	124	
1	s16	W/D	F	NIG	4/2/96	0.20	3.66	0.74	740.2	ASTM C136	100.0	96.6	90.9	76.2	54.8	45.0	36.5	19.1	12.3	11.2	77.40	1.5	66.00	11.40	873.43	126.88	1011	Water in gutter
1	s16	W/D	F	IG	4/2/96	0.20	3.66	0.74	960.3	ASTM C136	100.0	100.0	96.7	82.6	46.6	37.1	30.2	17.9	12.9	11.9	80.60	1.5	66.00	14.60	1,125.39	173.40	1312	Water in gutter
1	s36	W/D	F	ING	3/21/96	0.20	60.05	12.20	1569.9	ASTM C136	100.0	100.0	100.0	97.1	55.9	37.2	28.2	13.5	9.2	6.6	100.20	1.9	71.00	29.20	116.83	10.89	131	
1	s36	W/D	F	NIG	3/21/96	0.20	7.32	1.49	4278.0	ASTM C136	100.0	100.0	99.9	94.3	49.6	34.6	26.8	11.8	7.9	5.5	499.60	10.0	71.00	428.60	2,650.64	446.63	3166	
1	s36	W/D	F	IG	3/21/96	0.20	6.10	1.24	2623.9	ASTM C136	100.0	100.0	99.8	88.0	63.3	45.7	34.6	19.6	16.3	14.9	146.70	2.9	71.00	75.70	1,773.42	376.83	2180	
1	s5	W/D	F	NING	3/27/96	0.20	57.61	11.71	1275.0	ASTM C136	100.0	100.0	100.0	93.2	65.8	46.9	29.4	8.3	4.2	2.4	77.50	0.9	66.00	11.50	104.35	3.60	110	

Street Sediment Sample Database (SEDDATA.DBF)

Wet/Dry Vacuum Samples

round	site_id	sample	to	strata	sampdate	transwidth	transleng	transarea	totdrywt	analysis	Percent Passing Sieve (mm) 38.1	19.0	9.5	4.76	2.00	0.84	0.42	0.149	0.105	0.074	bagwt	pctretain	bagtare	retained	Loadings (g/m²) ogs	airsusp	totload	notes
1	s5	W/D	F	ING	3/27/96	0.20	63.09	12.82	2434.0	ASTM C136	100.0	100.0	100.0	93.5	62.5	45.7	32.4	10.9	6.6	4.8	79.40	0.6	66.00	13.40	177.32	10.16	191	
1	s5	W/D	F	NIG	3/27/96	0.20	3.66	0.74	4085.0	ASTM C136	100.0	100.0	97.8	89.9	67.6	54.2	39.5	16.4	11.4	8.8	98.60	0.8	66.00	32.60	4,869.74	527.54	5540	
1	s5	W/D	F	IG	3/27/96	0.20	3.66	0.74	4090.0	ASTM C136	100.0	100.0	96.9	82.9	49.4	36.7	27.1	11.4	7.7	5.7	122.20	1.4	66.00	56.20	5,079.31	389.29	5579	
1	s9	W/D	F	NING	4/5/96	0.15	37.49	5.71	1001.1	ASTM C136	100.0	100.0	100.0	92.0	54.2	31.2	21.4	10.4	7.0	6.0	83.70	1.8	66.00	17.70	162.95	13.61	178	
1	s9	W/D	F	ING	4/5/96	0.15	39.01	5.95	2161.0	ASTM C136	100.0	100.0	100.0	90.0	36.3	20.4	15.7	9.1	7.1	6.2	84.40	0.9	66.00	18.40	337.64	25.63	367	
1	s9	W/D	F	NIG	4/5/96	0.20	3.66	0.74	1062.9	ASTM C136	100.0	98.8	98.3	86.7	54.3	38.4	29.7	16.1	11.9	9.5	0.00	0.0	0.00	0.00	1,259.93	135.86	1430	Sampled with broom
1	s9	W/D	F	IG	4/5/96	0.20	3.66	0.74	1463.7	ASTM C136	100.0	100.0	98.9	83.5	34.7	22.6	18.2	10.3	7.5	5.8	0.00	0.0	0.00	0.00	1,821.69	114.22	1969	Sampled with broom
2	15A	W/D	F	NING	4/25/96	0.25	29.26	7.43	444.2	ASTM C136	100.0	100.0	100.0	99.7	98.1	92.4	86.1	63.8	53.8	46.9	87.30	4.8	66.00	21.30	27.61	30.90	63	
2	15A	W/D	F	ING	4/25/96	0.25	29.26	7.43	447.0	ASTM C136	100.0	100.0	100.0	100.0	98.1	92.0	84.7	60.0	50.4	43.4	91.00	5.6	66.00	25.00	29.83	29.47	64	
2	15A	W/D	F	NIG	4/25/96	0.51	3.66	1.86	1383.6	ASTM C136	100.0	100.0	97.9	96.7	94.6	91.2	85.9	56.4	41.5	34.4	80.30	1.0	66.00	14.30	435.62	263.85	752	
2	15A	W/D	F	IG	4/25/96	0.51	3.66	1.86	700.5	ASTM C136	100.0	100.0	98.2	96.7	95.5	94.0	90.4	63.9	51.0	42.6	87.40	3.1	66.00	21.40	184.73	172.12	389	
2	36B	W/D	F	NING	4/16/96	0.15	53.04	8.08	78.6	ASTM C136	100.0	100.0	100.0	96.8	80.7	39.3	24.8	7.4	4.6	2.9	71.30	6.7	66.00	5.30	9.28	0.94	10	
2	36B	W/D	F	ING	4/16/96	0.15	76.20	11.61	702.7	ASTM C136	100.0	100.0	100.0	91.4	64.7	50.1	37.5	16.0	10.3	6.5	80.40	1.3	71.66	9.40	54.28	4.74	61	
2	36B	W/D	F	NIG	4/16/96	0.15	7.32	1.11	1171.9	ASTM C136	100.0	100.0	100.0	97.4	89.3	71.5	52.7	20.6	10.2	6.9	73.50	0.6	66.32	7.50	943.96	79.26	1058	
2	36B	W/D	F	IG	4/16/96	0.15	6.10	0.93	1717.6	ASTM C136	100.0	100.0	100.0	93.6	75.1	58.3	42.9	17.9	9.8	6.5	94.50	1.7	66.00	28.50	1,667.62	150.85	1879	
2	36E	W/D	F	NING	4/24/96	0.51	64.62	32.83	67.6	ASTM C136	100.0	100.0	100.0	93.9	78.0	40.1	26.2	8.9	6.2	4.4	75.50	8.9	69.50	6.00	1.93	0.27	2	
2	36E	W/D	F	ING	4/24/96	0.51	64.62	32.83	159.2	ASTM C136	100.0	100.0	100.0	96.4	73.4	49.6	37.2	16.3	11.4	8.0	74.50	6.1	64.75	9.75	4.30	0.69	5	
2	36E	W/D	F	NIG	4/24/96	0.51	7.32	3.72	5213.4	ASTM C136	100.0	100.0	100.0	97.4	89.0	78.2	63.4	31.0	21.6	15.6	94.10	0.5	69.50	24.60	1,099.88	225.47	1410	
2	36E	W/D	F	IG	4/24/96	0.51	7.32	3.72	4498.4	ASTM C136	100.0	100.0	99.6	97.8	94.0	85.2	68.4	30.9	20.1	13.5	85.70	0.5	65.12	20.58	967.20	168.96	1216	
2	CO	W/D	F	NING	4/23/96	0.20	29.26	5.95	274.1	ASTM C136	100.0	100.0	100.0	99.9	98.1	91.9	77.3	43.9	34.4	29.1	83.30	6.3	66.00	17.30	30.24	16.32	49	
2	CO	W/D	F	ING	4/23/96	0.20	31.09	6.32	475.3	ASTM C136	100.0	100.0	100.0	98.9	92.7	82.4	68.2	38.5	29.3	23.9	81.30	3.0	67.00	14.30	53.19	20.25	78	
2	CO	W/D	F	NIG	4/23/96	0.41	3.66	1.49	678.0	ASTM C136	100.0	100.0	99.7	96.7	89.2	82.8	74.1	44.2	34.3	28.8	82.00	2.4	66.00	16.00	299.67	142.13	467	
2	CO	W/D	F	IG	4/23/96	0.41	3.66	1.49	855.6	ASTM C136	100.0	100.0	99.6	93.2	83.3	77.0	68.8	43.7	34.4	29.2	79.60	1.5	67.00	12.60	377.59	176.55	584	
2	COL	W/D	F	NING	4/25/96	0.25	29.26	7.43	639.0	ASTM C136	100.0	100.0	100.0	99.9	98.6	94.9	85.4	51.0	40.9	35.8	82.70	2.6	66.00	16.70	50.81	33.03	88	
2	COL	W/D	F	ING	4/25/96	0.25	29.26	7.43	647.5	ASTM C136	100.0	100.0	100.0	99.6	96.1	89.9	80.0	50.3	41.3	36.5	84.20	2.8	66.00	18.20	51.14	34.25	90	
2	COL	W/D	F	NIG	4/25/96	0.25	3.66	0.93	1011.3	ASTM C136	100.0	100.0	98.6	96.4	91.7	86.1	77.3	51.4	44.0	39.9	81.50	1.5	66.00	15.50	609.59	451.02	1105	
2	COL	W/D	F	IG	4/25/96	0.25	3.66	0.93	1782.6	ASTM C136	100.0	100.0	99.6	89.9	68.3	58.1	48.8	28.9	23.1	19.5	97.50	1.8	66.00	31.50	1,475.54	408.07	1953	
2	DM	W/D	F	NING	4/19/96	0.20	72.85	14.80	246.4	ASTM C136	100.0	100.0	95.8	90.3	77.9	63.1	49.8	29.4	23.4	19.0	83.50	7.1	66.00	17.50	12.75	4.35	18	
2	DM	W/D	F	ING	4/19/96	0.20	84.12	17.09	296.4	ASTM C136	100.0	100.0	100.0	94.4	71.0	49.7	37.2	20.6	16.4	13.7	77.70	3.9	66.00	11.70	14.50	3.06	18	
2	DM	W/D	F	NIG	4/19/96	0.20	7.32	1.49	1862.8	ASTM C136	100.0	100.0	100.0	99.3	97.1	92.3	77.6	34.6	22.5	15.5	81.80	0.8	66.00	15.80	971.22	204.87	1264	
2	DM	W/D	F	IG	4/19/96	0.20	6.10	1.24	1322.0	ASTM C136	100.0	100.0	100.0	97.8	91.1	82.9	67.9	32.3	22.0	15.9	83.40	1.3	66.00	17.40	832.66	183.78	1082	
2	EST	W/D	F	NING	4/25/96	0.51	27.43	13.94	185.1	ASTM C136	100.0	100.0	100.0	100.0	95.6	78.9	65.6	39.9	30.2	23.0	75.20	5.0	66.00	9.20	9.27	3.72	14	
2	EST	W/D	F	ING	4/25/96	0.51	29.87	15.17	122.9	ASTM C136	100.0	100.0	100.0	99.1	92.2	72.3	57.0	32.5	23.9	17.8	75.80	8.0	66.00	9.80	6.16	2.09	9	
2	EST	W/D	F	NIG	4/25/96	0.25	3.66	0.93	521.5	ASTM C136	100.0	100.0	98.7	97.1	89.1	80.6	67.7	36.4	25.4	18.4	77.30	2.2	66.00	11.30	418.76	115.45	574	

Street Sediment Sample Database (SEDDATA.DBF)

Wet/Dry Vacuum Samples

February 13, 1997

											Percent Passing Sieve (mm)														Loadings (g/m²)			
round	site_id	sample	to	strata	sampdate	transwidth	transleng	transarea	totdrywt	analysis	38.1	19.0	9.5	4.76	2.00	0.84	0.42	0.149	0.105	0.074	bagwt	pctretain	bagtare	retained	ogs	airsusp	totload	notes
2	E ST	W/D	F	IG	4/25/96	0.25	3.66	0.93	435.2	ASTM C136	100.0	100.0	99.0	96.4	87.8	79.6	65.5	31.7	21.6	15.2	84.60	4.3	66.00	18.60	367.26	91.22	488	
2	KA	W/D	F	NING	4/24/96	0.25	37.49	9.52	1305.5	ASTM C136	100.0	100.0	100.0	94.8	74.9	61.1	49.7	28.6	22.2	18.0	83.70	1.4	66.00	17.70	106.66	26.54	139	
2	KA	W/D	F	ING	4/24/96	0.25	40.54	10.30	516.6	ASTM C136	100.0	100.0	100.0	99.3	95.7	84.3	70.6	42.1	32.4	25.7	82.00	3.1	66.00	16.00	33.92	14.45	52	
2	KA	W/D	F	NIG	4/24/96	0.25	3.66	0.93	3034.5	ASTM C136	100.0	100.0	97.5	87.6	64.0	54.3	47.1	30.1	24.0	20.2	82.40	0.5	66.00	16.40	2,482.39	677.45	3284	
2	KA	W/D	F	IG	4/24/96	0.51	3.66	1.86	3271.9	ASTM C136	100.0	100.0	97.4	86.8	63.8	55.4	48.8	30.1	23.2	18.9	89.90	0.7	66.00	23.90	1,352.39	345.68	1774	
2	KB	W/D	F	NING	4/18/96	0.20	37.49	7.62	333.3	ASTM C136	100.0	100.0	100.0	99.5	93.8	84.0	73.1	43.1	32.5	25.6	79.00	3.9	66.00	13.00	29.53	12.91	45	
2	KB	W/D	F	ING	4/18/96	0.20	39.01	7.93	276.7	ASTM C136	100.0	100.0	100.0	99.3	93.1	82.7	70.3	38.3	27.6	20.7	84.70	6.8	66.00	18.70	25.27	9.58	37	
2	KB	W/D	F	NIG	4/18/96	0.41	3.66	1.49	622.7	ASTM C136	100.0	100.0	98.8	92.2	77.8	68.2	58.1	31.7	23.0	18.1	84.70	3.0	66.00	18.70	322.57	88.40	431	
2	KB	W/D	F	IG	4/18/96	0.41	3.66	1.49	410.0	ASTM C136	100.0	100.0	99.7	97.1	90.2	85.0	77.6	50.4	39.5	32.3	87.20	5.2	66.00	21.20	166.87	103.35	290	
2	KING	W/D	F	NING	4/25/96	0.25	42.06	10.68	1216.6	ASTM C136	100.0	100.0	100.0	91.9	60.5	44.2	32.5	16.1	11.7	8.6	99.00	2.7	66.00	33.00	100.55	12.88	117	
2	KING	W/D	F	ING	4/25/96	0.25	49.62	12.60	1086.4	ASTM C136	100.0	100.0	99.5	91.2	59.2	47.3	37.8	17.3	11.3	7.4	86.20	1.9	66.00	20.20	76.45	7.98	88	
2	KING	W/D	F	NIG	4/25/96	0.25	6.10	1.55	3940.8	ASTM C136	100.0	100.0	99.5	94.0	62.0	49.4	38.9	19.6	14.5	11.5	86.60	0.5	66.00	20.60	2,175.63	305.93	2558	
2	KING	W/D	F	IG	4/25/96	0.25	6.10	1.55	1813.1	ASTM C136	100.0	100.0	99.8	99.1	94.7	86.7	73.2	37.2	25.6	18.2	83.90	1.0	66.00	17.90	871.02	224.63	1182	
2	N ST	W/D	F	NING	4/26/96	0.25	27.43	6.97	382.5	ASTM C136	100.0	100.0	100.0	99.9	96.3	78.9	58.9	29.5	22.5	18.0	85.30	3.9	70.50	14.80	42.54	12.01	57	
2	N ST	W/D	F	ING	4/26/96	0.25	28.04	7.12	280.7	ASTM C136	100.0	100.0	100.0	99.8	93.6	77.3	58.0	29.6	22.6	18.1	83.80	4.7	70.50	13.30	30.50	9.00	41	
2	N ST	W/D	F	NIG	4/26/96	0.25	3.66	0.93	799.6	ASTM C136	100.0	100.0	97.6	96.0	93.9	85.6	72.7	41.3	32.0	26.8	94.90	3.1	70.50	24.40	585.26	256.93	887	
2	N ST	W/D	F	IG	4/26/96	0.25	3.66	0.93	321.2	ASTM C136	100.0	100.0	98.1	97.1	92.3	85.6	75.3	44.0	33.4	26.8	82.90	3.9	70.50	12.40	230.26	106.00	359	
2	NS	W/D	F	NING	4/16/96	0.15	48.46	7.39	793.4	ASTM C136	100.0	100.0	100.0	99.7	87.1	55.8	36.5	16.1	11.3	8.2	349.50	35.2	70.50	279.00	95.28	46.58	145	
2	NS	W/D	F	ING	4/16/96	0.15	42.37	6.46	2084.4	ASTM C136	100.0	100.0	100.0	99.1	86.3	59.6	40.7	18.0	12.7	9.3	315.90	12.0	66.00	249.90	281.83	68.73	362	
2	NS	W/D	F	NIG	4/16/96	0.15	9.14	1.39	525.3	ASTM C136	100.0	100.0	100.0	96.5	87.5	71.5	52.5	22.7	13.3	10.0	303.40	45.2	66.00	237.40	326.82	208.05	547	
2	NS	W/D	F	IG	4/16/96	0.15	9.14	1.39	1865.7	ASTM C136	100.0	100.0	99.1	96.1	87.5	77.0	62.8	32.9	23.3	17.1	358.40	15.7	66.00	292.40	1,026.87	438.76	1549	
2	OS	W/D	F	NING	4/24/96	0.51	45.72	23.23	43.2	ASTM C136	100.0	100.0	100.0	97.9	88.2	62.5	40.3	15.7	10.4	6.9	74.30	20.4	65.50	8.80	1.67	0.51	2	
2	OS	W/D	F	ING	4/24/96	0.51	51.51	26.17	288.4	ASTM C136	100.0	100.0	100.0	97.8	82.9	61.1	45.6	20.7	13.8	9.2	77.60	4.2	65.40	12.20	9.50	1.48	11	
2	OS	W/D	F	NIG	4/24/96	0.51	7.32	3.72	723.8	ASTM C136	100.0	100.0	100.0	99.3	98.1	93.4	79.5	37.1	23.8	17.0	93.20	3.8	65.50	27.70	148.42	40.57	202	
2	OS	W/D	F	IG	4/24/96	0.51	6.10	3.10	804.3	ASTM C136	100.0	100.0	99.8	98.9	96.9	93.4	82.3	41.1	26.6	18.1	97.40	3.5	69.50	27.90	190.66	56.02	269	
2	OSD	W/D	F	NING	5/30/96	0.25	64.01	16.26	297.7	ASTM C136	100.0	100.0	100.0	97.8	89.1	77.3	63.1	42.6	34.8	27.8	93.20	7.6	70.47	22.73	11.94	6.49	20	
2	OSD	W/D	F	ING	5/30/96	0.25	70.71	17.96	293.2	ASTM C136	100.0	100.0	100.0	97.0	87.9	74.4	55.1	27.3	20.2	16.0	90.30	6.6	71.05	19.25	13.03	3.68	17	
2	OSD	W/D	F	NIG	5/30/96	0.25	7.92	2.01	1008.2	ASTM C136	100.0	100.0	99.0	97.8	96.5	93.6	84.8	49.5	35.4	25.0	108.30	3.8	70.05	38.25	323.51	144.20	520	
2	OSD	W/D	F	IG	5/30/96	0.25	6.10	1.55	925.3	ASTM C136	100.0	100.0	100.0	98.8	96.9	93.0	81.7	45.1	30.9	21.1	104.40	3.8	69.58	34.82	412.85	148.55	620	
2	RV	W/D	F	NING	4/19/96	0.20	53.95	10.96	433.1	ASTM C136	100.0	100.0	100.0	99.4	92.3	68.0	41.4	17.2	11.7	8.0	76.80	2.5	66.00	10.80	34.88	4.15	40	
2	RV	W/D	F	ING	4/19/96	0.20	55.78	11.33	1737.7	ASTM C136	100.0	100.0	100.0	97.1	87.6	74.8	58.8	28.3	19.7	14.3	85.70	1.1	66.00	19.70	123.11	23.66	155	
2	RV	W/D	F	NIG	4/19/96	0.20	3.66	0.74	1224.9	ASTM C136	100.0	100.0	99.6	97.1	90.6	82.7	67.6	32.9	22.4	16.1	92.00	2.1	66.00	26.00	1,278.92	300.32	1683	
2	RV	W/D	F	IG	4/19/96	0.20	3.66	0.74	810.8	ASTM C136	100.0	100.0	100.0	97.0	90.9	85.2	73.6	35.1	21.7	15.7	90.80	3.1	66.00	24.80	854.19	204.64	1124	
2	s12	W/D	F	NING	4/26/96	0.25	27.43	6.97	391.2	ASTM C136	100.0	100.0	100.0	99.8	97.2	83.3	63.2	34.5	26.9	22.1	89.80	4.9	70.50	19.30	41 04	15.18	59	

Wet/Dry Vacuum Samples

											Percent Passing Sieve (mm)														Loadings (g/m^2)			
round	site_id	sample	to	strata	sampdate	transwidth	transleng	transarea	totdrywt	analysis	38.1	19.0	9.5	4.76	2.00	0.84	0.42	0.149	0.105	0.074	bagwt	pctretain	bagtare	retained	ogs	airsusp	totload	notes
2	s12	W/D	F	ING	4/26/96	0.25	28.04	7.12	306.3	ASTM C136	100.0	100.0	100.0	99.3	91.3	74.7	57.9	29.7	22.1	17.3	83.10	4.1	70.50	12.60	33.50	9.21	45	
2	s12	W/D	F	NIG	4/26/96	0.25	3.66	0.93	442.3	ASTM C136	100.0	100.0	99.4	98.4	95.0	86.6	75.4	38.8	27.4	20.9	77.10	1.5	70.50	6.60	345.64	106.61	483	
2	s12	W/D	F	IG	4/26/96	0.25	3.66	0.93	517.2	ASTM C136	100.0	100.0	100.0	97.9	91.0	80.7	69.1	38.9	28.8	22.9	93.50	4.4	70.50	23.00	396.38	152.24	581	
2	s13	W/D	F	NING	4/24/96	0.25	37.49	9.52	543.1	ASTM C136	100.0	100.0	98.6	97.9	93.8	80.2	65.1	39.2	31.1	26.1	91.70	4.7	66.00	25.70	39.30	17.58	60	
2	s13	W/D	F	ING	4/24/96	0.25	32.92	8.36	835.0	ASTM C136	100.0	100.0	99.2	98.2	91.0	80.6	69.7	41.6	31.5	25.1	83.10	2.0	66.00	17.10	68.41	27.11	102	
2	s13	W/D	F	NIG	4/24/96	0.51	3.66	1.86	424.8	ASTM C136	100.0	100.0	99.1	98.0	95.6	91.7	84.0	54.1	42.8	35.9	81.20	3.6	66.00	15.20	130.77	90.26	237	
2	s13	W/D	F	IG	4/24/96	0.51	3.66	1.86	352.6	ASTM C136	100.0	100.0	98.1	96.9	94.3	90.8	84.1	52.6	40.4	33.2	83.50	5.0	66.00	17.50	113.10	72.42	199	
2	s15	W/D	F	NING	4/25/96	0.51	29.26	14.86	92.9	ASTM C136	100.0	100.0	100.0	98.9	87.7	54.4	38.0	18.6	15.4	11.8	77.60	12.5	66.00	11.60	5.29	1.52	7	
2	s15	W/D	F	ING	4/25/96	0.51	33.53	17.03	193.2	ASTM C136	100.0	100.0	99.3	98.0	73.9	41.1	28.3	13.5	9.9	7.6	76.10	5.2	66.00	10.10	10.22	1.46	12	
2	s15	W/D	F	NIG	4/25/96	0.25	3.66	0.93	2242.0	ASTM C136	100.0	100.0	98.6	96.4	88.0	70.7	52.8	24.7	17.8	14.0	87.30	1.0	66.00	21.30	1,983.70	360.78	2436	
2	s15	W/D	F	IG	4/25/96	0.25	3.66	0.93	908.5	ASTM C136	100.0	100.0	99.8	98.5	89.3	72.4	55.2	24.9	17.3	13.2	80.00	1.5	66.00	14.00	808.72	144.15	993	
2	s16	W/D	F	NING	4/23/96	0.20	29.26	5.95	156.5	ASTM C136	100.0	100.0	100.0	96.2	82.6	66.8	52.1	27.7	21.0	16.8	74.40	4.7	67.00	7.40	20.79	5.67	28	
2	s16	W/D	F	ING	4/23/96	0.20	31.09	6.32	96.3	ASTM C136	100.0	100.0	100.0	98.2	91.0	78.7	68.2	40.8	31.6	24.9	73.50	6.7	67.00	6.50	10.43	4.82	16	
2	s16	W/D	F	NIG	4/23/96	0.41	3.66	1.49	336.4	ASTM C136	100.0	100.0	98.4	96.3	93.2	89.7	84.8	66.2	58.8	54.0	77.80	3.2	67.00	10.80	93.24	129.47	234	
2	s16	W/D	F	IG	4/23/96	0.41	3.66	1.49	369.7	ASTM C136	100.0	100.0	100.0	98.8	95.8	92.5	87.2	65.9	55.7	48.1	83.60	4.5	67.00	16.60	110.18	130.80	260	
2	s21	W/D	F	NING	5/22/96	0.25	106.07	26.94	680.0	ASTM C136	100.0	100.0	100.0	95.3	81.6	68.2	38.5	29.4	24.9	24.1	103.70	4.9	70.24	33.46	18.95	7.32	26	
2	s21	W/D	F	ING	5/22/96	0.25	52.73	13.39	440.5	ASTM C136	100.0	100.0	100.0	98.1	80.4	68.0	51.9	25.4	17.9	14.1	88.50	5.4	64.51	23.99	27.00	6.43	35	
2	s21	W/D	F	NIG	5/22/96	0.25	13.41	3.41	809.1	ASTM C136	100.0	100.0	96.0	92.2	87.7	81.4	73.9	48.9	39.3	33.3	108.60	5.5	64.46	44.14	144.16	92.04	250	
2	s21	W/D	F	IG	5/22/96	0.25	6.71	1.70	439.6	ASTM C136	100.0	100.0	100.0	95.2	86.2	77.2	67.6	41.8	32.1	26.0	88.10	5.4	64.43	23.67	175.28	81.02	272	
2	s36	W/D	F	NING	4/24/96	0.51	52.12	26.48	86.4	ASTM C136	100.0	100.0	100.0	98.1	83.0	62.7	48.1	21.3	13.8	8.7	73.70	9.5	65.50	8.20	2.81	0.59	4	
2	s36	W/D	F	ING	4/24/96	0.51	60.05	30.50	279.8	ASTM C136	100.0	100.0	100.0	98.3	88.7	74.5	58.7	24.7	15.0	8.4	80.00	5.2	65.50	14.50	7.80	1.25	10	
2	s36	W/D	F	NIG	4/24/96	0.51	7.32	3.72	2013.7	ASTM C136	100.0	100.0	100.0	99.1	96.1	89.5	75.6	36.3	24.5	17.6	92.30	1.3	65.50	26.80	409.12	102.58	549	
2	s36	W/D	F	IG	4/24/96	0.51	6.10	3.10	1817.7	ASTM C136	100.0	100.0	99.1	97.3	94.1	88.8	76.8	34.7	21.8	14.2	87.50	1.2	65.50	22.00	459.05	90.46	594	
2	s5	W/D	F	NING	4/19/96	0.20	57.61	11.71	478.8	ASTM C136	100.0	100.0	99.6	98.5	93.6	76.0	52.6	18.8	11.5	7.4	76.50	2.2	66.00	10.50	36.20	3.92	42	
2	s5	W/D	F	ING	4/19/96	0.20	63.09	12.82	533.6	ASTM C136	100.0	100.0	99.5	96.3	82.2	60.5	40.3	14.4	8.9	5.7	77.40	2.1	66.00	11.40	37.92	3.26	43	
2	s5	W/D	F	NIG	4/19/96	0.20	3.66	0.74	1022.3	ASTM C136	100.0	100.0	99.7	96.1	92.1	84.5	68.9	27.6	16.9	11.1	84.20	1.8	66.00	18.20	1,143.03	177.17	1400	
2	s5	W/D	F	IG	4/19/96	0.20	3.66	0.74	922.7	ASTM C136	100.0	100.0	97.8	94.0	84.0	76.4	62.5	26.9	17.0	11.4	82.70	1.8	66.00	16.70	1,030.43	164.00	1264	
2	s9	W/D	F	NING	4/18/96	0.20	37.49	7.62	193.4	ASTM C136	100.0	100.0	98.7	96.6	88.7	77.4	65.6	30.7	20.9	14.8	74.80	4.6	66.00	8.80	20.08	4.91	27	
2	s9	W/D	F	ING	4/18/96	0.20	39.01	7.93	165.1	ASTM C136	100.0	100.0	100.0	96.5	86.5	77.6	68.7	39.7	30.1	23.4	83.00	10.3	66.00	17.00	14.56	7.02	23	
2	s9	W/D	F	NIG	4/18/96	0.41	3.66	1.48	194.5	ASTM C136	100.0	100.0	98.4	94.5	69.8	60.5	53.6	28.0	19.7	13.9	100.30	17.6	66.00	34.30	105.33	41.37	154	
2	s9	W/D	F	IG	4/18/96	0.41	3.66	1.49	273.8	ASTM C136	100.0	100.0	100.0	99.3	96.3	89.7	81.8	53.5	37.1	28.6	85.30	7.0	66.00	19.30	115.86	65.66	197	
3	15A	W/D	F	NING	8/6/96	0.25	29.26	7.43	161.0	ASTM C136	100.0	100.0	100.0	99.3	93.5	67.1	45.0	21.4	15.2	11.0	79.30	8.4	65.80	13.50	18.37	4.20	23	
3	15A	W/D	F	ING	8/6/96	0.25	29.26	7.43	104.3	ASTM C136	100.0	100.0	100.0	99.7	92.7	65.4	44.1	20.2	14.6	11.0	76.40	9.6	66.39	10.01	11.98	2.89	15	
3	15A	W/D	F	NIG	8/6/96	0.25	3.66	0.93	260.9	ASTM C136	100.0	100.0	100.0	98.3	97.2	94.8	86.9	56.7	42.8	30.4	93.50	10.5	66.12	27.38	160.63	114.84	310	

Wet/Dry Vacuum Samples

February 13, 1997

round	site_id	sample	to	strata	sampdate	transwidth	transleng	transarea	totdrywt	analysis	Percent Passing Sieve (mm) 38.1	19.0	9.5	4.76	2.00	0.84	0.42	0.149	0.105	0.074	bagwt	pctretain	bagtare	retained	Loadings (g/m²) ogs	airsusp	totload	notes
3	15A	W/D	F	IG	8/6/96	0.25	3.66	0.93	144.1	ASTM C136	100.0	100.0	95.1	94.2	92.6	87.9	76.7	43.4	30.8	22.1	66.10	-9.5	79.80	0.00	107.33	34.28	155	
3	15A	W/D	T	TOG	8/6/96	0.25	3.66	0.93	458.2	ASTM C136	100.0	100.0	89.2	79.9	74.8	70.2	63.5	37.8	26.2	20.4	93.00	5.8	66.50	26.50	363.98	129.14	522	
3	15A	W/D	T	TONG	8/6/96	0.25	14.63	3.72	265.6	ASTM C136	100.0	100.0	95.4	88.7	79.4	53.7	36.4	18.3	13.4	10.5	88.20	8.2	66.38	21.82	61.90	13.38	77	
3	15A	W/D	T	NTOG	8/6/96	0.25	3.66	0.93	144.6	ASTM C136	100.0	100.0	100.0	99.2	96.8	93.4	86.1	51.1	34.6	24.3	75.30	6.3	66.25	9.05	101.79	47.56	165	
3	15A	W/D	T	NTONG	8/6/96	0.25	29.26	7.43	99.1	ASTM C136	100.0	100.0	100.0	99.2	94.2	76.0	54.4	25.8	18.1	13.9	74.60	8.4	66.28	8.32	10.92	2.97	14	
3	36B	W/D	F	NING	7/16/96	0.51	53.04	26.94	86.1	ASTM C136	100.0	100.0	100.0	100.0	93.0	57.5	37.3	19.5	15.6	12.7	82.10	18.4	66.25	15.85	2.70	0.99	4	
3	36B	W/D	F	ING	7/16/96	0.25	76.20	19.35	1017.5	ASTM C136	100.0	100.0	89.5	65.0	44.0	31.3	22.8	10.8	7.8	6.1	93.20	2.7	65.30	27.90	48.47	4.65	54	
3	36B	W/D	F	NIG	7/16/96	0.25	7.32	1.86	2390.3	ASTM C136	100.0	100.0	100.0	95.9	85.8	68.6	51.1	25.5	18.2	13.6	98.90	1.4	65.21	33.69	1,052.31	193.09	1305	
3	36B	W/D	F	IG	7/16/96	0.25	6.10	1.55	3152.4	ASTM C136	100.0	100.0	97.5	93.3	86.3	74.5	60.3	38.4	32.3	28.2	124.70	1.9	66.34	58.36	1,378.05	611.70	2073	
3	A	W/D	F	NIG	7/26/96	0.25	3.66	0.93	84.2	ASTM C136	100.0	100.0	100.0	98.1	97.4	93.3	82.5	51.2	38.2	28.6	80.07	14.6	67.80	12.27	56.01	39.13	104	
3	A	W/D	F	IG	7/26/96	0.25	3.66	0.93	234.0	ASTM C136	100.0	100.0	100.0	99.4	97.2	92.1	79.9	44.4	28.8	19.0	90.10	9.8	67.25	22.85	179.34	72.45	276	
3	A	W/D	T	TOG	7/26/96	0.25	3.66	0.93	626.1	ASTM C136	100.0	100.0	84.7	68.7	48.9	42.9	35.3	17.7	13.2	10.8	131.40	10.3	66.82	64.58	584.97	142.30	743	
3	A	W/D	T	TONG	7/26/96	0.25	12.50	3.17	45.7	ASTM C136	100.0	100.0	100.0	96.1	88.4	81.6	70.5	42.2	28.9	19.3	80.70	28.9	67.50	13.20	10.24	6.94	19	
3	A	W/D	T	NTOG	7/26/96	0.25	3.66	0.93	58.9	ASTM C136	100.0	100.0	100.0	100.0	99.2	93.9	83.9	56.2	43.8	34.8	79.80	21.6	67.10	12.70	35.63	35.73	77	
3	A	W/D	T	NTONG	7/26/96	0.25	12.50	3.17	25.5	ASTM C136	100.0	100.0	100.0	100.0	98.4	91.0	76.9	45.5	36.9	26.3	74.60	30.0	66.94	7.66	5.07	4.53	10	
3	CO	W/D	F	NING	8/6/96	0.25	29.26	7.43	117.4	ASTM C136	100.0	100.0	100.0	95.4	91.0	80.0	62.8	32.5	24.2	19.2	84.10	14.6	66.97	17.13	11.97	5.34	18	
3	CO	W/D	F	ING	8/6/96	0.25	31.09	7.90	181.9	ASTM C136	100.0	100.0	100.0	97.5	92.2	81.7	66.5	38.5	30.7	26.0	94.80	16.4	64.90	29.90	15.96	9.78	27	
3	CO	W/D	F	NIG	8/6/96	0.25	3.66	0.93	391.0	ASTM C136	100.0	100.0	100.0	97.4	92.7	81.6	66.5	36.4	28.0	23.2	84.80	5.1	64.88	19.92	303.03	119.08	442	
3	CO	W/D	F	IG	8/6/96	0.25	3.66	0.93	329.2	ASTM C136	100.0	100.0	100.0	96.5	92.1	82.1	66.7	32.8	23.8	19.1	80.60	4.8	64.70	15.90	270.01	84.79	371	
3	COL	W/D	F	NING	8/6/96	0.25	29.26	7.43	122.8	ASTM C136	100.0	100.0	100.0	99.8	95.1	85.3	65.9	29.6	20.5	15.1	78.60	10.4	65.85	12.75	13.14	4.21	18	
3	COL	W/D	F	ING	8/6/96	0.25	29.26	7.43	80.5	ASTM C136	100.0	100.0	94.5	91.3	82.1	72.4	56.9	27.0	19.9	14.0	76.70	11.9	67.16	9.54	8.68	2.80	12	
3	COL	W/D	F	NIG	8/6/96	0.25	3.66	0.93	447.9	ASTM C136	100.0	100.0	99.5	97.0	93.7	87.8	79.2	56.9	49.2	43.6	83.30	4.0	65.40	17.90	244.91	229.47	501	
3	COL	W/D	F	IG	8/6/96	0.25	3.66	0.93	142.5	ASTM C136	100.0	100.0	98.1	91.6	81.8	75.4	67.6	41.1	30.6	22.2	88.20	16.0	65.43	22.77	106.45	58.56	178	
3	DEB	W/D	F	NIGO	7/24/96	0.25	7.32	1.86	291.4	ASTM C136	100.0	100.0	100.0	99.6	97.4	92.7	82.4	43.0	28.7	19.5	90.40	8.0	67.12	23.28	111.82	43.11	169	
3	DEB	W/D	F	IGO	7/24/96	0.25	6.71	1.70	597.9	ASTM C136	100.0	100.0	100.0	99.5	98.4	94.3	79.8	37.2	26.5	19.2	104.20	5.9	68.79	35.41	258.06	88.21	372	
3	DEN	W/D	F	NIGO	7/26/96	0.25	3.66	0.93	1649.4	ASTM C136	100.0	100.0	100.0	95.5	87.7	79.6	64.8	29.4	18.6	11.6	87.90	1.2	67.37	20.53	1,445.17	228.04	1797	
3	DEN	W/D	F	IGO	7/26/96	0.25	3.66	0.93	1721.9	ASTM C136	100.0	100.0	95.7	91.2	84.4	78.6	68.3	32.7	20.2	12.3	94.20	1.6	67.30	26.90	1,479.04	256.93	1882	
3	DM	W/D	F	NING	7/16/96	0.25	72.85	18.50	289.4	ASTM C136	100.0	100.0	100.0	91.9	77.1	59.0	42.9	21.2	15.7	11.7	84.30	6.1	66.68	17.62	13.18	2.78	17	
3	DM	W/D	F	ING	7/16/96	0.25	84.12	21.37	294.0	ASTM C136	100.0	100.0	94.2	86.4	65.7	47.6	32.7	15.1	11.6	9.1	94.50	8.8	68.57	25.93	12.16	2.47	15	
3	DM	W/D	F	NIG	7/16/96	0.25	7.32	1.86	2322.1	ASTM C136	100.0	100.0	100.0	99.4	97.6	90.2	36.5	26.9	21.1	20.8	110.90	1.9	66.59	44.31	986.05	283.79	1274	
3	DM	W/D	F	IG	7/16/96	0.25	6.10	1.55	1500.6	ASTM C136	100.0	100.0	100.0	98.9	97.4	89.6	71.2	30.1	19.0	11.6	91.40	1.7	66.25	25.15	784.85	128.64	985	
3	E ST	W/D	F	NING	8/7/96	0.25	27.43	6.97	11.3	ASTM C136	100.0	100.0	100.0	100.0	96.5	75.2	47.8	15.0	12.4	8.8	70.10	43.7	65.16	4.94	1.42	0.85	2	
3	E ST	W/D	F	ING	8/7/96	0.25	29.87	7.59	24.3	ASTM C136	100.0	100.0	100.0	100.0	88.5	76.1	65.0	49.8	45.3	44.0	68.80	13.6	65.49	3.31	1.75	1.85	4	
3	E ST	W/D	F	NIG	8/7/96	0.25	3.66	0.93	70.9	ASTM C136	100.0	100.0	93.7	87.7	76.7	63.5	45.6	18.3	11.7	8.7	71.70	7.3	66.55	5.15	67.39	12.18	82	

Wet/Dry Vacuum Samples

February 13, 1997

											Percent Passing Sieve (mm)														Loadings (g/m²)			
round	site_id	sample	to	strata	sampdate	transwidth	transleng	transarea	totdrywt	analysis	38.1	19.0	9.5	4.76	2.00	0.84	0.42	0.149	0.105	0.074	bagwt	pctretain	bagtare	retained	ogs	airsusp	totload	notes
3	E ST	W/D	F	IG	8/7/96	0.25	3.66	0.93	304.3	ASTM C136	100.0	100.0	100.0	90.2	79.0	59.7	38.4	13.2	7.8	5.4	73.90	2.8	65.35	8.55	302.00	26.89	337	
3	IOW	W/D	F	NIGO	7/24/96	0.25	3.66	0.93	2029.1	ASTM C136	100.0	100.0	100.0	93.5	80.6	68.5	54.0	20.5	10.3	5.8	126.20	2.9	67.30	58.90	1,959.14	190.08	2248	
3	IOW	W/D	F	IGO	7/24/96	0.25	3.66	0.93	116.3	ASTM C136	100.0	100.0	98.2	90.9	81.1	73.3	61.6	25.5	14.7	9.2	76.70	8.0	67.44	9.26	106.78	21.48	135	
3	KA	W/D	F	NING	7/9/96	0.25	37.49	9.52	294.3	ASTM C136	100.0	100.0	97.9	92.0	88.3	74.5	57.8	31.2	22.7	16.8	90.40	7.5	68.24	22.16	23.89	7.52	33	
3	KA	W/D	F	ING	7/9/96	0.25	40.54	10.30	252.3	ASTM C136	100.0	100.0	100.0	98.3	91.2	78.9	61.2	31.9	23.0	16.5	90.20	9.2	66.98	23.22	18.87	6.30	27	
3	KA	W/D	F	NIG	7/9/96	0.25	3.66	0.93	1175.4	ASTM C136	100.0	100.0	91.8	87.2	81.2	76.6	63.4	35.9	25.9	19.7	100.80	2.9	66.83	33.97	937.50	285.81	1302	
3	KA	W/D	F	IG	7/9/96	0.25	3.66	0.93	870.0	ASTM C136	100.0	100.0	91.0	88.5	82.5	76.2	66.1	37.4	26.9	19.6	134.20	7.9	65.22	68.98	684.55	257.80	1011	
3	KB	W/D	F	NING	8/8/96	0.25	37.49	9.52	118.8	ASTM C136	100.0	100.0	100.0	99.5	95.5	72.6	48.0	18.6	12.7	9.3	83.40	13.8	67.00	16.40	10.89	2.88	14	
3	KB	W/D	F	ING	8/8/96	0.25	39.01	9.91	82.1	ASTM C136	100.0	100.0	100.0	98.9	93.1	68.8	43.5	16.6	11.0	8.5	73.40	7.9	66.94	6.46	7.37	1.36	9	
3	KB	W/D	F	NIG	8/8/96	0.25	3.66	0.93	309.4	ASTM C136	100.0	100.0	94.5	90.9	86.8	80.7	70.9	44.0	35.1	29.6	101.20	11.2	66.66	34.54	216.14	135.76	370	
3	KB	W/D	F	IG	8/8/96	0.25	3.66	0.93	80.7	ASTM C136	100.0	100.0	100.0	97.4	93.7	89.1	81.0	48.2	33.6	23.9	77.50	13.6	66.54	10.96	57.68	32.56	99	
3	KB	W/D	T	TOG	8/8/96	0.25	3.66	0.93	149.8	ASTM C136	100.0	100.0	97.7	90.9	79.5	70.4	59.0	30.6	22.0	16.2	83.10	12.0	65.11	17.99	125.77	45.49	181	
3	KB	W/D	T	TONG	8/8/96	0.25	37.49	9.52	100.7	ASTM C136	100.0	100.0	100.0	97.8	91.6	71.9	49.1	20.6	14.0	10.8	76.40	11.3	65.05	11.35	9.09	2.33	12	
3	KB	W/D	T	NTOG	8/8/96	0.25	3.66	0.93	88.2	ASTM C136	100.0	100.0	100.0	96.9	94.0	90.4	84.0	55.4	41.5	30.3	78.40	13.5	66.52	11.88	55.54	41.55	108	
3	KB	W/D	T	NTONG	8/8/96	0.25	37.49	9.52	83.6	ASTM C136	100.0	100.0	100.0	98.4	95.2	70.8	43.7	16.6	11.4	8.7	73.70	9.7	65.56	8.14	7.78	1.62	10	
3	KING	W/D	F	NING	7/16/96	0.25	44.32	11.26	303.5	ASTM C136	100.0	100.0	99.3	98.2	87.6	70.0	54.7	28.2	20.5	14.9	90.10	8.1	65.38	24.72	21.43	6.21	29	
3	KING	W/D	F	ING	7/16/96	0.25	49.62	12.60	233.8	ASTM C136	100.0	100.0	98.8	96.1	88.2	64.8	47.5	24.9	17.5	11.9	85.40	8.0	66.66	18.74	15.30	3.69	20	
3	KING	W/D	F	NIG	7/16/96	0.25	3.66	0.93	3307.8	ASTM C136	100.0	100.0	100.0	93.6	81.6	65.3	48.3	19.4	12.2	7.9	107.20	1.2	66.48	40.72	3,126.10	325.11	3604	
3	KING	W/D	F	IG	7/16/96	0.25	6.10	1.55	675.3	ASTM C136	100.0	100.0	100.0	97.2	92.2	84.3	72.8	35.5	22.9	14.6	90.60	3.6	66.42	24.18	336.19	79.28	452	
3	LKOT	W/D	F	NIGO	8/7/96	0.25	3.66	0.93	364.1	ASTM C136	100.0	100.0	100.0	99.6	97.6	92.2	78.0	44.5	33.3	26.5	97.80	8.6	66.66	31.14	261.41	137.38	425	
3	LKOT	W/D	F	IGO	8/7/96	0.25	3.66	0.93	438.1	ASTM C136	100.0	100.0	100.0	98.5	94.9	86.8	81.2	66.7	40.6	18.9	101.50	8.0	66.64	34.86	280.11	126.65	509	
3	MUL	W/D	F	NIGO	7/24/96	0.25	7.32	1.86	392.4	ASTM C136	100.0	100.0	100.0	99.8	98.0	94.2	84.6	42.7	27.2	18.3	113.50	11.4	68.60	44.90	153.74	62.81	235	
3	MUL	W/D	F	IGO	7/24/96	0.25	6.10	1.55	712.4	ASTM C136	100.0	100.0	100.0	99.4	97.8	93.6	80.4	39.0	26.4	12.1	117.60	6.9	68.72	48.88	338.56	87.22	492	
3	N LTS	W/D	F	NING	7/26/96	0.25	94.52	24.01	84.5	ASTM C136	100.0	100.0	100.0	98.6	71.4	42.4	24.5	13.0	3.2	0.6	72.80	6.5	67.30	5.50	3.41	0.25	4	
3	N LTS	W/D	F	ING	7/26/96	0.25	49.04	12.46	90.0	ASTM C136	100.0	100.0	100.0	97.7	83.2	50.2	30.9	9.8	6.0	4.2	72.60	5.5	67.67	4.93	6.79	0.70	8	
3	N LTS	W/D	F	NIG	7/26/96	0.25	8.53	2.17	1412.3	ASTM C136	100.0	100.0	95.7	91.7	81.0	68.3	50.6	18.9	10.8	6.7	94.30	1.9	66.89	27.41	581.23	56.30	664	
3	N LTS	W/D	F	IG	7/26/96	0.25	4.27	1.08	1075.3	ASTM C136	100.0	100.0	98.4	96.1	90.6	77.9	58.5	23.4	13.8	8.9	86.30	1.8	67.43	18.87	854.94	105.68	1009	
3	N ST	W/D	F	NING	7/8/96	0.25	27.43	6.97	548.9	ASTM C136	100.0	100.0	97.5	67.4	63.4	51.4	30.3	8.6	5.5	3.9	94.90	4.9	67.80	27.10	74.44	6.96	83	
3	N ST	W/D	F	ING	7/8/96	0.25	28.04	7.12	831.1	ASTM C136	100.0	100.0	96.5	91.5	84.0	75.0	60.8	32.4	24.8	19.6	77.90	1.4	66.55	11.35	87.74	24.46	118	
3	N ST	W/D	F	NIG	7/8/96	0.25	3.66	0.93	1364.9	ASTM C136	100.0	100.0	91.0	85.6	77.7	67.3	53.3	26.0	19.1	14.6	92.10	1.9	66.40	25.70	1,188.55	242.16	1497	
3	N ST	W/D	F	IG	7/8/96	0.25	3.66	0.93	374.7	ASTM C136	100.0	100.0	98.8	95.5	87.1	69.7	40.9	12.3	7.9	5.4	95.20	7.5	67.18	28.02	371.46	51.94	433	
3	NLTB	W/D	F	NIGO	7/26/96	0.25	3.66	0.93	252.8	ASTM C136	100.0	100.0	95.8	93.4	86.2	72.9	52.5	22.2	14.1	8.8	81.70	5.5	67.68	14.02	233.74	39.04	287	
3	NLTB	W/D	F	IGO	7/26/96	0.25	3.66	0.93	729.9	ASTM C136	100.0	100.0	99.1	93.0	86.3	73.2	52.8	21.3	12.8	8.0	90.40	3.2	67.09	23.31	685.09	87.94	811	
3	NS	W/D	F	NING	7/16/96	0.25	39.01	9.91	584.0	ASTM C136	100.0	100.0	100.0	99.7	88.5	63.9	46.5	27.7	22.8	19.3	90.20	4.0	66.75	23.45	45.49	13.74	61	

Street Sediment Sample Database (SEDDATA.DBF)

Wet/Dry Vacuum Samples

											Percent Passing Sieve (mm)															Loadings (g/m²)			
round	site_id	sample	to	strata	sampdate	transwidth	transleng	transarea	totdrywt	analysis	38.1	19.0	9.5	4.76	2.00	0.84	0.42	0.149	0.105	0.074	bagwt	pctretain	bagtare	retained	ogs	airsusp	totload	notes
3	NS	W/D	F	ING	7/16/96	0.25	41.15	10.45	671.7	ASTM C136	100.0	100.0	97.7	94.2	84.3	63.5	45.7	23.5	21.5	13.7	95.20	4.3	66.55	28.65	50.45	11.55	67	
3	NS	W/D	F	NIG	7/16/96	0.25	9.14	2.32	4148.7	ASTM C136	100.0	100.0	97.1	92.7	80.4	65.8	48.9	20.7	14.1	10.2	92.70	0.6	66.67	26.03	1,534.39	193.40	1797	
3	NS	W/D	F	IG	7/16/96	0.25	10.36	2.63	8844.0	ASTM C136	100.0	100.0	100.0	97.1	87.6	73.0	54.7	23.7	16.1	11.6	88.50	0.2	67.21	21.29	2,819.25	397.88	3368	
3	OS	W/D	F	NING	7/17/96	0.51	45.72	23.23	18.1	ASTM C136	100.0	100.0	100.0	100.0	94.5	69.1	47.5	26.5	18.8	13.8	65.20	0.8	65.05	0.15	0.63	0.11	1	
3	OS	W/D	F	ING	7/17/96	0.51	51.51	26.17	46.6	ASTM C136	100.0	100.0	100.0	95.9	87.6	68.7	52.1	20.8	15.0	13.1	76.00	21.8	65.82	10.18	1.51	0.62	2	
3	OS	W/D	F	NIG	7/17/96	0.25	7.32	1.86	344.3	ASTM C136	100.0	100.0	100.0	96.2	92.2	78.9	58.6	20.9	10.0	3.3	83.10	5.0	65.72	17.38	166.77	15.47	195	
3	OS	W/D	F	IG	7/17/96	0.25	6.10	1.55	324.1	ASTM C136	100.0	100.0	98.0	96.5	92.2	81.6	62.8	27.3	16.8	10.6	79.50	4.3	65.59	13.91	174.12	31.16	218	
3	OSD	W/D	F	NING	7/17/96	0.25	64.01	16.26	487.9	ASTM C136	100.0	100.0	100.0	89.6	60.9	43.5	29.4	12.9	9.2	7.2	78.20	2.7	65.26	12.94	27.25	2.96	31	
3	OSD	W/D	F	ING	7/17/96	0.25	70.71	17.96	271.4	ASTM C136	100.0	100.0	100.0	90.9	59.1	41.4	27.4	10.9	7.7	6.3	81.80	6.2	64.90	16.90	13.95	1.89	16	
3	OSD	W/D	F	NIG	7/17/96	0.25	7.32	1.86	3057.9	ASTM C136	100.0	100.0	100.0	96.4	89.0	78.3	57.6	24.5	16.2	10.9	92.40	0.9	65.64	26.76	1,379.14	193.79	1660	
3	OSD	W/D	F	IG	7/17/96	0.25	6.10	1.55	2851.4	ASTM C136	100.0	100.0	100.0	95.7	87.5	76.7	58.4	25.4	16.6	11.1	88.40	0.8	65.25	23.15	1,535.53	219.32	1856	
3	RV	W/D	F	NING	7/17/96	0.25	53.95	13.70	172.7	ASTM C136	100.0	100.0	100.0	98.7	96.1	82.4	53.0	13.3	8.2	5.4	81.10	8.5	66.35	14.75	11.57	1.76	14	
3	RV	W/D	F	ING	7/17/96	0.25	55.78	14.17	687.8	ASTM C136	100.0	100.0	100.0	98.0	90.7	83.8	63.0	22.0	14.0	9.4	84.70	2.7	66.29	18.41	41.75	5.86	50	
3	RV	W/D	F	NIG	7/17/96	0.25	3.66	0.93	412.5	ASTM C136	100.0	100.0	95.6	89.6	78.7	73.0	60.6	28.6	18.1	13.3	88.70	5.2	67.15	21.55	363.64	82.25	467	
3	RV	W/D	F	IG	7/17/96	0.25	3.66	0.93	581.7	ASTM C136	100.0	100.0	95.8	91.8	81.3	79.5	69.1	35.4	24.9	18.1	94.40	5.1	64.97	29.43	470.23	145.01	658	
3	SP	W/D	F	NIGO	7/24/96	0.25	7.32	1.86	454.2	ASTM C136	100.0	100.0	100.0	95.3	88.9	78.4	59.8	26.2	18.4	14.2	99.10	6.9	67.80	31.30	199.47	51.56	261	
3	SP	W/D	F	IGO	7/24/96	0.25	6.10	1.55	126.9	ASTM C136	100.0	100.0	100.0	97.2	85.4	69.0	50.5	21.2	13.5	9.3	87.40	14.8	68.56	18.84	70.88	19.79	94	
3	s12	W/D	F	NING	7/8/96	0.25	27.43	6.97	261.0	ASTM C136	100.0	100.0	100.0	98.8	93.4	75.6	49.0	19.0	13.5	10.3	77.10	3.8	67.28	9.82	32.40	5.27	39	
3	s12	W/D	F	ING	7/8/96	0.25	28.04	7.12	238.0	ASTM C136	100.0	100.0	100.0	97.7	92.5	73.2	47.3	17.3	10.3	6.9	75.60	4.6	64.55	11.05	29.97	3.86	35	
3	s12	W/D	F	NIG	7/8/96	0.25	3.66	0.93	292.0	ASTM C136	100.0	100.0	98.7	92.0	84.6	76.2	62.7	30.9	20.7	13.9	87.80	6.2	69.77	18.03	249.24	63.10	334	
3	s12	W/D	F	IG	7/8/96	0.25	3.66	0.93	490.2	ASTM C136	100.0	100.0	96.5	87.4	75.7	64.9	51.1	23.6	16.4	11.7	91.30	4.4	69.87	21.43	441.11	84.80	551	
3	s13	W/D	F	NING	7/9/96	0.25	32.92	8.36	283.6	ASTM C136	100.0	100.0	100.0	98.6	96.8	86.6	73.7	43.0	32.9	26.4	94.60	10.2	65.54	29.06	22.76	12.43	37	
3	s13	W/D	F	ING	7/9/96	0.25	37.49	9.52	252.9	ASTM C136	100.0	100.0	100.0	99.6	96.3	82.0	68.0	38.6	28.9	22.4	98.00	11.8	68.24	29.76	18.88	9.07	30	
3	s13	W/D	F	NIG	7/9/96	0.25	3.66	0.93	202.4	ASTM C136	100.0	100.0	95.2	89.6	84.3	79.8	70.9	38.4	27.2	20.2	89.60	11.4	66.60	23.00	158.60	68.76	243	
3	s13	W/D	F	IG	7/9/96	0.25	3.66	0.93	158.3	ASTM C136	100.0	100.0	97.9	94.1	89.3	84.1	76.0	43.6	32.3	25.3	88.90	13.7	67.15	21.75	115.36	66.52	194	
3	s13	W/D	T	TOG	8/8/96	0.25	3.66	0.93	413.6	ASTM C136	100.0	100.0	94.2	88.6	77.8	66.0	54.4	30.1	23.1	18.9	94.60	6.7	66.90	27.70	342.35	113.96	475	
3	s13	W/D	T	TONG	8/8/96	0.25	32.92	8.36	457.1	ASTM C136	100.0	100.0	100.0	98.2	94.0	70.3	51.3	25.9	19.9	16.7	93.70	6.0	66.47	27.23	43.79	12.39	58	
3	s13	W/D	T	NTOG	8/8/96	0.25	3.66	0.93	39.3	ASTM C136	100.0	100.0	100.0	98.5	95.4	91.9	80.2	42.0	30.0	24.2	77.50	27.9	66.55	10.95	29.61	22.02	54	
3	s13	W/D	T	NTONG	8/8/96	0.25	32.92	8.36	235.3	ASTM C136	100.0	100.0	100.0	95.6	90.4	73.9	22.9	14.6	13.0	10.4	91.30	10.2	67.21	24.09	24.48	5.81	31	
3	s15	W/D	F	NING	8/7/96	0.25	29.26	7.43	13.6	ASTM C136	100.0	100.0	100.0	100.0	89.7	56.6	36.8	13.2	11.0	5.1	72.10	41.2	66.50	5.60	1.63	0.85	3	
3	s15	W/D	F	ING	8/7/96	0.25	33.53	8.52	18.8	ASTM C136	100.0	100.0	100.0	97.3	79.8	50.5	35.1	14.9	11.7	8.5	64.90	-2.2	65.31	0.00	1.95	0.19	2	
3	s15	W/D	F	NIG	8/7/96	0.25	3.66	0.93	579.2	ASTM C136	100.0	100.0	100.0	98.0	89.0	76.8	58.8	26.6	19.0	14.3	89.80	4.2	65.30	24.50	504.99	115.52	650	
3	s15	W/D	F	IG	8/7/96	0.25	3.66	0.93	664.1	ASTM C136	100.0	100.0	98.1	92.4	83.0	71.1	56.4	26.3	18.6	13.3	84.10	2.9	64.73	19.37	581.87	115.92	736	
3	s16	W/D	F	NING	8/6/96	0.25	29.26	7.43	117.0	ASTM C136	100.0	100.0	100.0	99.2	93.2	69.7	48.4	23.4	16.9	13.2	76.70	8.8	66.42	10.28	13.08	3.46	17	

Street Sediment Sample Database (SEDDATA.DBF)

Wet/Dry Vacuum Samples

February 13, 1997

											Percent Passing Sieve (mm)														Loadings (g/m²)			
round	site_id	sample	to	strata	sampdate	transwidth	transleng	transarea	totdrywt	analysis	38.1	19.0	9.5	4.76	2.00	0.84	0.42	0.149	0.105	0.074	bagwt	pctretain	bagtare	retained	ogs	airsusp	totload	notes
3	s16	W/D	F	ING	8/6/96	0.25	30.94	7.86	97.7	ASTM C136	100.0	100.0	100.0	98.2	88.7	68.2	49.1	24.1	16.7	12.8	77.30	10.7	66.85	10.45	10.36	2.92	14	
3	s16	W/D	F	NIG	8/6/96	0.25	3.66	0.93	223.6	ASTM C136	100.0	100.0	95.9	92.6	87.0	79.7	65.0	33.9	25.0	19.4	98.10	14.1	66.51	31.59	180.51	80.70	275	
3	s16	W/D	F	IG	8/6/96	0.25	3.66	0.93	205.5	ASTM C136	100.0	100.0	100.0	87.4	63.1	54.3	44.4	25.0	19.1	15.3	80.60	7.0	66.12	14.48	178.95	49.43	237	
3	s16	W/D	T	TOG	8/6/96	0.25	4.88	1.24	577.9	ASTM C136	100.0	100.0	100.0	95.4	88.4	78.7	67.5	41.6	33.7	28.6	92.80	4.5	66.81	25.99	309.39	154.45	488	
3	s16	W/D	T	TONG	8/6/96	0.25	28.04	7.12	136.3	ASTM C136	100.0	100.0	100.0	99.6	91.4	60.3	38.5	17.8	13.4	10.7	80.50	10.1	66.71	13.79	16.57	3.98	21	
3	s16	W/D	T	NTOG	8/6/96	0.25	4.88	1.24	127.2	ASTM C136	100.0	100.0	100.0	99.5	96.1	90.5	79.9	50.9	39.8	32.0	81.20	11.6	66.50	14.70	61.83	44.74	115	
3	s16	W/D	T	NTONG	8/6/96	0.25	28.04	7.12	76.5	ASTM C136	100.0	100.0	100.0	99.2	89.5	73.5	51.9	24.7	17.9	13.7	78.10	15.0	66.65	11.45	8.82	3.08	12	
3	s20	W/D	F	NIGO	8/7/96	0.25	3.66	0.93	200.1	ASTM C136	100.0	100.0	100.0	96.2	86.2	81.0	74.8	44.4	30.9	23.3	86.80	11.0	64.80	22.00	148.83	73.87	239	
3	s20	W/D	F	IGO	8/7/96	0.25	3.66	0.93	1000.4	ASTM C136	100.0	100.0	98.6	92.4	73.8	65.1	55.4	31.3	24.4	17.2	90.10	2.5	65.59	24.51	814.08	211.60	1103	
3	s21	W/D	F	NING	8/12/96	0.25	106.07	26.94	931.6	ASTM C136	100.0	100.0	99.2	96.3	88.0	65.2	44.3	18.5	12.8	10.1	93.60	3.0	65.34	28.26	30.15	4.54	36	
3	s21	W/D	F	ING	8/12/96	0.25	52.73	13.39	123.8	ASTM C136	100.0	100.0	100.0	96.8	79.8	59.3	40.4	16.2	11.2	8.4	75.20	8.0	65.35	9.85	8.21	1.51	10	
3	s21	W/D	F	NIG	8/12/96	0.25	13.41	3.41	1603.2	ASTM C136	100.0	100.0	94.4	88.4	80.1	66.9	52.5	26.7	19.0	15.5	122.30	3.5	65.43	56.87	381.18	89.64	487	
3	s21	W/D	F	IG	8/12/96	0.25	6.71	1.70	189.8	ASTM C136	100.0	100.0	93.0	89.6	84.4	77.0	68.9	44.8	32.8	32.0	82.80	8.8	66.05	16.75	74.90	45.50	121	
3	s36	W/D	F	NING	7/17/96	0.51	52.12	26.48	63.6	ASTM C136	100.0	100.0	100.0	100.0	89.0	67.0	48.3	27.5	22.3	19.3	78.90	21.4	65.31	13.59	1.87	0.98	3	
3	s36	W/D	F	ING	7/17/96	0.51	60.05	30.50	165.8	ASTM C136	100.0	100.0	100.0	98.3	88.2	69.3	48.0	21.5	15.6	12.0	79.70	8.8	65.13	14.57	4.59	1.13	6	
3	s36	W/D	F	NIG	7/17/96	0.25	7.32	1.86	1191.8	ASTM C136	100.0	100.0	100.0	96.7	86.8	72.5	54.8	25.3	17.5	12.6	101.80	3.1	65.00	36.80	529.17	100.62	661	
3	s36	W/D	F	IG	7/17/96	0.25	6.10	1.55	880.2	ASTM C136	100.0	100.0	100.0	97.4	92.2	83.2	67.7	29.1	17.7	12.1	109.40	5.1	64.77	44.63	467.75	97.59	597	
3	s5	W/D	F	NING	7/17/96	0.25	57.61	14.63	219.1	ASTM C136	100.0	100.0	100.0	99.8	62.7	53.4	37.3	15.6	10.4	8.1	79.60	5.8	66.90	12.70	13.42	2.08	16	
3	s5	W/D	F	ING	7/17/96	0.25	63.09	16.03	199.4	ASTM C136	100.0	100.0	99.6	98.8	93.9	78.2	55.4	19.1	12.0	7.9	78.50	6.5	65.62	12.88	10.95	1.79	13	
3	s5	W/D	F	NIG	7/17/96	0.25	3.66	0.93	143.1	ASTM C136	100.0	100.0	98.0	97.1	94.0	89.7	68.7	66.2	41.8	27.4	94.60	20.3	65.59	29.01	89.65	73.43	185	
3	s5	W/D	F	IG	7/17/96	0.25	3.66	0.93	170.6	ASTM C136	100.0	100.0	100.0	98.8	96.3	93.6	82.1	37.3	23.6	15.7	82.50	9.9	65.69	16.81	140.29	46.92	202	
3	s6	W/D	F	NIGO	7/24/96	0.25	3.66	0.93	94.7	ASTM C136	100.0	100.0	98.4	93.7	92.5	88.2	76.0	36.2	23.8	15.5	89.80	22.1	68.86	20.94	77.67	38.34	124	
3	s6	W/D	F	IGO	7/24/96	0.25	3.66	0.93	238.5	ASTM C136	100.0	100.0	98.0	93.8	88.7	82.0	70.4	34.5	23.0	15.3	88.20	8.3	68.50	19.70	197.67	60.48	278	
3	s9	W/D	F	NING	8/8/96	0.25	37.49	9.52	37.6	ASTM C136	100.0	100.0	100.0	98.1	93.6	81.1	53.5	17.8	12.5	9.0	70.80	10.8	66.75	4.05	3.45	0.78	4	
3	s9	W/D	F	ING	8/8/96	0.25	39.01	9.91	33.0	ASTM C136	100.0	100.0	100.0	99.4	94.2	79.7	54.8	21.2	13.9	10.3	71.90	16.5	66.45	5.45	2.87	0.89	4	
3	s9	W/D	F	NIG	8/8/96	0.25	3.66	0.93	36.9	ASTM C136	100.0	100.0	100.0	100.0	95.9	91.9	72.9	31.2	19.2	12.7	73.30	17.8	66.72	6.58	32.09	12.13	47	
3	s9	W/D	F	IG	8/8/96	0.25	3.66	0.93	62.9	ASTM C136	100.0	100.0	100.0	100.0	86.8	71.9	63.8	53.1	25.6	16.4	74.40	12.4	66.60	7.80	50.37	19.50	76	

Street Sediment Sample Database (AQDATA.DBF)

HEPA Samples

											Percent Passing Sieve (mm)														Loadings (g/m^2)			
round	site_id	sample	to	strata	sampdate	transwidth	transleng	transarea	totdrywt	analysis	38.1	19.0	9.5	4.76	2.00	0.84	0.42	0.149	0.105	0.074	bagwt	pctretain	bagtare	retained	ogs	airsusp	totload	notes
1	15A	HEPA	F	ING	4/10/96	0.25	29.26	7.43	1488.0	ASTM C136	100.0	100.0	99.9	89.7	38.1	23.4	19.3	11.6	8.9	7.3	0.00	0.0	0.00	0.00	182.39	14.62	200	3 FILTERS
1	15A	HEPA	F	NING	4/10/96	0.25	29.26	7.43	372.4	ASTM C136	100.0	100.0	99.0	87.6	62.3	42.9	33.9	18.6	14.6	12.1	0.00	0.0	0.00	0.00	42.79	6.06	50	2 FILTERS
1	COL	HEPA	F	ING	4/10/96	0.25	29.26	7.43	1267.7	ASTM C136	100.0	100.0	100.0	89.2	40.1	24.6	19.5	12.1	9.9	8.5	0.00	0.0	0.00	0.00	153.68	14.50	171	2 FILTERS
1	COL	HEPA	F	NING	4/10/96	0.25	29.26	7.43	528.1	ASTM C136	100.0	100.0	100.0	91.1	66.0	42.8	29.0	13.7	9.3	8.5	0.00	0.0	0.00	0.00	64.45	6.04	71	2 FILTERS
1	N LTS	HEPA	F	ING	3/22/96	0.25	41.73	10.60	496.1	ASTM C136	100.0	100.0	100.0	99.2	90.9	59.7	37.2	15.0	11.2	9.3	0.00	0.0	0.00	0.00	41.57	4.35	47	
1	N LTS	HEPA	F	NING	3/22/96	0.25	40.51	10.29	67.0	ASTM C136	100.0	0.0	0.0	100.0	82.1	40.3	25.2	7.0	5.2	4.8	0.00	0.0	0.00	0.00	6.17	0.31	7	
1	OS	HEPA	F	ING	3/21/96	0.25	36.27	9.21	837.3	ASTM C136	100.0	100.0	100.0	96.3	72.0	51.6	38.0	17.2	12.6	10.5	0.00	0.0	0.00	0.00	79.43	9.54	91	
1	OS	HEPA	F	NING	3/21/96	0.25	45.72	11.61	116.2	ASTM C136	100.0	100.0	100.0	98.4	86.5	48.6	28.7	12.1	10.0	8.5	0.00	0.0	0.00	0.00	9.01	0.85	10	
1	OSD	HEPA	F	ING	4/16/96	0.25	31.70	8.05	768.8	ASTM C136	100.0	100.0	100.0	97.9	77.1	60.5	48.4	23.2	16.6	12.7	0.00	0.0	0.00	0.00	79.63	12.13	95	
1	OSD	HEPA	F	NING	4/16/96	0.51	62.79	31.90	233.0	ASTM C136	100.0	100.0	100.0	100.0	88.7	50.3	30.2	10.7	7.4	5.3	0.00	0.0	0.00	0.00	6.76	0.39	7	
1	RV	HEPA	F	ING	3/27/96	0.25	55.78	14.17	1555.5	ASTM C136	100.0	100.0	99.5	91.9	49.2	36.1	29.5	16.0	11.6	8.9	0.00	0.0	0.00	0.00	97.06	9.77	110	
1	RV	HEPA	F	NING	3/27/96	0.25	53.95	13.70	668.0	ASTM C136	100.0	100.0	100.0	91.6	52.5	29.4	21.1	9.9	7.2	5.8	0.00	0.0	0.00	0.00	45.24	2.83	49	
1	s36	HEPA	F	ING	3/21/96	0.25	42.67	10.84	951.5	ASTM C136	100.0	100.0	99.7	97.2	71.0	50.9	39.9	20.4	15.6	12.6	0.00	0.0	0.00	0.00	74.09	11.06	88	TWO TRANSECTS (T 5, T10
1	s36	HEPA	F	NING	3/21/96	0.25	34.75	8.83	732.3	ASTM C136	100.0	100.0	100.0	91.1	47.6	33.6	27.2	12.0	8.3	6.2	0.00	0.0	0.00	0.00	76.09	5.14	83	
1	s5	HEPA	F	ING	3/27/96	0.25	63.09	16.03	2103.0	ASTM C136	100.0	100.0	100.0	96.1	70.0	52.5	37.6	14.2	9.1	6.6	0.00	0.0	0.00	0.00	119.28	8.66	131	
1	s5	HEPA	F	NING	3/27/96	0.25	57.61	14.63	1119.3	ASTM C136	100.0	100.0	100.0	99.2	82.8	61.9	42.4	16.5	11.3	10.1	0.00	0.0	0.00	0.00	67.85	7.73	76	
2	15A	HEPA	F	ING	4/25/96	0.25	19.51	4.95	210.7	ASTM C136	100.0	100.0	100.0	100.0	98.4	94.4	89.2	60.8	50.1	42.2	0.00	0.0	0.00	0.00	21.22	17.95	43	2 TRANSECTS ONLY (5,50)
2	15A	HEPA	F	NING	4/25/96	0.25	19.51	4.95	248.3	ASTM C136	100.0	100.0	100.0	99.9	98.2	92.3	85.0	60.9	51.0	45.1	0.00	0.0	0.00	0.00	24.56	22.60	50	2 TRANSECTS ONLY (5,50)
2	CO	HEPA	F	ING	4/23/96	0.20	21.34	4.34	322.4	ASTM C136	100.0	100.0	100.0	99.4	94.7	83.8	70.6	38.7	29.8	24.2	0.00	0.0	0.00	0.00	52.20	17.99	74	2 TRANSECTS ONLY 5,50
2	CO	HEPA	F	NING	4/23/96	0.20	29.26	5.95	249.8	ASTM C136	100.0	100.0	100.0	100.0	98.1	90.8	78.3	46.6	36.7	30.4	0.00	0.0	0.00	0.00	26.59	12.77	42	
2	COL	HEPA	F	ING	4/25/96	0.25	19.51	4.95	427.8	ASTM C136	100.0	100.0	100.0	100.0	96.9	89.5	81.5	56.8	47.3	40.8	0.00	0.0	0.00	0.00	45.50	35.23	86	2 TRANSECTS ONLY (5,50)
2	COL	HEPA	F	NING	4/25/96	0.25	19.51	4.95	319.3	ASTM C136	100.0	100.0	100.0	100.0	99.4	96.2	86.8	54.4	43.8	37.7	0.00	0.0	0.00	0.00	36.22	24.30	64	2 TRANSECTS ONLY (5,50)
2	DM	HEPA	F	ING	4/19/96	0.20	84.12	17.09	236.7	ASTM C136	100.0	100.0	100.0	95.0	76.2	55.0	43.2	25.4	21.1	18.2	0.00	0.0	0.00	0.00	10.93	2.52	14	
2	DM	HEPA	F	NING	4/19/96	0.20	72.85	14.80	174.8	ASTM C136	100.0	100.0	100.0	97.3	81.6	62.7	49.5	28.8	23.4	19.5	0.00	0.0	0.00	0.00	9.05	2.30	12	
2	KING	HEPA	F	ING	4/25/96	0.25	49.62	12.60	1697.1	ASTM C136	100.0	100.0	99.6	96.1	45.4	31.0	27.5	14.4	10.1	8.5	0.00	0.0	0.00	0.00	121.05	11.44	135	
2	KING	HEPA	F	NING	4/25/96	0.25	26.67	6.77	883.1	ASTM C136	100.0	100.0	100.0	97.7	70.9	54.9	44.4	24.1	18.3	14.5	0.00	0.0	0.00	0.00	106.50	18.90	130	2 TRANSECTS ONLY (5,50)
2	OS	HEPA	F	ING	4/25/96	0.25	51.51	13.03	164.5	ASTM C136	100.0	100.0	98.3	93.4	79.3	62.1	51.3	24.3	17.3	12.5	0.00	0.0	0.00	0.00	10.44	1.58	13	DOUBLE SAMPLED
2	OS	HEPA	F	NING	4/25/96	0.51	45.72	23.23	41.9	ASTM C136	100.0	100.0	100.0	100.0	95.9	82.1	65.3	38.8	31.6	24.0	0.00	0.0	0.00	0.00	1.23	0.43	2	DOUBLE SAMPLED
2	OSD	HEPA	F	ING	5/30/96	0.25	70.71	17.96	312.5	ASTM C136	100.0	100.0	100.0	96.9	90.6	80.7	69.7	43.2	34.6	26.8	0.00	0.0	0.00	0.00	11.38	4.66	17	
2	OSD	HEPA	F	NING	5/30/96	0.25	44.50	11.30	329.1	ASTM C136	100.0	100.0	100.0	98.4	97.1	94.0	85.5	62.0	51.0	42.1	0.00	0.0	0.00	0.00	14.27	12.26	29	
2	s16	HEPA	F	ING	4/23/96	0.20	21.34	4.34	82.8	ASTM C136	100.0	100.0	100.0	99.3	91.0	77.4	66.7	40.8	32.2	27.0	0.00	0.0	0.00	0.00	12.95	5.16	19	
2	s16	HEPA	F	NING	4/23/96	0.20	19.51	3.96	123.8	ASTM C136	100.0	100.0	100.0	96.8	79.1	60.9	48.7	22.7	16.8	12.9	0.00	0.0	0.00	0.00	25.98	4.03	31	
2	s36	HEPA	F	ING	4/25/96	0.25	60.05	15.25	87.7	ASTM C136	100.0	100.0	100.0	100.0	98.5	91.8	77.6	43.3	30.4	22.6	0.00	0.0	0.00	0.00	4.00	1.30	6	
2	s36	HEPA	F	NING	4/25/96	0.51	52.12	26.48	93.0	ASTM C136	100.0	100.0	100.0	99.0	89.2	80.1	70.5	44.0	34.4	27.4	0.00	0.0	0.00	0.00	2.30	0.96	4	

Street Sediment Sample Database (AQDATA.DBF)

HEPA Samples

February 13, 1997

											Percent Passing Sieve (mm)														Loadings (g/m²)			
round	site_id	sample	to	strata	sampdate	transwidth	transleng	transarea	totdrywt	analysis	38.1	19.0	9.5	4.76	2.00	0.84	0.42	0.149	0.105	0.074	bagwt	pctretain	bagtare	retained	ogs	airsusp	totload	notes
3	15A	HEPA	F	ING	8/6/96	0.25	19.51	4.95	61.0	ASTM C136	100.0	100.0	100.0	100.0	97.4	79.9	61.2	30.4	21.7	16.8	0.00	0.0	0.00	0.00	9.64	2.07	12	
3	15A	HEPA	F	NING	8/6/96	0.25	19.51	4.95	90.2	ASTM C136	100.0	100.0	100.0	99.2	96.1	74.5	54.5	28.0	20.9	16.6	0.00	0.0	0.00	0.00	14.40	3.02	18	
3	15A	HEPA	T	NTONG	8/6/96	0.25	29.26	7.43	76.1	ASTM C136	100.0	100.0	100.0	100.0	99.2	90.7	74.4	39.1	29.0	21.8	0.00	0.0	0.00	0.00	7.27	2.23	10	
3	15A	HEPA	T	TONG	8/6/96	0.25	14.63	3.72	130.6	ASTM C136	100.0	100.0	100.0	98.8	92.3	70.6	53.8	30.1	22.3	18.8	0.00	0.0	0.00	0.00	27.31	6.61	35	
3	A	HEPA	T	NTONG	7/26/96	0.25	12.50	3.17	23.8	ASTM C136	100.0	100.0	100.0	100.0	97.6	88.8	80.0	50.4	42.4	37.6	0.00	0.0	0.00	0.00	4.32	2.82	7	
3	A	HEPA	T	TONG	7/26/96	0.25	12.50	3.17	26.7	ASTM C136	100.0	100.0	100.0	100.0	91.1	78.5	64.4	46.7	40.0	31.9	0.00	0.0	0.00	0.00	5.05	2.68	8	
3	COL	HEPA	F	ING	8/6/96	0.25	29.26	7.43	62.3	ASTM C136	100.0	100.0	100.0	100.0	98.0	90.9	70.9	28.7	16.6	10.8	0.00	0.0	0.00	0.00	6.99	0.91	8	
3	COL	HEPA	F	NING	8/6/96	0.25	29.26	7.43	82.4	ASTM C136	100.0	100.0	100.0	98.6	96.7	91.4	77.5	36.8	26.9	20.8	0.00	0.0	0.00	0.00	8.10	2.31	11	
3	N LTS	HEPA	F	ING	7/26/96	0.25	41.73	10.60	46.8	ASTM C136	100.0	100.0	100.0	100.0	88.1	49.2	24.2	6.1	4.9	4.5	0.00	0.0	0.00	0.00	4.20	0.20	4	
3	N LTS	HEPA	F	NING	7/26/96	0.25	40.54	10.30	25.5	ASTM C136	100.0	100.0	100.0	100.0	88.3	52.5	33.3	12.5	10.0	7.5	0.00	0.0	0.00	0.00	2.23	0.19	2	
3	OS	HEPA	F	ING	7/17/96	0.51	51.51	26.17	26.9	ASTM C136	100.0	100.0	100.0	100.0	92.1	84.2	66.7	34.2	28.9	24.6	0.00	0.0	0.00	0.00	0.73	0.25	1	
3	OS	HEPA	F	NING	7/17/96	0.51	45.72	23.23	25.9	ASTM C136	100.0	100.0	100.0	58.0	54.1	41.4	24.2	23.6	21.0	20.4	0.00	0.0	0.00	0.00	0.88	0.23	1	
3	OSD	HEPA	F	ING	7/17/96	0.25	70.71	17.96	106.5	ASTM C136	100.0	100.0	100.0	89.0	74.0	59.6	42.0	17.4	13.2	11.0	0.00	0.0	0.00	0.00	5.15	0.65	6	
3	OSD	HEPA	F	NING	7/17/96	0.25	64.01	16.26	146.8	ASTM C136	100.0	100.0	100.0	97.2	85.5	62.1	40.5	17.4	13.2	10.1	0.00	0.0	0.00	0.00	7.84	0.91	9	
3	s36	HEPA	F	ING	7/17/96	0.51	60.05	30.50	136.0	ASTM C136	100.0	100.0	94.5	90.7	85.8	77.1	58.6	27.5	20.4	16.0	0.00	0.0	0.00	0.00	3.55	0.71	4	
3	s36	HEPA	F	NING	7/17/96	0.51	52.12	26.48	65.2	ASTM C136	100.0	100.0	100.0	100.0	97.9	79.2	56.9	32.4	26.6	22.6	0.00	0.0	0.00	0.00	1.81	0.56	2	

STRATA.DBF (Look-up Table)

Field Summary, Legend, and Hardcopy Printout

Strata Legend

Strata	Strata Description
IG	Intersection, gutter
IGO	Intersection, gutter only (when no corresponding non-gutter sample was taken)
ING	Intersection, non-gutter
NIG	Non-intersection, gutter
NIGO	Non-intersection, gutter only (when no corresponding non-gutter sample was taken)
NING	Non-intersection, non-gutter
NTOG	Non-trackout, gutter
NTONG	Non-trackout, non-gutter
TOG	Trackout, gutter
TONG	Trackout, non-gutter

STRATA.DBF Field Summary and Legend

Field Name	Unit	Data Type	Size	Field Description
STRATA		Character	5	The strata code
DESC		Character	81	Description of the part of the street surface corresponding to the strata code

Appendix B

Site Survey Field Note Forms (organized by date)

Sampling Field Note Forms (organized by date)

Particle Size Distribution (Sieve Analysis) Plots (organized alphabetically by sampling round)

Chain-of-Custody Documentation (organized by date)

Street Sediment Loads Assessment Project
Site Survey Field Note Form

3:30 AM Date: 03 / 20 / 96   Weather: COLD, CLEAR, DARK ~26°F LIGHT WIND

Sampling Team: CB, Md, CW /

Intersection: 36th AVE / NEW SEWARD

Sampled only 5' transect (gutter & non gutter) on NS only

12' of gutter

Field Sketch



22 Intersection Lanes

Note track out site, controlled lane configuration, traffic flow, photo stations, transects, medians, and permanent features. ✓

* **Transect Lengths** (transect locations are measured from the curbline of the crossing street) (feet)

	Site	A NS ~~36~~ / Median	Site	B 36 ~~NS~~ / Median	Trackout Site
125'	5	140 - 6:134	5 61'	70 - 5:65	0
81'	50	98 - 12=86	50 56'	65 - 5:60	+15
64'	100	80 - 12=68	100 52'	60 - 5:55	-15
64'	102	80 - 12=68	102 51'	59 - 5:54	
66'	150	82 - 12=70	150 55'	64 - 5:59	NI transects overlap with stop zone at 36th & old seward
68'	200	84 - 12=72	200 52'	60 (CURB ICED OVER) - 5:55	

53 paces = 50 feet = 0.94 ft/pace

* paced

Street Sediment Loads Assessment Project
Site Survey Field Note Form

Date: 3 / 21 / 96 Weather: Clear, dark (2:00am) 15°, Calm

Sampling Team: CN CW, BF /

Intersection: 36th & OS

Field Sketch



Note track out site, controlled lane configuration, traffic flow, photo stations, transects, medians, and permanent features.

Transect Lengths (transect locations are measured from the curbline of the crossing street)

Site	36	Site	OS	Trackout Site	
5	87'	5	73'	0	
50	65'	50	58'	+15	
100		100		-15	
102		102			
150		150			
200		200			

No TOS
CN

Street Sediment Loads Assessment Project
Site Survey Field Note Form

Date: 3 / 22 / 96   Weather: CLOUDY, 25° WITH WIND

Sampling Team: CHRIS BROWN / BRENT CARE /

Intersection: DIMOND AND KING ST

17.5 paces

17.5 paces

Field Sketch



Note track out site, controlled lane configuration, traffic flow, photo stations, transects, medians, and permanent features.

☒ photo

Transect Lengths (transect locations are measured from the curbline of the crossing street)

Site	Dimond	Site	King		Trackout Site	
5	106'	5	84'	14 paces (CR)	0	
50	95'	50	49.4'	8.25 paces	+15	
100	95'	100	49.4'	8.25 paces	-15	
102	95'	102	49.4'	8.25 paces		
150	84'	150	54'	9 paces		
200	84'	200	54'	9 paces		

includes bus stop area (50, 100)

Need to be verified (150, 200) CR 3/22/96

6'/pace.

Street Sediment Loads Assessment Project
Site Survey Field Note Form

Date: 3 / 26 / 96 Weather Cloudy Temp: 28°F

Sampling Team: CW / BF /

Intersection: 12th W & N - North
West

Field Sketch



Note track out site, controlled lane configuration, traffic flow, photo stations, transects, medians, and permanent features.

Transect Lengths (transect locations are measured from the curbline of the crossing street)

Site	N - North	Site	12 - West	Trackout Site	
5	36	5	36	0	
50	34	50	34	+15	
100	34	100	34	-15	
102	34	102	34		
150	34	150	34		
200	34	200	34		

Street Sediment Loads Assessment Project
Site Survey Field Note Form

3:00 am

Date: 3/27/96 Weather 27°F Partly Cloudy → Clearing

Sampling Team: CW / BF /

Intersection: 5th & Reeve

Reeve

Field Sketch



Note track out site, controlled lane configuration, traffic flow, photo stations, transects, medians, and permanent features.

Transect Lengths (transect locations are measured from the curbline of the crossing street)

Site	5th		Site	Reeve		Trackout Site	
5	85	38 paces	5	69	30 paces	0	
50	67	29 paces	50	63 ft	27 paces	+15	/
100	67		100	63		-15	/
102	67		102	63			
150	67		150	63			
200	67		200	63			

Street Sediment Loads Assessment Project
Site Survey Field Note Form

9:00 am

Date: 3/27/96 Weather 35° F Sunny - Slight Wind

Sampling Team: CW / BF

Intersection: 15th & E

Field Sketch E



Note track out site, controlled lane configuration, traffic flow, photo stations, transects, medians, and permanent features.

Transect Lengths (transect locations are measured from the curbline of the crossing street)

Site	E	Site	15th	Trackout Site	
5	42	5	50	0	
50	34	50	36	+15	
100	34	100	36	-15	
102	34	102	36		
150	34	150	36		
200	34	200	36		

Street Sediment Loads Assessment Project
Site Survey Field Note Form

Date: 4 / 2 / 96 Weather: Cloudy, 28°

Sampling Team: Bill Spencer / Brent Farr

Intersection: 16th and Columbine



Note track out site, controlled lane configuration, traffic flow, photo stations, transects, medians, and permanent features.

Transect Lengths (transect locations are measured from the curbline of the crossing street)

Site	16th	Site	Columbine	Trackout Site	
5	41.5	5	[illegible]	0	
50	36	50	36	+15	
100	36	100	36	-15	
102	36	102	36		
150	36	150	36		
200	36	200	36		

Street Sediment Loads Assessment Project
Site Survey Field Note Form

Date: 4/5/96 Weather: Overcast 38°F, Light wind

Sampling Team: Bill Spencer /

Intersection: 9th & Karluk

Moved transect to S Bound Karluk + West Bound 9th to avoid snow berms

Field Sketch



5'-transect misses the major sand deposits at these intersections

Note track out site, controlled lane configuration, traffic flow, photo stations, transects, medians, and permanent features.

Transect Lengths (transect locations are measured from the curbline of the crossing street)

Site	Karluk	Site	9th	Trackout Site	
5	8½ paces (50')	5	8½ paces 50')	0	
50	8 paces (45')	50	8 paces (45')	+15	
100		100		-15	
102		102			
150		150			
200	✓	200	✓		

6" transects

Street Sediment Loads Assessment Project
Site Survey Field Note Form

Date: 4 / 5 / 96 Weather: Partly Cloudy 40°F

Sampling Team: Bill Spencer / Mark Alder

Intersection: 13th + Karluk

Field Sketch



Note track out site, controlled lane configuration, traffic flow, photo stations, transects, medians, and permanent features.

Transect Lengths (transect locations are measured from the curbline of the crossing street)

Site	Karluck S bound	Site	13th West bound	Trackout Site	
5	(35')	5	8 1/2 paces (35)'	0	40'
50	(45')	50	7 1/2 pac (40')	+15	40'
100		100	7 1/2 pac	-15	40
102		102	7 1/2 pac		
150		150	7 1/2		
200	↓	200	↓		

Includes gutter CP 7/2/96

Note Track out site is within the Non Int Area and included areas of large snow berms. site was deleted as infeasible

Call Steve all 4/9/96
Cw 11/13/96

Street Sediment Loads Assessment Project
Site Survey Field Note Form

Date: 4 / 9-10 / 96 Weather: Clear 40°F

Sampling Team: Bill Spencer /

Intersection: 15th + Columbine

Field Sketch



Note track out site, controlled lane configuration, traffic flow, photo stations, transects, medians, and permanent features.

Transect Lengths (transect locations are measured from the curbline of the crossing street)

Site	15th	Site	Columbine	Trackout Site	
5	36'	5	36'	0	
50		50		+15	
100		100		-15	
102		102			
150		150			
200		200			

Street Sediment Loads Assessment Project
Site Survey Field Note Form

Date: 4 / 16 / 96 Weather 39°F Clear

Sampling Team: Bill Spencer / Chris Brown

Intersection: Dowling + Old Seward

Field Sketch



Note track out site, controlled lane configuration, traffic flow, photo stations, transects, medians, and permanent features.

Transect Lengths (transect locations are measured from the curbline of the crossing street)

Site	O.S.	Site		Trackout Site	
5	108 ft 18 paces	5		0	
50	72 ft 12	50		+15	
100	72 ft 12	100		-15	
102	72 ft 12	102			
150	81 ft 13.5	150			
200	81 ft 13.5	200			

↳ Not including raised median

Street Sediment Loads Assessment Project
Site Survey Field Note Form

Date: 7/24/96 Weather: Overcast 50°F

Sampling Team: B. Spencer /

Intersection: Iowa + Spencer

Field Sketch



Note track out site, controlled lane configuration, traffic flow, photo stations, transects, medians, and permanent features.

Transect Lengths (transect locations are measured from the curbline of the crossing street)

Site	Spencer	Site	Iowa	Trackout Site	
5	4	5	4	0	
50	8	50	4	+15	
100	8	100	4	-15	
102	8	102	4		
150	8	150	4		
200	8	200	4		

Gutters Only

Street Sediment Loads Assessment Project
Site Survey Field Note Form

Date: 7/24/96 Weather: Overcast 50°F

Sampling Team: B. Spencer /

Intersection: 6th & A Gutters only

Field Sketch



Note track out site, controlled lane configuration, traffic flow, photo stations, transects, medians, and permanent features.

NTO

Transect Lengths (transect locations are measured from the curbline of the crossing street)

Site	6th	Site	A st	Trackout Site	
5	4	5	4	0	7 1/4 paces 9 = 50 ft
50	4	50	4	+15	
100	4	100	4	-15	
102	4	102	4	Non Track out	
150	4	150	4	0	
200	4	200	4	+15	
				-15	

Gutters only

Street Sediment Loads Assessment Project
Site FieldSurvey Form

Date: 7 / 26 / 96

Intersection: NL & Denali Weather: Clear, 55°F

Sampling Team: Bill S. / Chris B /

Field Sketch



Note track out site, controlled lane configuration, traffic flow, photo stations, transects, medians, and permanent features.

Transect Lengths (transect locations are measured from the curbline of the crossing street)

Site		Site			Trackout Site
5		5		TO	0
50		50			+15
100		100			-15
102		102		NTO	0
150		150			+15
200		200			-15

FIELD LOGS AND SEDIMENT ANALYSIS DATA

Street Sediment Loads Assessment Project
Sampling Field Note Form

330 Am

Date: 3 / 20 / 96 Weather: Clear, Cold 26°, Light Wind

Sampling Team: CW, CB, MD /

Intersection: Newseward & 36

Track Out Site Present: Y / N (circled N)   Air Quality Site: Y / N ? (circled N ?)

Y	N		Comments
	✓	Photos taken of all transects	Night Time
	✓	Photos taken from all photo stations	↓
NA		Trackout site sampled (if present)	
NA		Air quality samples collected (if appropriate)	
~~[illegible]~~	✓	All transects and strata sampled	Not enough time. 1st Attempt at Sampling. Next time Start @ 2am. Sampled from 3:30 - 5:00. Sampled 5' transect on NS only. CP 3/20/96

Vacuum Bag Tare Weights/Total Sample Weight

Site New Seward

IG	g/ g	8" Head Sample ID	~~3/20 0320NSIG~~ NSIG032096
ING	g/ g	Sample ID	~~0320 NSING~~ NSING032096
NIG	g/ g	Sample ID	
NING	g/ g	Sample ID	

Site

IG	g/ g	Sample ID	
ING	g/ g	Sample ID	
NIG	g/ g	Sample ID	
NING	g/ g	Sample ID	

TO Site

G	g/ g	Sample ID	
NG	g/ g	Sample ID	

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 3 / 21 / 96 Weather Clear, dark (2:00 am) 15°, Calm

Sampling Team: CB, CW, BF /

Intersection: Old Seward & 36th

Track Out Site Present: Y / (N) Air Quality Site: (Y) / N

Y	N		Comments
✓		Photos taken of all transects	Photos taken later in day when light
✓		Photos taken from all photo stations	
NA		Trackout site sampled (if present)	
✓		Air quality samples collected (if appropriate)	Only Non gutter transects per DHHS AQ
	✓	All transects and strata sampled	2 transects / area except OSNING due to large amount of dirt

Air Q Samps
36 ~~ING~~ AQ 2 Transects
36 NING AQ
OS ING AQ
OS NING AQ 3 Transects

Vacuum Bag Tare Weights/Total Sample Weight

Site OS

Transect width 2 8"

		Sample ID
IG	71g g/ g	OSIG032196
ING	g/ g	OSING032196 +AQ
NIG	g/ g	OS NIG032196
NING	g/ g	OSNING032196 +AQ

Site 36

		Sample ID
IG	71g g/ g	36IG032196
ING	g/ g	36ING032196 +AQ 10" Transects
NIG	g/ g	36 NIG032196
NING	g/ g	36 NING032196 +AQ 10"

~~TO Site~~

		Sample ID
G	g/ g	
NG	g/ g	

8 inch Wide Transects

Oil and Grit Seperator Assessment Program
Initial Sediment Load Sampling and Oiled Surface Assessment
Field Notes.

Sampled only gutter on N Side of Street. South side gutter was Swept. @ 3/22/96

Sampling Date: 3/22/96

Sampling Team: Field Team Leader CB
Sampler BF

Washoff Area:
(X N.Lt. W.) (W. 23 rd Ave.)
Sub area: ✓ Intersection ✓ Non Intersection
✓ Gutter Non Gutter
Sampling Method . Film Roll Number 66 B.B.
Composit Sample ID Number .

Bag Weights are ?g Tare

Transect number	Transect length	Photo Number	Age and area of oiled patches > 6 " Ø in previous 50' of street.	Comments
				IG Sample # 9500311201 NLtS IG 032296
111	26.0		___ft2 Fresh 2 3 4 Weath.	NIG Sample # 9500311202 NLtS NIG 032296
101	52.3		___ft2 Fresh 2 3 4 Weath.	ING Sample # 9500311203 NLtS ING 032296
102	48.3	AQ	___ft2 Fresh 2 3 4 Weath.	NING Sample # 9500311204 NLtS NING 032296
103		Sample	___ft2 Fresh 2 3 4 Weath.	
104			___ft2 Fresh 2 3 4 Weath.	
105		AQ Sample	___ft2 Fresh 2 3 4 Weath.	
106			___ft2 Fresh 2 3 4 Weath.	
107			___ft2 Fresh 2 3 4 Weath.	
108			___ft2 Fresh 2 3 4 Weath.	
109			___ft2 Fresh 2 3 4 Weath.	

Int

Non Int

110

112

Street Sediment Loads Assessment Project
Sampling Field Note Form

8 inch Transects

Date: 3/22/96 Weather: Cold, clear, 25°, 2am, dark

Sampling Team: CB / BF

Intersection: ~~ ~~ Dimond & King (Only Dimond Sampled)

Track Out Site Present: Y (N) Air Quality Site: Y (N)

Y	N		Comments
✓		Photos taken of all transects	
	✓	Photos taken from all photo stations	only Dimond (2)
NA		Trackout site sampled (if present)	
NA		Air quality samples collected (if appropriate)	
	✓	All transects and strata sampled	Ran out of Time

Transect #2 for IG is 5" wide not 8"

Intersection Gutter collected

Intersection non-gutter collected Composite from Transects at 5 and 100 feet only.

Vacuum Bag Tare Weights/Total Sample Weight

Site Dimond

IG	~~71~~ 66 g/ g	Sample ID	DMIG 032296
ING	~~71~~ 66 g/ g	Sample ID	DMING 032296
NIG	g/ g	Sample ID	
NING	g/ g	Sample ID	

See sampling episode note on back of site survey form. CB 3/24/96

Site

IG	g/ g	Sample ID	
ING	g/ g	Sample ID	
NIG	g/ g	Sample ID	
NING	g/ g	Sample ID	

TO Site

G	g/ g	Sample ID	
NG	g/ g	Sample ID	

8 inch
· Transects

Street Sediment Loads Assessment Project
Sampling Field Note Form

Time 10:00 am
Date: 3 / 26 / 96 Weather 28° Cloudy

Sampling Team: CW BF /

Intersection: 12 / N

Track Out Site Present: Y / N Air Quality Site: Y / N

Y	N		Comments
✓	~~W~~	Photos taken of all transects	
✓		Photos taken from all photo stations	
NA		Trackout site sampled (if present)	
NA		Air quality samples collected (if appropriate)	
✓		All transects and strata sampled	

Vacuum Bag Tare Weights/Total Sample Weight

Site 12

IG	~~7~~ 66 B.S. g/ g	Sample ID	12IG-032696
ING	g/ g	Sample ID	12ING-032696
NIG	g/ g	Sample ID	12NIG 032696
NING	g/ g	Sample ID	12NING-032696

Site ~~12~~ N

IG	~~7~~ 166 B.S. g/ g	Sample ID	NIG 032696
ING	g/ g	Sample ID	NING 032696
NIG	g/ g	Sample ID	NNIG 032696
NING	g/ g	Sample ID	NNING 032696

TO Site

G	g/ g	Sample ID	
NG	g/ g	Sample ID	

8 inch - Transects

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 3/27/96 3:00am Weather 27°F Partly Cloudy Dark → Clearing

Sampling Team: CW / BF

Intersection: 5th & Reeve

Track Out Site Present: Y / (N) Air Quality Site: (Y) / N

Y	N		Comments
		Photos taken of all transects	
N/A		Trackout site sampled (if present)	
		Photos taken from all photo stations	
✓		Air quality samples collected (if appropriate)	
✓		All transects and strata sampled	

Vacuum Bag Tare Weights/Total Sample Weight

Site 5th

IG	~~71~~ 66 g/ g	Sample ID	5IG032796
ING	g/ g	Sample ID	5ING032796 & AQ
NIG	g/ g	Sample ID	5NIG032796
NING	g/ g	Sample ID	5NING032796 & AQ

Site Reeve

IG	~~71~~ 66 g/ g	Sample ID	RVIG032796
ING	g/ g	Sample ID	RVING032796 & AQ
NIG	g/ g	Sample ID	RVNIG032796
NING	g/ g	Sample ID	RVNING032796 & AQ

TO Site

G	g/ g	Sample ID	
NG	g/ g	Sample ID	

Street Sediment Loads Assessment Project
Sampling Field Note Form

8 inch Transects

9:00am

Date: 3/27/96 Weather: 35°F Sunny - Slight Wind

Sampling Team: CW / BF

Intersection: 15th & E

Track Out Site Present: Y / N (circled N) Air Quality Site: Y / N (circled N)

Y	N		Comments
✓		Photos taken of all transects	
✓		Photos taken from all photo stations	
	N/A	Trackout site sampled (if present)	
	✓	Air quality samples collected (if appropriate)	
✓		All transects and strata sampled	

Vacuum Bag Tare Weights/Total Sample Weight

Site E

IG	~~21~~ 66 g/ g	Sample ID	EIG032796
ING	g/ g	Sample ID	EING032796
NIG	g/ g	Sample ID	ENIG032796
NING	g/ g	Sample ID	ENING032796

Site 15th

IG	~~21~~ 66 g/ g	Sample ID	15IG032796
ING	g/ g	Sample ID	15ING032796
NIG	g/ g	Sample ID	15NIG032796
NING	g/ g	Sample ID	15NING032796

TO Site

G	g/ g	Sample ID	
NG	g/ g	Sample ID	

Street Sediment Loads Assessment Project
Sampling Field Note Form

- 8 inch Transects

Date: 4 / 2 / 96 Weather: Overcast 28°

Sampling Team: Bill Spencer / Brent Furr

Intersection: 16th + Columbine

Track Out Site Present: Y / (N) Air Quality Site: Y / (N)

Y	N		Comments
✓		Photos taken of all transects	
	✓	Photos taken from all photo stations	2 general Photos + all Transects
N/A		Trackout site sampled (if present)	
	✓	Air quality samples collected (if appropriate)	
✓		All transects and strata sampled	– Some transects were offset slightly to avoid ice in gutters – Some gutter areas sampled with shovel only, no vacume, as they contained standing water

Vacuum Bag Tare Weights/Total Sample Weight

Site 16th

IG	66 ~~71~~ g/ g	Sample ID	16 IG 040296
ING	g/ g	Sample ID	16 ING 040296
NIG	g/ g	Sample ID	16 NIG 040296
NING	✓ g/ g	Sample ID	16 NING 040296

Site Columbine

IG	66 ~~71~~ g/ g	Sample ID	Co IG 040296
ING	g/ g	Sample ID	Co ING 040296
NIG	g/ g	Sample ID	Co NIG 040296
NING	✓ g/ g	Sample ID	Co NING 040296

TO Site

G	g/ g	Sample ID	
NG	g/ g	Sample ID	

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 4/5/95 Weather: Overcast 38° light wind

Sampling Team: Bill Spencer /

Intersection: 9th & Karluk

Track Out Site Present: Y / (N) Air Quality Site: Y / (N)

Y	N		Comments
✓		Photos taken of all transects	
✓		Photos taken from all photo stations	
N/A		Trackout site sampled (if present)	
N/A		Air quality samples collected (if appropriate)	
✓		All transects and strata sampled	

9th may have Been Swept before snow burms melted? check dates

NO evidence of this 10/2/96 CP

Vacuum Bag Tare Weights/Total Sample Weight

Site: 9th Trans width

All Gutter transects Sampled with shovel + Broom

IG	g/ g	8"	Sample ID	9th IG 040596
ING	66 ~~71~~ g/ g	6"	Sample ID	9th ING
NIG	g/ g	8"	Sample ID	9th NIG
NING	66 ~~71~~ g/ g	6"	Sample ID	9th NING ✓

Site: Karluk

IG	g/ g	8 ~~10~~"	Sample ID	KAIG 040596
ING	66 ~~71~~ g/ g	6"	Sample ID	ING
NIG	g/ g	8 ~~10~~"	Sample ID	NIG
NING	66 ~~71~~ g/ g	6"	Sample ID	✓ NING ✓

TO Site

G	NA g/ g	Sample ID	N/A
NG	g/ g	Sample ID	

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 4/5/96 Weather: Overcast 40°F

Sampling Team: Bill Spencer / Mark Alder

Intersection: 13th + Karluck

Track Out Site Present: Y / N Air Quality Site: Y / N

Not Sampled see note on sketch

Y	N		Comments
✓		Photos taken of all transects	
✓		Photos taken from all photo stations	
	✓	Trackout site sampled (if present)	Trackout site Snow Bound
		Air quality samples collected (if appropriate)	
✓		All transects and strata sampled	

Vacuum Bag Tare Weights/Total Sample Weight

Site 13th

IG	71 g/ g	8	Sample ID	13IG040596
ING	~~471~~ 466 g/ g		Sample ID	13ING040596
NIG	4 g/ g		Sample ID	13NIG040596
NING	~~471~~ 466 g/ g		Sample ID	13NING040596

all Gutter Transects sampled with ~~8"~~ 4" shovel

Non Gutter sampled with 6" suction head

Site

IG	NA g/ g	Sample ID	KAIG040596
ING	6671 g/ g	Sample ID	KAING040596
NIG	N/A g/ g	Sample ID	KANIG040596
NING	6671 g/ g	Sample ID	KANING040596

TO Site

G	g/ g	Sample ID	
NG	g/ g	Sample ID	

bill all Sumps 4/19/96 (CA) 11/18/96

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 4/9-10/96 Weather: Clear 40°F

Sampling Team: Bill Spencer /

Intersection: 15 & Columbus

Track Out Site Present: Y / N   Air Quality Site: Y / N

Y	N		Comments
✓		Photos taken of all transects	Two photos misslabled made labels for them
✓		Photos taken from all photo stations	
	✓	Trackout site sampled (if present)	
✓		Air quality samples collected (if appropriate)	AQ sampling requires a new filter for each transect, very time consuming
✓		All transects and strata sampled	

Vacuum Bag Tare Weights/Total Sample Weight

Sampling method

Site 15th

IG	g/ g	Sample ID	15AIG040996	shovel + 041096 AQ
ING	66 g/ g	Sample ID	15A ING 040996	6" transect GV
NIG	g/ g	Sample ID	15A NIG 040996	8" shovel
NING	66 g/ g	Sample ID	15A NING040996	6" transect GV + 041096 AQ

Site Col

IG	g/ g	Sample ID	COLIG 040996	shovel
ING	66 g/ g	Sample ID ✓	COL ING 040996	+ 041096 AQ 6" transect GV
NIG	g/ g	Sample ID	COL NIG040996	8" shovel
NING	66 g/ g	Sample ID ✓	COL NING 040996	6" transect Gas Vacuum + 041096 AQ

TO Site

G	g/ g	Sample ID	
NG	g/ g	Sample ID	

all transects Vacumed 6" except as noted

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 4/16/96 Weather 39°F Clear

Sampling Team: Bill Spencer / Chris Brown

Intersection: 36th & New Seward

Track Out Site Present: Y / (N) Air Quality Site: Y / (N)

Y	N		Comments
	✓	Photos taken of all transects	
	✓	Photos taken from all photo stations	
	✓	Trackout site sampled (if present)	
	N/A	Air quality samples collected (if appropriate)	
✓		All transects and strata sampled	

Vacuum Bag Tare Weights/Total Sample Weight

Site 36th ~~Length of~~ ~~Transect~~ D.S. See 36th & NS 3/20/96

IG	66 g/ g	~~20~~	Sample ID	36BIG041696
ING	71 g/ g	~~177~~	Sample ID	36B ING
NIG	66 g/ g	~~24~~	Sample ID	36B NIG
NING	66 g/ g	~~150~~	Sample ID	36B NING

Site New Seward

IG	66 g/ g	Sample ID	NSIG	– E Side Transects 4' long
ING	66 g/ g	Sample ID	NSING	
NIG	66 g/ g	Sample ID	NSNIG	– E Side Transects 4' long
NING	66 g/ g	Sample ID	NSNING	

TO Site

G	N/A g/ g	Sample ID	
NG	g/ g	Sample ID	

Intersection has been swept several times but still contains dirt along gutters and may be swept again. — Estimate 04/05/96 in addition to document ... 3/25/96 CN 11/9/96

Street Sediment Loads Assessment Project
Sampling Field Note Form

·6" Transects

Date: 4/16/96 Weather: Clear 39°F

Sampling Team: CR BS /

Intersection: Old Seward & Dowling (OSD) OSD only

Track Out Site Present: Y / (N) Air Quality Site: (Y) / N

Dowling has no gutters & dirt area adjacent to street so no sampling

Y	N		Comments
	✓	Photos taken of all transects	return during day
	✓	Photos taken from all photo stations	
	✓	Trackout site sampled (if present)	
✓		Air quality samples collected (if appropriate)	NING AQ Transects doubled & WMS
✓		All transects and strata sampled	W side Gutter transect 4' for 200' and 150' Transect W side only

Vacuum Bag Tare Weights/Total Sample Weight

Site (OS) & Dowling

IG	66 g/ g	Sample ID	OSDIG041696
ING	g/ g	Sample ID	OSDING041696 AQ
NIG	g/ g (in 2 bags)	Sample ID	OSDNIG041696
NING	g/ g	Sample ID	OSDNING041696 AQ

Sampled Transects 2X both AirQ & WMS Samples

1 Transect only 5' very dirty Dirtiest of 3 intersect Transects

Site ______

IG	g/ g	Sample ID	
ING	g/ g	Sample ID	
NIG	g/ g	Sample ID	
NING	g/ g	Sample ID	

~~TO Site~~ Bus stop

X2 (200' & 150')

NI G	11'3" / Transects g/ g	Sample ID	OSDBSNIG041696
NG	g/ g	Sample ID	



Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 4 / 18 / 96 Weather: Sunny 50°F

Sampling Team: Bill Spencer / —

Intersection: 9th & Karluk

Track Out Site Present: Y / (N) Air Quality Site: Y / (N)

Y	N		Comments
			assumed same for 13th & Karluck @ 11/19/96
✓		Photos taken of all transects	Swept 2 days ago, rained
✓		Photos taken from all photo stations	yesterday, sunny today but
		Trackout site sampled (if present)	still some gutter flow. Used
		Air quality samples collected (if appropriate)	8" brush head to loosen
✓		All transects and strata sampled	street sweep smear from pavement

Vacuum Bag Tare Weights/Total Sample Weight

Site Karluk

	Weight		Sample ID	width of Transect
IG	66 g/ g	Sample ID	KBIG041896	16"
ING	66 g/ g	Sample ID	KBING041896	8"
NIG	66 g/ g	Sample ID	KBNIG041896	16"
NING	66 g/ g	Sample ID	KBNING041896	8"

Site 9th

	Weight		Sample ID	
IG	66 g/ g	Sample ID	9thIG041896	16"
ING	66 g/ g	Sample ID	9thING041896	8"
NIG	66 g/ g	Sample ID	9thNIG041896	16"
NING	66 g/ g	Sample ID	9thNING041896	8"

TO Site

G	N/A g/ g	Sample ID	
NG	g/ g	Sample ID	

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 4 / 19 / 96 Weather Clear 48 °F

Sampling Team: Bill Spencer /

Intersection: 5th & Reeve

Track Out Site Present: Y / (N) Air Quality Site: Y / (N)

Y	N		Comments
✓		Photos taken of all transects	
✓		Photos taken from all photo stations	next morning
		Trackout site sampled (if present)	
		Air quality samples collected (if appropriate)	
✓		All transects and strata sampled	

Vacuum Bag Tare Weights/Total Sample Weight ✓ B.S. 5/13

Site 5th Transect width check photos

IG	66 g/ g	~~16~~ 8"	Sample ID	5IG041996
ING	66 g/ g	8"	Sample ID	5ING041996
NIG	66 g/ g	~~16~~ 8"	Sample ID	5NIG 041996
NING	66 g/ g	8"	Sample ID	5NING041996

Site Reeve

IG	66 g/ g	~~16~~ 8"	Sample ID	RV IG041996
ING	66 g/ g	8"	Sample ID	RVING041996
NIG	66 g/ g	~~16~~ 8"	Sample ID	RVNIG041996
NING	60 g/ g	8"	Sample ID	RVNING041996

TO Site

G	g/ g	Sample ID	
NG	g/ g	Sample ID	

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 4 / 19 / ____ Weather Clear 45°F

Sampling Team: Bill Spencer / ____

Intersection: Diamond & King (Diamond only)

Track Out Site Present: Y / N (N circled) Air Quality Site: Y / N (Y circled)

Y	N		Comments
✓		Photos taken of all transects	
✓		Photos taken from all photo stations	Photos taken on the following morning
		Trackout site sampled (if present)	
✓		Air quality samples collected (if appropriate)	
✓		All transects and strata sampled	

Vacuum Bag Tare Weights/Total Sample Weight ✓ BS 5/13

Site Diamond — Transect width — check from photos may be 8"

	Weight	Transect width		Sample ID
IG	66 g/ g	~~16~~ 8"	Sample ID	DMIG041996
ING	g/ g	8"	Sample ID	DMING041996 + AQ
NIG	g/ g	~~16~~ 8"	Sample ID	DMNIG041996
NING	g/ g	8"	Sample ID	DMNING041996 + AQ

Site ________ King Sampled later (4/25)

IG	g/ g	Sample ID	
ING	g/ g	Sample ID	
NIG	g/ g	Sample ID	
NING	g/ g	Sample ID	

TO Site

G	g/ g	Sample ID	
NG	g/ g	Sample ID	

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 4 / 23 / 96 Weather Over Cast 48°F Rain showers (street not wet)

Sampling Team: B. Spencer /

Intersection: 16th + Columbine

Track Out Site Present: Y / N Air Quality Site: Y / N

Y	N		Comments
✓		Photos taken of all transects	
✓		Photos taken from all photo stations	
N/A		Trackout site sampled (if present)	
✓		Air quality samples collected (if appropriate)	~~Air Quality on Columbine only~~
✓		All transects and strata sampled	~~Rain shower stopped sampling~~

Vacuum Bag Tare Weights/Total Sample Weight

Check Bag wts

Site 16th

	g/ g	Transect width		
IG	67 g/ g	16"	Sample ID	16IG042396
ING	67 g/ g	8"	Sample ID	16ING042396 +AQ
NIG	67 g/ g	16"	Sample ID	16NIG042396
NING	67 g/ g	8"	Sample ID	16NING042396 +AQ - Sampled off of Damp Pavement

Site Columbine

	g/ g			
IG	67 g/ g	16"	Sample ID	COIG042396
ING	67 g/ g	8"	Sample ID	COING042396 +AQ (2 transects only)
NIG	66 g/ g	16"	Sample ID	CONIG042396
NING	66 g/ g	8"	Sample ID	CONING042396 +AQ

TO Site

G	N/A g/ g	Sample ID	
NG	g/ g	Sample ID	

Streets swept approximately 5 days ago, parked cars left several areas of heavy deposits.

7/18/96 assumed same dates for 15th & Col @ 4/24/96

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 4/24/96 Weather 50° Overcast

Sampling Team: B. Spencer /

Intersection: 13th & Karluk

Track Out Site Present: Y / N (circled N) Air Quality Site: Y / N (circled N)

Y	N		Comments
✓		Photos taken of all transects	
✓		Photos taken from all photo stations	
		Trackout site sampled (if present)	
		Air quality samples collected (if appropriate)	
✓		All transects and strata sampled	

Vacuum Bag Tare Weights/Total Sample Weight

- First Site for new 10" Brush Attachment
- seems to be better for picking up street sweep smear.

Site 13th

		Transect width		
IG	66 g/ g	20"	Sample ID	13IG042496
ING	g/ g	10"	Sample ID	13ING042496
NIG	g/ g	20"	Sample ID	13NIG 042496
NING	g/ g	10"	Sample ID	13NING042496

Site Karluk

IG	66 g/ g	20"	Sample ID	KAIG042496
ING	g/ g	10"	Sample ID	KAING042496
NIG	g/ g	10"	Sample ID	KANIG042496
NING	g/ g	10"	Sample ID	KANING042496

TO Site

G	g/ g	Sample ID
NG	g/ g	Sample ID

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 4 / 24 / 96 Weather 40°F Clear

Sampling Team: B. Spencer /

Intersection: 36th & Old Seward

Track Out Site Present: Y / N (N circled) Air Quality Site: Y / N (Y circled)

Y	N		Comments
✓		Photos taken of all transects	
✓		Photos taken from all photo stations	
		Trackout site sampled (if present)	
✓		Air quality samples collected (if appropriate)	Ran out of Time No AQ taken
✓		All transects and strata sampled	

AQ collected 042596

Vacuum Bag Tare Weights/Total Sample Weight

Site 36th Transect width 20"

			Sample ID	
IG	65.5 g/ g	Sample ID	36IG 042496	No QC ~~call the AQ samps 0424 for simplicity~~ 11/7/96
ING	g/ g	Sample ID	36ING 042496	36ING-042596 AQ
NIG	g/ g	Sample ID	36NIG 042496	
NING	g/ g	Sample ID	36NING 042496	36NING 042596 AQ doubled transects

Site Old Seward

			Sample ID	
IG	69.5 g/ g	Sample ID	OSIG 042496	
ING	65.5 g/ g	Sample ID	OSING 042496	OSING 042596 AQ
NIG	65.5 g/ g	Sample ID	OSNIG 042496	
NING	64.5 g/ g	Sample ID	OSNING 042496	OSNING 042596 AQ doubled transects

TO Site

G	g/ g	Sample ID	
NG	g/ g	Sample ID	

See reverse for comments

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 4 / 24 / ____ Weather____________________

Sampling Team: B. Spencer / ____________________

Intersection: 36th East of Old Seward, Sampled in error, Data Submitted to lab

Track Out Site Present: Y / (N) Air Quality Site: Y / (N)

Y	N		Comments
	✓	Photos taken of all transects	
	✓	Photos taken from all photo stations	
	✓	Trackout site sampled (if present)	
	✓	Air quality samples collected (if appropriate)	
✓		All transects and strata sampled	

Vacuum Bag Tare Weights/Total Sample Weight

Site 36th E

Transect width 20"

IG	65.12 g/ g	Sample ID	36EIG042496
ING	64.75 g/ g	Sample ID	36EING042496
NIG	69.5 g/ g	Sample ID	36ENIG042496
NING	69.5 g/ g	Sample ID	36ENING042496

Site____________

IG	g/ g	Sample ID	
ING	g/ g	Sample ID	
NIG	g/ g	Sample ID	
NING	g/ g	Sample ID	

TO Site

G	g/ g	Sample ID	
NG	g/ g	Sample ID	

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 04 / 25 / 96 Weather: Clear 40°

Sampling Team: CA BS /

Intersection: Dimond & King

Track Out Site Present: Y / N   Air Quality Site: Y / N

Y	N		Comments
✓		Photos taken of all transects	
✓		Photos taken from all photo stations	Sampled 2+ weeks ago 4/5/96
N	A	Trackout site sampled (if present)	
✓		Air quality samples collected (if appropriate)	@ 11/13/96
✓		All transects and strata sampled	

Vacuum Bag Tare Weights/Total Sample Weight

Site: King   Transect width

IG	66 g/ g	10"	Sample ID	KIIG042596
ING	g/ g		Sample ID	KIING042596 AQ
NIG	g/ g		Sample ID	KINIG042596
NING	g/ g		Sample ID	KINING042596AQ 2 Transects only

Site ___

IG	g/ g	Sample ID	
ING	g/ g	Sample ID	
NIG	g/ g	Sample ID	
NING	g/ g	Sample ID	

TO Site

G	g/ g	10"	Sample ID	
NG	g/ g		Sample ID	

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 4 / 25 / 96 Weather 50°F overcast

Sampling Team: Bill Spencer /

Intersection: 15th & Columbine

Track Out Site Present: Y / N Air Quality Site: Y / N

Y	N		Comments
✓		Photos taken of all transects	Swept last week
✓		Photos taken from all photo stations	sweep smear still
N	A	Trackout site sampled (if present)	very evident 4/19/96
✓		Air quality samples collected (if appropriate)	CP
✓		All transects and strata sampled	

Vacuum Bag Tare Weights/Total Sample Weight

completed 4/25

Site 15th

		Transect width			
IG	66 g/ g	20	Sample ID	15A IG 042596	
ING	g/ g	10	Sample ID	ING	+ AQ 2 transects only S, SO
NIG	g/ g	20	Sample ID	NIG	
NING	g/ g	10	Sample ID	NING	+ AQ 2 transects

Site Columbine

IG	66 g/ g	10	Sample ID	COL IG 042596	
ING	g/ g	10	Sample ID	COL ING	+ AQ 2 transects
NIG	g/ g	10	Sample ID	COL NIG	
NING	g/ g	10	Sample ID	COL NING	+ AQ 2 transects

TO Site

G g/ g Sample ID

NG g/ g Sample ID

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 4/26/96 Weather: 45° Partly Cloudy

Sampling Team: Bill Spencer /

Intersection: 15th + E

Track Out Site Present: Y / N (circled: N) Air Quality Site: Y / N (circled: N)

Y	N		Comments
✓		Photos taken of all transects	
✓		Photos taken from all photo stations	
N	A	Trackout site sampled (if present)	
N	A	Air quality samples collected (if appropriate)	
✓		All transects and strata sampled	

Vacuum Bag Tare Weights/Total Sample Weight

Sample bags were labled for mixed sampling on the 25th - sampling discontinued and done on the 26th

Note different Date on this bag

Site 15th

	g/ g	Tran. width		
IG	66 g/ g	10"	Sample ID	15IG042596
ING	g/ g	20"	Sample ID	15ING042596
NIG	g/ g	10"	Sample ID	15NIG042696
NING	g/ g	20"	Sample ID	15NING042596

Site E st.

IG	g/ g	10"	Sample ID	EIG042596
ING	g/ g	20"	Sample ID	EING042596
NIG	g/ g	10"	Sample ID	ENIG042596
NING	✓ g/ g	20"	Sample ID	ENING042596

TO Site

G	g/ g	Sample ID	
NG	g/ g	Sample ID	

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 4 / 26 / 96 Weather 50°F Sunny

Sampling Team: Bill Spencer /

Intersection: 12th & N

Track Out Site Present: Y / N (circled) Air Quality Site: Y / N (circled)

Y	N		Comments
✓		Photos taken of all transects	
✓		Photos taken from all photo stations	
NA		Trackout site sampled (if present)	
NA		Air quality samples collected (if appropriate)	
✓		All transects and strata sampled	

Has been 2+ weeks since last sweep
~~estimate 4/12/96~~ CR 4/19/96

Vacuum Bag Tare Weights/Total Sample Weight

Test large flap bags

Site 12th — Trans. width

IG	~~8~~ 70.5 g/ g	10	Sample ID	12IG042696
ING	g/ g	↓	Sample ID	12ING042696
NIG	g/ g	↓	Sample ID	12NIG042696
NING	↓ g/ g	↓	Sample ID	12NING042696

NO 4/15 CR 12/2/96

Site N — 10"

IG	~~8~~ 70.5 g/ g	↓	Sample ID	NIG042696
ING	g/ g	↓	Sample ID	NING042696
NIG	g/ g	↓	Sample ID	NNI~~N~~G042696
NING	↓ g/ g	↓	Sample ID	NNING042696

TO Site

G	g/ g	Sample ID	
NG	g/ g	Sample ID	

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 05/22/96 Weather: 50°F Partly Cloudy, Light wind

Sampling Team: Bill Spencer /

Intersection: 21st Ave + Blue Berry

Track Out Site Present: Y / (N) Air Quality Site: Y / (N)

Y	N		Comments
✓		Photos taken of all transects	
✓		Photos taken from all photo stations	
N/A		Trackout site sampled (if present)	
	✓	Air quality samples collected (if appropriate)	
✓		All transects and strata sampled	

Vacuum Bag Tare Weights/Total Sample Weight

Site 21st Ave

	g/ g	trans. width			Transect length
IG	64.43 g/ g	10'	Sample ID	21IG052296	22'
ING	64.77 g/ g	↓	Sample ID	21ING052296	173'
NIG	64.46 g/ g	↓	Sample ID	21NIG052296	44'
NING	70.24 g/ g	↓	Sample ID	21NING052296	348'

Site

IG	g/ g	Sample ID	
ING	g/ g	Sample ID	
NIG	g/ g	Sample ID	
NING	g/ g	Sample ID	

TO Site

G	g/ g	Sample ID	
NG	g/ g	Sample ID	

Street Sediment Loads Assessment Project
Sampling Field Note Form

Swept Monday Night 5/27

Date: 5 / 30 / 96 Weather Clear 55°F

Sampling Team: B. Spence / C. Brown

Intersection: Dowling + Old Seward

Track Out Site Present: Y / N (N circled) Air Quality Site: Y / N (Y circled)

Y	N		Comments on back
___	___	Photos taken of all transects	
___	___	Photos taken from all photo stations	
___	___	Trackout site sampled (if present)	
___	✓	Air quality samples collected (if appropriate)	
___	✓	All transects and strata sampled	

Vacuum Bag Tare Weights/Total Sample Weight

Site OS @ Dowling

	Weight	width		Sample ID	Transect length
IG	g/ g	10"	Sample ID	OSDIG053096	20
ING	71.05 g/ g	10"	Sample ID	OSDING053096	AQ all 3 transects
NIG	70.05 g/ g	10"	Sample ID	OSDNIG053096	26'
NING	70.47 g/ g	10"	Sample ID	OSDNING053096	AQ 2 transects only 200 & 150

Site____________

IG	g/ g	Sample ID	
ING	g/ g	Sample ID	
NIG	g/ g	Sample ID	
NING	g/ g	Sample ID	

TO Site

G	g/ g	Sample ID	
NG	g/ g	Sample ID	

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 7/8/96 Weather Overcast 65°F

Sampling Team: B. Spencer /

Intersection: 12 + N

Track Out Site Present: Y / N (circled N) Air Quality Site: Y / N (circled N)

Y	N		Comments
✓		Photos taken of all transects	
✓		Photos taken from all photo stations	
N/A		Trackout site sampled (if present)	
N/A		Air quality samples collected (if appropriate)	
✓		All transects and strata sampled	

Vacuum Bag Tare Weights/Total Sample Weight

Site 12th Transect width (Head, 85') 10"

IG	69.87 g/ g	Sample ID	12IG070896
ING	64.55 g/ g	Sample ID	12ING070896
NIG	69.77 g/ g	Sample ID	12NIG070896
NING	67.28 g/ g	Sample ID	12NING070896

Site N 10"

IG	67.18 g/ g	Sample ID	NIG070896
ING	66.55 g/ g	Sample ID	NING070896
NIG	66.40 g/ g	Sample ID	NNIG070896
NING	67.80 g/ g	Sample ID	NNING070896

TO Site

G	g/ g	Sample ID	
NG	g/ g	Sample ID	

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 7 / 9 / 96 Weather: Partly Cloudy 65°F

Sampling Team: B. Spencer /

Intersection: 13th & Karluck

Track Out Site Present: (Y) / N Air Quality Site: Y / N

cst 7/2/96
LN 11/13/96

Y	N		Comments
	✓	Photos taken of all transects - got all of Karluk + INT+S on 13th - ran out of Film	Streets have been swept
	✓	Photos taken from all photo stations	within last week, lots of
NA		Trackout site sampled (if present)	areas missed due to parked
NA		Air quality samples collected (if appropriate)	cars.
✓		All transects and strata sampled	TO Sampled on 8/8

Vacuum Bag Tare Weights/Total Sample Weight

Site 13th

10"

IG	67.15 g/ g	Sample ID	13IG070996
ING	68.24 g/ g	Sample ID	13ING
NIG	66.66 g/ g	Sample ID	13NIG
NING	65.54 g/ g	Sample ID	13NING

Site Karluck

IG	65.32 g/ g	Sample ID	KAIG
ING	66.98 g/ g	Sample ID	KAING
NIG	66.83 g/ g	Sample ID	KANIG
NING	68.24 g/ g	Sample ID	KANING

TO Site

G	g/ g	Sample ID	
NG	g/ g	Sample ID	

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 7 / 16 / 96 Weather Clear 50°F

Sampling Team: B. Spencer /

Intersection: Diamond & King

Track Out Site Present: Y / (N) Air Quality Site: Y / (N)

Y	N		Comments
✓		Photos taken of all transects	
✓		Photos taken from all photo stations	
		Trackout site sampled (if present)	
		Air quality samples collected (if appropriate)	
✓		All transects and strata sampled	

Vacuum Bag Tare Weights/Total Sample Weight

Site Diamond

					length
IG	66.25 g/ g	10"	Sample ID	DM IG 071696	20'
ING	68.57 g/ g		Sample ID	ING	
NIG	66.59 g/ g		Sample ID	NIG	24'
NING	66.68 g/ g		Sample ID	NING	

Site King

IG	66.42 g/ g	10"	Sample ID	KIIG 071696	20'
ING	66.66 g/ g		Sample ID	KTING 071696	
NIG	66.48 g/ g		Sample ID	NIG	12
NING	65.38 g/ g		Sample ID	NING	

TO Site

G	N/A g/ g	Sample ID	
NG	g/ g	Sample ID	7/10/96 @ 11/13/96

Diamond swept on Previous Wed, Dis Rain Fri-Sun
one gutter not swept all others pretty clean

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 7/16/96 Weather 45°F Clear

Sampling Team: B. Spencer /

Intersection: N.S. & 36th

Track Out Site Present: Y / (N) Air Quality Site: Y / (N)

Y	N		Comments
✓		Photos taken of all transects	
✓		Photos taken from all photo stations	
		Trackout site sampled (if present)	
		Air quality samples collected (if appropriate)	
✓		All transects and strata sampled	

Vacuum Bag Tare Weights/Total Sample Weight

Site New Seward width length

IG	67.21g/ g	10"	Sample ID	NS IG 071696	34'	sampled ? gutter
ING	66.55g/ g		Sample ID	ING		
NIG	66.67g/ g		Sample ID	NIG	30'	on one side
NING	66.75g/ g		Sample ID	NING		50 - 200

Site 36th

IG	66.34g/ g	10"	Sample ID	36O IG 071696	20
ING	65.30 g/ g		Sample ID	ING	
NIG	66.21 g/ g		Sample ID	NIG	24
NING	66.25g/ g	20"	Sample ID	NING	

TO Site

G	g/ g	Sample ID	
NG	g/ g	Sample ID	

rotor, m... working
S. of 36th on N.S. coarse
Sediment spilled into
S.W. corner of intersection.

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 7 / 17 / 96 Weather 45° Partly Cloudy

Sampling Team: B. Spencer /

Intersection: OS @ Dowling

Track Out Site Present: Y / N (circled N) Air Quality Site: Y (circled Y) N

Y	N		Comments
✓		Photos taken of all transects	
✓		Photos taken from all photo stations	
NA		Trackout site sampled (if present)	
✓		Air quality samples collected (if appropriate)	
	✓	All transects and strata sampled	

Has not been swept since spring may be an unswept area. Sweepers stop at Dowling

Vacuum Bag Tare Weights/Total Sample Weight

Site OS width

IG	65.25 g/ g	60"	Sample ID	OSDIG071796
ING	64.90 g/ g		Sample ID	ING +AQ*
NIG	65.04 g/ g		Sample ID	NIG
NING	65.26 g/ g		Sample ID	NING +AQ*

* These samples not on COC, but results posted ~~apparently not collected~~ ~~WOK 9-23-96~~

Site

IG	g/ g	Sample ID	
ING	g/ g	Sample ID	
NIG	g/ g	Sample ID	
NING	g/ g	Sample ID	

TO Site

G	g/ g	Sample ID	
NG	g/ g	Sample ID	

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 7/17/96 Weather: 50°F Partly Cloudy

Sampling Team: B. Spencer /

Intersection: ~~O~~ O.S. & 36th

Track Out Site Present: Y / (N) Air Quality Site: (Y) / N

Y	N		Comments
✓		Photos taken of all transects	
✓		Photos taken from all photo stations	
NA		Trackout site sampled (if present)	
✓		Air quality samples collected (if appropriate)	est 7/3/96
✓		All transects and strata sampled	- Swept 2 weeks ago - 3 days since big storm

Vacuum Bag Tare Weights/Total Sample Weight

Site O S

	g/ g	Tran width		Sample ID		Tran length
IG	65.59 g/ g	10"	Sample ID	OS IG 071796		20'
ING	65.82 g/ g	20"	Sample ID	ING	+ AQ 20"	
NIG	65.72 g/ g	10"	Sample ID	NIG		24'
NING	65.05 g/ g	20"	Sample ID	NING	+ AQ 20"	

Site 36th

	g/ g			Sample ID		
IG	64.72 g/ g	10"	Sample ID	36 IG 071796		20'
ING	65.13 g/ g	20"	Sample ID	ING	+ AQ 20"	
NIG	65.60 g/ g	10"	Sample ID	NIG		24'
NING	65.31 g/ g	20"	Sample ID	NING	+ AQ 20"	

TO Site

G g/ g Sample ID

NG g/ g Sample ID

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 7/17/96 Weather 50° partly cloudy

Sampling Team: B Span /

Intersection: 5th & Reeve

Track Out Site Present: Y / N (circled N) Air Quality Site: Y / N

Y	N		Comments
✓		Photos taken of all transects	
✓		Photos taken from all photo stations	
NA		Trackout site sampled (if present)	
	✓	Air quality samples collected (if appropriate)	
✓		All transects and strata sampled	

Recent Sweep < 1wk on 5th
Sweep smear still visible in Gutter

Vacuum Bag Tare Weights/Total Sample Weight

Site 5th width

IG	65.69 g/ g	10"	Sample ID	5IG071796
ING	65.62 g/ g	↓	Sample ID	ING
NIG	65.59 g/ g		Sample ID	NIG
NING	66.90 g/ g		Sample ID	NING

est 7/12/96
ER 11/10/96

Site Reeve

IG	64.97 g/ g		Sample ID	RVIG071796
ING	66.29 g/ g		Sample ID	ING
NIG	67.15 g/ g		Sample ID	NIG
NING	66.35 g/ g	↓	Sample ID	NING

TO Site

G	g/ g	Sample ID	
NG	g/ g	Sample ID	

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 7/24/96 Weather: Overcast 70°F

Sampling Team: D. Sr... /

Intersection: DeBarr & Muldoon

Track Out Site Present: Y / N (N circled) Air Quality Site: Y / N (N circled)

est 7/22/96
EP 11/19/96

Y	N		Comments
✓		Photos taken of all transects	
✓		Photos taken from all photo stations	Swept about 2-3 days ago
N/A		Trackout site sampled (if present)	
N/A		Air quality samples collected (if appropriate)	
✓		All transects and strata sampled	Gutters only, J.G.

Vacuum Bag Tare Weights/Total Sample Weight

Site Muldoon

	Weight	Width		Sample ID	Length
IG	68.62 g/ g	10"	Sample ID	MULIG072496	20'
ING	g/ g		Sample ID		
NIG	68.72 g/ g	10"	Sample ID	MULNIG072496	24'
NING	g/ g		Sample ID		

Site DeBarr

	Weight	Width		Sample ID	Length
IG	68.79 g/ g	10"	Sample ID	DEBIG072496	22'
ING	g/ g		Sample ID		
NIG	67.12 g/ g	10"	Sample ID	DEBNIG072496	24'
NING	g/ g		Sample ID		

TO Site

G	g/ g	Sample ID	
NG	g/ g	Sample ID	

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 7 / 24 / 96 Weather: Overcast 50°F

Sampling Team: B. Spence /

Intersection: Iowa & Spanard

Track Out Site Present: Y / N (circled N) Air Quality Site: Y / N (circled N)

Y	N		Comments
✓		Photos taken of all transects	
✓		Photos taken from all photo stations	
N/A		Trackout site sampled (if present)	
N/A		Air quality samples collected (if appropriate)	
✓		All transects and strata sampled	Gutter only

Vacuum Bag Tare Weights/Total Sample Weight

Site: Spanard

	Weight	width		Sample ID	length
IG	68.56 g/ g	10"	Sample ID	SPIG 072496	
ING	g/ g		Sample ID		
NIG	67.80 g/ g	10"	Sample ID	SPNIG 072496	
NING	g/ g		Sample ID		

Site: Iowa

	Weight	width		Sample ID
IG	67.44 g/ g	10"	Sample ID	IOWIG072496
ING	g/ g		Sample ID	
NIG	67.30 g/ g	10"	Sample ID	IOW NIG 072496
NING	g/ g		Sample ID	

TO Site

G	g/ g	Sample ID	
NG	g/ g	Sample ID	

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 7 / 25-26 / 96

Intersection: 6th & A Weather: Overcast 50°F

Sampling Team: B Spencer / C. Brown

Track Out Site Present: (Y) / N , Air Quality Site: Y / (N) Gutter Only: (Y) / N

(Y) N Photos taken of all transects

(Y) N Photos taken from all photo stations

(Y) N Trackout site sampled (if present)

(Y) N Air quality samples collected (if appropriate) TO Area Only

(Y) N All transects and strata sampled

Site 6th

Vacuum Bag Tare Weights				Air Quality	Transect width / length
IG	68.50 g	Sample ID	6IG 072496		10" / 12'
ING	g	Sample ID			/
NIG	68.86 g	Sample ID	6NIG 072496		10" / 12'
NING	g	Sample ID			/

Site A

IG	67.52 g	Sample ID	AIG072696		10" / 12'
ING	g	Sample ID			/
NIG	67.8 g	Sample ID	ANIG072696		10" / 12'
NING	g	Sample ID			/

Track Out Site A

TOG	66.82 g	Sample ID	ATOG072696		10" / 12'
TONG	67.50 g	Sample ID	ATONG072696	+AQ	10" / 41'
NTOG	67.10 g	Sample ID	ANTOG072696		10" / 12'
NTONG	66.94 g	Sample ID	ANTONG072696	+AQ	10" / 41'
TO Alley	67.31		ATOAlley072696	+AQ	10"

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 7 / 26 / 96

Intersection: Nits & Denali Weather Overcast 45°F

Sampling Team: B. Spencer / C. Brown

Track Out Site Present: Y / N Air Quality Site: Y / N Gutter Only: Y / N

Y N Photos taken of all transects

Y N Photos taken from all photo stations

Y N Trackout site sampled (if present) N/A

Y N Air quality samples collected (if appropriate) N/A

Y N All transects and strata sampled

Site Denali

Vacuum Bag Tare Weights			Sample ID		Air Quality	Transect width / length
IG	67.30 g	Sample ID	DenIG 072696			10" /
ING	g	Sample ID				/
NIG	67.37 g	Sample ID	DENNIG 072696			/
NING	g	Sample ID				/

Site NLTB

IG	67.09 g	Sample ID	NLTBIG 072696			/
ING	g	Sample ID				/
NIG	67.68 g	Sample ID	NLTBNIG 072696			/
NING	g	Sample ID				/

Track Out Site ______

TOG	g	Sample ID				/
TONG	g	Sample ID				/
NTOG	g	Sample ID				/
NTONG	g	Sample ID				/

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 07 / 26 / 96

Intersection: NLHS + Spenard Weather Overcast 45°F

Sampling Team: B. Spencer / C. Brown

Track Out Site Present: Y / N Air Quality Site: Y / N , Gutter Only: Y / N

Y N Photos taken of all transects

Y N Photos taken from all photo stations

~~Y N~~ Trackout site sampled (if present)

Y N Air quality samples collected (if appropriate)

Y N All transects and strata sampled Transect 112 not Sampled (Adjust length Accordingly)

Site NLHS

Vacuum Bag Tare Weights				Air Quality	Transect width / length
IG	67.43g	Sample ID	NLHS IG 072696		10" / 14'
ING	67.67g	Sample ID	ING	+ AQ	10" / 48.3+ ~~58.6~~ +24'
NIG	66.89g	Sample ID	NIG		10" / 28'
NING	67.30g	Sample ID	NING	+ AQ	10" / (44.3) + (?)

Transect 112 not Sampled

Site ______

IG	____g	Sample ID			/
ING	____g	Sample ID			/
NIG	____g	Sample ID			/
NING	____g	Sample ID			/

Track Out Site ______

TOG	____g	Sample ID			/
TONG	____g	Sample ID			/
NTOG	____g	Sample ID			/
NTONG	____g	Sample ID			/

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 08 / 06 / 96

Intersection: 15th + Columbine Weather: Clear 50°F light wind

Sampling Team: Bill Spence /

Track Out Site Present: Y / N , Air Quality Site: Y / N , Gutter Only: Y / N

Y N Photos taken of all transects

Y N Photos taken from all photo stations ~~except Col 150, 200, NE~~ 8/8 B.S.

Y N Trackout site sampled (if present)

Y N Air quality samples collected (if appropriate)

Y N All transects and strata sampled

completed 08/06

Site 15th

Vacuum Bag Tare Weights				Air Quality	Transect width / length	
IG	66.10 g	Sample ID	15AIG080696		10" /	
ING	66.39 g	Sample ID	15AING080696	+ AQ	/	AQ 2 Transect. 5, 50
NIG	66.12 g	Sample ID	15ANIG080696		/	
NING	65.80 g	Sample ID	15ANING080696	+ AQ	/	AQ 2 Transect. 100, 150

Site Columbine

Sample 8/7

IG	65.43 g	Sample ID	COLIG080696		/	
ING	67.16 g	Sample ID	COLING080696	+ AQ	/	3 tran
NIG	65.40 g	Sample ID	COLNIG080696		/	
NING	65.85 g	Sample ID	COLNING080696	+ AQ	/	3 tran

Track Out Site 15

TOG	66.50 g	Sample ID	15ATOG080696		/	
TONG	66.38 g	Sample ID	15ATONG	+ AQ	/	1,5 transect.
NTOG	66.25 g	Sample ID	15ANTOG		/	
NTONG	66.28 g	Sample ID	15ANTONG	+ AQ	/	3 transect.
TOAlley	66.37	Sample ID	15ATOAIG080696	+ AQ	/	

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 8 / 6 / 96

Intersection: 16th + Columbine Weather Clear 48°F

Sampling Team: B. Spencer /

Track Out Site Present: Y / N , Air Quality Site: Y / N Gutter Only: Y / N

Y N Photos taken of all transects photos taken 8/8

Y N Photos taken from all photo stations

Y N Trackout site sampled (if present)

N/A Air quality samples collected (if appropriate)

Y N All transects and strata sampled

Site 16th

Vacuum Bag Tare Weights		Sample ID		Air Quality	Transect width / length
IG	66.12 g	Sample ID	16IG 080596		10" /
ING	66.85 g	Sample ID	16 ING		/
NIG	66.51 g	Sample ID	16 NIG		/
NING	66.42 g	Sample ID	16NING		/

Site Columbine

IG	64.70 g	Sample ID	CO IG 080696		/
ING	64.96 g	Sample ID	COING		/
NIG	64.88 g	Sample ID	CONIG		/
NING	66.97 g	Sample ID	CONING		/

Track Out Site 16th TO

TOG	66.81 g	Sample ID	16TOG 080676		/ 16'
TONG	66.71 g	Sample ID	16TONG		/
NTOG	66.50 g	Sample ID	16NTOG		/
NTONG	66.65 g	Sample ID	16NTONG		/

TO Alley 65.15

16TOAlley 080696

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 8 / 7 / 96

Intersection: 15^{th} & E Weather: Clear 60°F

Sampling Team: B. Spencer / C. West

Track Out Site Present: Y / (N) Air Quality Site: Y / (N) Gutter Only: Y / (N)

(Y) N Photos taken of all transects Took loads mostly of the gutter, where the dirt was

(Y) N Photos taken from all photo stations

~~Y~~/~~N~~ Trackout site sampled (if present)

~~Y~~/~~N~~ Air quality samples collected (if appropriate)

(Y) N All transects and strata sampled

Site 15

Vacuum Bag Tare Weights				Air Quality	Transect width / length
IG	64.73g	Sample ID	15IG080796		10" /
ING	65.31g	Sample ID	15ING		/
NIG	65.30g	Sample ID	15NIG		/
NING	66.58 g	Sample ID	15NING		/

Site E

				Air Quality	Transect width / length
IG	65.35 g	Sample ID	EIG080796		10" /
ING	65.49	Sample ID	EING		/
NIG	66.55g	Sample ID	ENIG		/
NING	65.16g	Sample ID	ENING		/

Track Out Site

				Air Quality	Transect width / length
TOG	g	Sample ID			/
TONG	g	Sample ID			/
NTOG	g	Sample ID			/
NTONG	g	Sample ID			/

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 8 / 7 / 96

Intersection: 20th & Lk Otis Weather Clear 65°F

Sampling Team: D. Spencer / C. West

Track Out Site Present: Y / N, Air Quality Site: Y / N Gutter Only: Y / N

Y N Photos taken of all transects

Y N Photos taken from all photo stations

N/A Trackout site sampled (if present)

N/A Air quality samples collected (if appropriate)

Y N All transects and strata sampled

Site 20th

Vacuum Bag Tare Weights				Air Quality	Transect width / length
IG	65.59 g	Sample ID	20IG 080796		10" / 12'
ING	g	Sample ID			/
NIG	64.80 g	Sample ID	20NIG 080796		10" / 12'
NING	g	Sample ID			/

Site Lk Otis

IG	66.64 g	Sample ID	LkOtIG 080796		10" / 12'
ING	g	Sample ID			/
NIG	66.66 g	Sample ID	LkOtNIG 080796		10" / 12'
NING	g	Sample ID			/

Track Out Site

TOG	g	Sample ID			/
TONG	g	Sample ID			/
NTOG	g	Sample ID			/
NTONG	g	Sample ID			/

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 8 / 8 / 96

Intersection: 13th & Karluk Weather 50°F overcast

Sampling Team: B. Spencer /

Track Out Site Present: Y N , Air Quality Site: Y / N , Gutter Only: Y / N

Y N Photos taken of all transects

Y N Photos taken from all photo stations Track out & Non Track out

Y N Trackout site sampled (if present)

N/A Air quality samples collected (if appropriate)

Y N All transects and strata sampled Track out & Non Track out

Site

Vacuum Bag Tare Weights				Air Quality	Transect width / length
IG	g	Sample ID			/
ING	g	Sample ID			/
NIG	g	Sample ID			/
NING	g	Sample ID			/

Site

IG	g	Sample ID			/
ING	g	Sample ID			/
NIG	g	Sample ID			/
NING	g	Sample ID			/

Track Out Site 13th

TOG	66.90g	Sample ID	13TOG 080896		10" /
TONG	66.47g	Sample ID	13TONG	10"	/
NTOG	66.55g	Sample ID	13 NTOG		/
NTONG	67.21g	Sample ID	13NTONG	10"	/
TOAIG	66.70		13TOAIG	10"	

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 8 / 8 / 96

Intersection: 9th + Karluk Weather Overcast 50°

Sampling Team: B. Spencer /

Track Out Site Present: Y / N , Air Quality Site: Y / N Gutter Only: Y / N

Y N Photos taken of all transects

Y N Photos taken from all photo stations

Y N Trackout site sampled (if present)

NA Air quality samples collected (if appropriate)

Y N All transects and strata sampled

Site Karluk

Vacuum Bag Tare Weights				Air Quality	Transect width / length
IG	66.54g	Sample ID	KB IG 080896		10" /
ING	66.94g	Sample ID	KB ING	✓	/
NIG	66.66g	Sample ID	KB NIG		/
NING	67.00g	Sample ID	KB NING	✓	/

Site 9th

IG	66.60 g	Sample ID	9 IG 080896		/
ING	66.45 g	Sample ID	9 ING	✓	/
NIG	66.72 g	Sample ID	9 NIG		/
NING	66.75 g	Sample ID	9 NING	✓	/

Track Out Site Karluk

TOG	65.11 g	Sample ID	KBTOG 080896		/
TONG	65.05 g	Sample ID	KBTONG		/
NTOG	66.02 g	Sample ID	KBNTOG		/
NTONG	65.86 g	Sample ID	KBNTONG		/

TO Alley 67.64 KBTOAlley 080896

Street Sediment Loads Assessment Project
Sampling Field Note Form

Date: 8 / 12 / 96

Intersection: 21st & Blueberry Weather partly Sunny 50°F

Sampling Team: O. Spencer /

Track Out Site Present: Y / N (N circled) Air Quality Site: Y / N (N circled) Gutter Only: Y / N (N circled)

Y N Photos taken of all transects (Y circled)

Y N Photos taken from all photo stations (Y circled)

N/A Trackout site sampled (if present)

N/A Air quality samples collected (if appropriate)

Y N All transects and strata sampled (Y circled)

Site 21st Ave

Vacuum Bag Tare Weights				Air Quality	Transect width / length
IG	66.05 g	Sample ID	21IG081296		10" / ~~12'~~ 22'
ING	65.35 g	Sample ID	21ING081296		" / 183'
NIG	65.43 g	Sample ID	21NIG081296		" / 44'
NING	65.34 g	Sample ID	21NING081296		" / 348'

Site

IG	g	Sample ID			/
ING	g	Sample ID			/
NIG	g	Sample ID			/
NING	g	Sample ID			/

Track Out Site

TOG	g	Sample ID			/
TONG	g	Sample ID			/
NTOG	g	Sample ID			/
NTONG	g	Sample ID			/

Construction area has impacted area with sediments and wash from concrete operation.

Round 1 Particle Size Distribution (Sieve Analysis) Plots

GRAIN SIZE DISTRIBUTION TEST DATA

Test No.: 1

Da' : 4-29-95
P. ct No.: 1801.0441
Pro ect: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: 5IG032796
Sample Description: POORLY GRADED SAND WITH SILT
USCS Class: SP-SM
Liquid limit:
AASHTO Class:
Plasticity index:

Notes

Remarks:

Fig. No.: 6

Mechanical Analysis Data

	Initial
Dry sample and tare=	1127.20
Tare =	162.90
Dry sample weight =	964.30

Tare for cumulative weight retained= 228

eve	Cumul. Wt. retained	Percent finer
0.5 inches	228.00	100.0
0.375 inches	258.00	96.9
# 4	393.10	82.9
# 10	716.30	49.4
# 20	838.30	36.7
# 40	931.30	27.1
# 100	1082.10	11.4
# 140	1118.50	7.7
# 200	1137.50	5.7

Fractional Components

% + 75mm. = 0.0 % GRAVEL = 17.1 % SAND = 77.2
% FINES = 5.7

D85= 5.07 D60= 2.688 D50= 2.039
D30= 0.5064 D15= 0.19253 D10= 0.13167
Cc = 0.7244 Cu = 20.4174

GRAIN SIZE DISTRIBUTION TEST DATA

Test No.: 12

Date : 4-29-95
Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: 5ING032796
Sample Description: POORLY GRADED SAND
USCS Class: SP
AASHTO Class:
Liquid limit:
Plasticity index:

Notes

Remarks:

Fig. No.:

Mechanical Analysis Data

	Initial
Dry sample and tare =	1481.10
Tare =	222.30
Dry sample weight =	1258.80

Tare for cumulative weight retained= 223.4

Sieve	Cumul. Wt. retained	Percent finer
0.375 inches	223.40	100.0
# 4	304.70	93.5
# 10	694.90	62.5
# 20	907.20	45.7
# 40	1074.10	32.4
# 100	1345.00	10.9
# 140	1399.30	6.6
# 200	1421.40	4.8

Fractional Components

% + 75mm. = 0.0 % GRAVEL = 6.5 % SAND = 88.7
% FINES = 4.8

D85= 3.62 D60= 1.834 D50= 1.105
D30= 0.3745 D15= 0.18772 D10= 0.13916
Cc = 0.5495 Cu = 13.1826

GRAIN SIZE DISTRIBUTION TEST REPORT



	Test	%+75 mm	% GRAVEL	% SAND	% SILT	% CLAY
●	1	0.0	17.1	77.2	5.7	
▲	12	0.0	6.5	88.7	4.8	

	LL	PI	D_{85}	D_{60}	D_{50}	D_{30}	D_{15}	D_{10}	C_c	C_u
●			5.07	2.69	2.04	0.506	0.1925	0.1317	0.72	20.4
▲			3.62	1.83	1.11	0.375	0.1877	0.1392	0.55	13.2

MATERIAL DESCRIPTION	USCS	AASHTO
● POORLY GRADED SAND WITH SILT	SP-SM	
▲ POORLY GRADED SAND	SP	

Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING
● Location: 5IG032796
▲ Location: 5ING032796

Date: 4-29-95

Remarks:

GRAIN SIZE DISTRIBUTION TEST REPORT

RODNEY P. KINNEY ASSOCIATES

Figure No. 6

GRAIN SIZE DISTRIBUTION TEST DATA   Test No.: 14

Da' :   4-29-95
P: ict No.:   1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: 5NING032796
Sample Description: POORLY GRADED SAND
USCS Class: SP   Liquid limit:
AASHTO Class: Plasticity index:

Notes

Remarks:

Fig. No.:

Mechanical Analysis Data

Initial
Dry sample and tare= 1522.10
Tare = 247.10
Dry sample weight = 1275.00
Tare for cumulative weight retained= 247.1

?eve	Cumul. Wt. retained	Percent finer
0.375 inches	247.10	100.0
# 4	333.20	93.2
# 10	683.30	65.8
# 20	923.50	46.9
# 40	1147.20	29.4
# 100	1415.80	8.3
# 140	1468.00	4.2
# 200	1492.10	2.4

Fractional Components

% + 75mm. = 0.0   % GRAVEL = 6.8   % SAND = 90.9
% FINES = 2.3

D85= 3.54 D60= 1.596 D50= 0.972
D30= 0.4290 D15= 0.22004 D10= 0.16501
Cc = 0.6990 Cu = 9.6716

GRAIN SIZE DISTRIBUTION TEST DATA   Test No.: 13

Da+ - :   4-29-95
Pr   ct No.:   1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: 5NIG032796
Sample Description: POORLY GRADED SAND WITH SILT
USCS Class: SP-SM   Liquid limit:
AASHTO Class: Plasticity index:

Notes

Remarks:

Fig. No.: 7

Mechanical Analysis Data

Initial
Dry sample and tare= 1257.60
Tare = 226.40
Dry sample weight = 1031.20
Tare for cumulative weight retained= 228

ve	Cumul. Wt. retained	Percent finer
0.75 inches	228.00	100.0
0.375 inches	250.80	97.8
# 4	331.90	89.9
# 10	561.70	67.6
# 20	700.70	54.2
# 40	851.70	39.5
# 100	1089.80	16.4
# 140	1141.50	11.4
# 200	1168.00	8.8

Fractional Components

% + 75mm. = 0.0   % GRAVEL = 10.1   % SAND = 81.1
% FINES = 8.8

D85= 3.85 D60= 1.259 D50= 0.668
D30= 0.2818 D15= 0.13646 D10= 0.08810
Cc = 0.7161 Cu = 14.2889

GRAIN SIZE DISTRIBUTION TEST REPORT



	Test	%+75 mm	% GRAVEL	% SAND	% SILT	% CLAY
●	13	0.0	10.1	81.1	8.8	
▲	14	0.0	6.8	90.9	2.3	

	LL	PI	D_{85}	D_{60}	D_{50}	D_{30}	D_{15}	D_{10}	C_c	C_u
●			3.85	1.26	0.67	0.282	0.1365	0.0881	0.72	14.3
▲			3.54	1.60	0.97	0.429	0.2200	0.1650	0.70	9.7

MATERIAL DESCRIPTION	USCS	AASHTO
● POORLY GRADED SAND WITH SILT	SP-SM	
▲ POORLY GRADED SAND	SP	

Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING
● Location: 5NIG032796
▲ Location: 5NING032796

Date: 4-29-95

Remarks:

GRAIN SIZE DISTRIBUTION TEST REPORT
RODNEY P. KINNEY ASSOCIATES

Figure No. 7

GRAIN SIZE DISTRIBUTION TEST DATA   Test No.: 8

Da+ :   4-29-95
P ct No.:   1801.0441
Pr ject: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: 5NING032796AQ
Sample Description: POORLY GRADED SAND WITH SILT
USCS Class: SP-SM   Liquid limit:
AASHTO Class: Plasticity index:

Notes

Remarks:

Fig. No.:

Mechanical Analysis Data

Initial
Dry sample and tare= 743.30
Tare = 169.50
Dry sample weight = 573.80
Tare for cumulative weight retained= 230.8

eve	Cumul. Wt. retained	Percent finer
0.375 inches	230.80	100.0
# 4	235.60	99.2
# 10	329.30	82.8
# 20	449.40	61.9
# 40	561.30	42.4
# 100	710.10	16.5
# 140	740.00	11.3
# 200	746.70	10.1

Fractional Components

% + 75mm. = 0.0   % GRAVEL = 0.8   % SAND = 89.1
% FINES = 10.1

D85= 2.19 D60= 0.782 D50= 0.547
D30= 0.2676 D15= 0.13725

GRAIN SIZE DISTRIBUTION TEST DATA   Test No.: 7

Date: 4-29-95
Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: 5ING032796AQ
Sample Description: POORLY GRADED SAND WITH SILT
USCS Class: SP-SM   Liquid limit:
AASHTO Class: Plasticity index:

Notes

Remarks:

Fig. No.: 24

Mechanical Analysis Data

Initial
Dry sample and tare= 1178.30
Tare = 227.00
Dry sample weight = 951.30
Tare for cumulative weight retained= 227

Sieve	Cumul. Wt. retained	Percent finer
0.375 inches	227.00	100.0
# 4	263.70	96.1
# 10	512.40	70.0
# 20	679.00	52.5
# 40	820.70	37.6
# 100	1042.80	14.2
# 140	1092.10	9.1
# 200	1115.40	6.6

Fractional Components

% + 75mm. = 0.0   % GRAVEL = 3.9   % SAND = 89.5
% FINES = 6.6

D85= 3.16 D60= 1.274 D50= 0.733
D30= 0.3055 D15= 0.15488 D10= 0.11350
Cc = 0.6457 Cu = 11.2202

GRAIN SIZE DISTRIBUTION TEST REPORT



	Test	%+75mm	% GRAVEL	% SAND	% SILT	% CLAY
●	7	0.0	3.9	89.5	6.6	
▲	8	0.0	0.8	89.1	10.1	

	LL	PI	D_{85}	D_{60}	D_{50}	D_{30}	D_{15}	D_{10}	C_c	C_u
●			3.16	1.27	0.73	0.305	0.1549	0.1135	0.65	11.2
▲			2.19	0.78	0.55	0.268	0.1372			

MATERIAL DESCRIPTION	USCS	AASHTO
● POORLY GRADED SAND WITH SILT	SP-SM	
▲ POORLY GRADED SAND WITH SILT	SP-SM	

Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING
● Location: 5ING032796AQ
▲ Location: 5NING032796AQ

Date: 4-29-95

Remarks:

GRAIN SIZE DISTRIBUTION TEST REPORT
RODNEY P. KINNEY ASSOCIATES

Figure No. 24

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST DATA

Test No.: 15

Da : 4-29-95
P ect No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: 12IG032696
Sample Description: POORLY GRADED SAND WITH SILT
USCS Class: SP-SM
Liquid limit:
AASHTO Class:
Plasticity index:

Notes

Remarks:

Fig. No.: 8

Mechanical Analysis Data

Initial
Dry sample and tare= 1091.60
Tare = 169.30
Dry sample weight = 922.30
Tare for cumulative weight retained= 169.3

eve	Cumul. Wt. retained	Percent finer
0.75 inches	169.30	100.0
0.5 inches	180.20	98.8
0.375 inches	202.90	96.4
# 4	399.50	75.0
# 10	752.20	36.8
# 20	842.20	27.0
# 40	902.90	20.5
# 100	998.30	10.1
# 140	1021.70	7.6
# 200	1033.70	6.3

Fractional Components

% + 75mm. = 0.0 % GRAVEL = 25.0 % SAND = 68.8
% FINES = 6.2

D85= 6.10 D60= 3.467 D50= 2.818
D30= 1.3646 D15= 0.25119 D10= 0.14622
Cc = 3.6728 Cu = 23.7137

GRAIN SIZE DISTRIBUTION TEST DATA   Test No.: 16

Da :   4-29-95
Pr ect No.:   1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: 12ING032696
Sample Description: POORLY GRADED SAND WITH SILT
USCS Class: SP-SM   Liquid limit:
AASHTO Class: Plasticity index:

Notes

Remarks:

Fig. No.:

Mechanical Analysis Data

	Initial
Dry sample and tare=	842.60
Tare =	161.50
Dry sample weight =	681.10

Tare for cumulative weight retained= 162.4

eve	Cumul. Wt. retained	Percent finer
0.375 inches	162.40	100.0
# 4	215.10	92.3
# 10	518.50	47.7
# 20	661.30	26.8
# 40	703.80	20.5
# 100	773.90	10.2
# 140	792.70	7.5
# 200	802.10	6.1

Fractional Components

% + 75mm. = 0.0   % GRAVEL = 7.7   % SAND = 86.2
% FINES = 6.1

D85= 3.98 D60= 2.532 D50= 2.099
D30= 1.0765 D15= 0.23823 D10= 0.14521
Cc = 3.1514 Cu = 17.4381

GRAIN SIZE DISTRIBUTION TEST REPORT



	Test	%+75mm	% GRAVEL	% SAND	% SILT	% CLAY
●	15	0.0	25.0	68.8	6.2	
▲	16	0.0	7.7	86.2	6.1	

	LL	PI	D_{85}	D_{60}	D_{50}	D_{30}	D_{15}	D_{10}	C_c	C_u
●			6.10	3.47	2.82	1.365	0.2512	0.1462	3.67	23.7
▲			3.98	2.53	2.10	1.076	0.2382	0.1452	3.15	17.4

MATERIAL DESCRIPTION	USCS	AASHTO
● POORLY GRADED SAND WITH SILT	SP-SM	
▲ POORLY GRADED SAND WITH SILT	SP-SM	

Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING
● Location: 12IG032696
▲ Location: 12ING032696

Date: 4-29-95

Remarks:

GRAIN SIZE DISTRIBUTION TEST REPORT
RODNEY P. KINNEY ASSOCIATES

Figure No. 8

GRAIN SIZE DISTRIBUTION TEST DATA Test No.: 18

Da+ · 4-29-95
P: ct No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: 12NING032696
Sample Description: WELL GRADED SAND
USCS Class: SW Liquid limit:
AASHTO Class: Plasticity index:

Notes

Remarks:

Fig. No.:

Mechanical Analysis Data

Initial
Dry sample and tare= 892.10
Tare = 164.70
Dry sample weight = 727.40
Tare for cumulative weight retained= 164.7

ve	Cumul. Wt. retained	Percent finer
0.375 inches	164.70	100.0
# 4	179.00	98.0
# 10	315.30	79.3
# 20	548.60	47.2
# 40	677.40	29.5
# 100	808.70	11.5
# 140	841.30	7.0
# 200	857.90	4.7

Fractional Components

% + 75mm. = 0.0 % GRAVEL = 2.0 % SAND = 93.3
% FINES = 4.7

D85= 2.40 D60= 1.189 D50= 0.911
D30= 0.4261 D15= 0.18599 D10= 0.13320
Cc = 1.1468 Cu = 8.9228

GRAIN SIZE DISTRIBUTION TEST DATA   Test No.: 17

Da-: 4-29-95
Pr ct No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: 12NIG032696
Sample Description: WELL GRADED SAND WITH SILT
USCS Class: SW-SM   Liquid limit:
AASHTO Class: Plasticity index:

Notes

Remarks:

Fig. No.: 9

Mechanical Analysis Data

Initial
Dry sample and tare= 823.10
Tare = 227.20
Dry sample weight = 595.90
Tare for cumulative weight retained= 231.2

ve	Cumul. Wt. retained	Percent finer
1 inches	231.20	100.0
0.75 inches	277.10	92.3
0.375 inches	344.80	80.9
# 4	431.80	66.3
# 10	526.80	50.4
# 20	629.70	33.1
# 40	687.70	23.4
# 100	762.10	10.9
# 140	777.40	8.3
# 200	782.70	7.5

Fractional Components

% + 75mm. = 0.0   % GRAVEL = 33.7   % SAND = 58.9
% FINES = 7.4

D85= 12.45 D60= 3.388 D50= 1.950
D30= 0.6839 D15= 0.21627 D10= 0.13183
Cc = 1.0471 Cu = 25.7040

GRAIN SIZE DISTRIBUTION TEST REPORT



	Test	%+75mm	% GRAVEL	% SAND	% SILT	% CLAY
●	17	0.0	33.7	58.9	7.4	
▲	18	0.0	2.0	93.3	4.7	

	LL	PI	D_{85}	D_{60}	D_{50}	D_{30}	D_{15}	D_{10}	C_c	C_u
●			12.45	3.39	1.95	0.684	0.2163	0.1318	1.05	25.7
▲			2.40	1.19	0.91	0.426	0.1860	0.1332	1.15	8.9

MATERIAL DESCRIPTION	USCS	AASHTO
● WELL GRADED SAND WITH SILT	SW-SM	
▲ WELL GRADED SAND	SW	

Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING
● Location: 12NIG032696
▲ Location: 12NING032696

Date: 4-29-95

Remarks:

GRAIN SIZE DISTRIBUTION TEST REPORT
RODNEY P. KINNEY ASSOCIATES

Figure No. 9

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST DATA — Test No.: 19

Da+ -: 4-29-95
P: .ct No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: 15IG032796
Sample Description: POORLY GRADED SAND WITH SILT
USCS Class: SP-SM   Liquid limit:
AASHTO Class: Plasticity index:

Notes

Remarks:

Fig. No.: 10

Mechanical Analysis Data

Initial
Dry sample and tare= 1290.70
Tare = 230.80
Dry sample weight = 1059.90
Tare for cumulative weight retained= 231.2

ve	Cumul. Wt. retained	Percent finer
0.75 inches	231.20	100.0
0.375 inches	237.20	99.4
# 4	375.20	86.4
# 10	686.90	57.0
# 20	870.80	39.7
# 40	981.40	29.2
# 100	1158.50	12.5
# 140	1197.50	8.8
# 200	1207.30	7.9

Fractional Components

% + 75mm. = 0.0   % GRAVEL = 13.6   % SAND = 78.5
% FINES = 7.9

D85= 4.52 D60= 2.203 D50= 1.507
D30= 0.4395 D15= 0.17701 D10= 0.11967
Cc = 0.7328 Cu = 18.4077

GRAIN SIZE DISTRIBUTION TEST DATA   Test No.: 20

Da :   4-29-95
Pr ect No.:   1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: 15ING032796
Sample Description: POORLY GRADED SAND
USCS Class: SP   Liquid limit:
AASHTO Class: Plasticity index:

Notes

Remarks:

Fig. No.:

Mechanical Analysis Data

	Initial
Dry sample and tare=	583.60
Tare =	186.60
Dry sample weight =	397.00

Tare for cumulative weight retained= 186.6

eve	Cumul. Wt. retained	Percent finer
0.375 inches	186.60	100.0
# 4	196.10	97.6
# 10	358.90	56.6
# 20	492.20	23.0
# 40	545.00	9.7
# 100	579.00	1.2
# 140	581.20	0.6
# 200	582.60	0.3

Fractional Components

% + 75mm. = 0.0   % GRAVEL = 2.4   % SAND = 97.4
% FINES = 0.2

D85= 3.41 D60= 2.133 D50= 1.750
D30= 1.0617 D15= 0.58345 D10= 0.42756
Cc = 1.2359 Cu = 4.9888

GRAIN SIZE DISTRIBUTION TEST REPORT



	Test	%+75 mm	% GRAVEL	% SAND	% SILT	% CLAY
●	19	0.0	13.6	78.5	7.9	
▲	20	0.0	2.4	97.4	0.2	

	LL	PI	D_{85}	D_{60}	D_{50}	D_{30}	D_{15}	D_{10}	C_c	C_u
●			4.52	2.20	1.51	0.440	0.1770	0.1197	0.73	18.4
▲			3.35	2.13	1.75	1.067	0.5794	0.4246	1.26	5.0

MATERIAL DESCRIPTION	USCS	AASHTO
● POORLY GRADED SAND WITH SILT	SP-SM	
▲ POORLY GRADED SAND	SP	

Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING
● Location: 15IG032796
▲ Location: 15ING032796

Date: 4-29-95

Remarks:

GRAIN SIZE DISTRIBUTION TEST REPORT
RODNEY P. KINNEY ASSOCIATES

Figure No. 10

GRAIN SIZE DISTRIBUTION TEST DATA   Test No.: 1

Da⁺ ·   4-29-95
Pr ct No.:   1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: 15NIG032796
Sample Description: POORLY GRADED SAND WITH SILT
USCS Class: SP-SM   Liquid limit:
AASHTO Class: Plasticity index:

Notes

Remarks:

Fig. No.: 11

Mechanical Analysis Data

Initial
Dry sample and tare= 2677.10
Tare = 233.10
Dry sample weight = 2444.00
Tare for cumulative weight retained= 234

ve	Cumul. Wt. retained	Percent finer
0.75 inches	234.00	100.0
0.375 inches	250.80	99.3
# 4	367.90	94.5
# 10	860.20	74.4
# 20	1350.70	54.3
# 40	1751.30	37.9
# 100	2261.60	17.0
# 140	2364.20	12.8
# 200	2384.80	12.0

Fractional Components

% + 75mm. = 0.0   % GRAVEL = 5.5   % SAND = 82.5
% FINES = 12.0

D85= 3.02 D60= 1.079 D50= 0.697
D30= 0.2938 D15= 0.12823

GRAIN SIZE DISTRIBUTION TEST DATA   Test No.: 2

Da' : 4-29-95
P: ct No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: 15NING032796
Sample Description: POORLY GRADED SAND
USCS Class: SP   Liquid limit:
AASHTO Class: Plasticity index:

Notes

Remarks:

Fig. No.:

Mechanical Analysis Data

Initial
Dry sample and tare= 339.60
Tare = 163.80
Dry sample weight = 175.80
Tare for cumulative weight retained= 163.8

›ve	Cumul. Wt. retained	Percent finer
# 4	163.80	100.0
# 10	184.00	88.5
# 20	259.60	45.5
# 40	300.90	22.0
# 100	333.90	3.2
# 140	336.60	1.7
# 200	338.10	0.9

Fractional Components

% + 75mm. = 0.0   % GRAVEL = 0.0   % SAND = 99.1
% FINES = 0.9

D85= 1.82 D60= 1.113 D50= 0.922
D30= 0.5553 D15= 0.31225 D10= 0.24519
Cc = 1.1298 Cu = 4.5394

GRAIN SIZE DISTRIBUTION TEST REPORT



	Test	%+75 mm	% GRAVEL	% SAND	% SILT	% CLAY
●	1	0.0	5.5	82.5	12.0	
▲	2	0.0	0.0	99.1	0.9	

	LL	PI	D_{85}	D_{60}	D_{50}	D_{30}	D_{15}	D_{10}	C_c	C_u
●			3.02	1.08	0.70	0.294	0.1282			
▲			1.82	1.11	0.92	0.555	0.3122	0.2452	1.13	4.5

MATERIAL DESCRIPTION	USCS	AASHTO
● POORLY GRADED SAND WITH SILT	SP-SM	
▲ POORLY GRADED SAND	SP	

Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING
● Location: 15NIG032796
▲ Location: 15NING032796

Date: 4-29-95

Remarks:

GRAIN SIZE DISTRIBUTION TEST REPORT
RODNEY P. KINNEY ASSOCIATES

Figure No. 11

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST DATA

Test No.: 3

Da' : 4-29-95
Pr ct No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: 36IG032196
Sample Description: SILTY SAND
USCS Class: SM
AASHTO Class:

Liquid limit:
Plasticity index:

Notes

Remarks:

Fig. No.: 12

Mechanical Analysis Data

Initial
Dry sample and tare= 2788.70
Tare = 164.80
Dry sample weight = 2623.90
Tare for cumulative weight retained= 228

eve	Cumul. Wt. retained	Percent finer
0.75 inches	228.00	100.0
0.375 inches	234.20	99.8
# 10	1192.20	63.3
# 20	1652.40	45.7
# 40	1944.40	34.6
# 100	2338.50	19.6
# 140	2423.50	16.3
# 200	2461.50	14.9

No #4 ≈ 88% from Grain size Dist. curve.

Fractional Components

% + 75mm. = 0.0   % GRAVEL = 13.0   % SAND = 72.1
% FINES = 14.9

D85= 4.41 D60= 1.736 D50= 1.070
D30= 0.3122 D15= 0.07405

GRAIN SIZE DISTRIBUTION TEST DATA

Test No.: 4

Date: 4-29-95
Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: 36ING032196
Sample Description: POORLY GRADED SAND WITH SILT
USCS Class: SP-SM
Liquid limit:
AASHTO Class:
Plasticity index:

Notes

Remarks:

Fig. No.:

Mechanical Analysis Data

Initial
Dry sample and tare= 1797.90
Tare = 228.00
Dry sample weight = 1569.90
Tare for cumulative weight retained= 228

Sieve	Cumul. Wt. retained	Percent finer
0.375 inches	228.00	100.0
# 4	274.30	97.1
# 10	921.10	55.9
# 20	1214.50	37.2
# 40	1355.60	28.2
# 100	1586.40	13.5
# 140	1652.90	9.2
# 200	1694.10	6.6

Fractional Components

% + 75mm. = 0.0 % GRAVEL = 2.9 % SAND = 90.4
% FINES = 6.7

D85= 3.53 D60= 2.193 D50= 1.702
D30= 0.4797 D15= 0.16634 D10= 0.11246
Cc = 0.9333 Cu = 19.4984

GRAIN SIZE DISTRIBUTION TEST REPORT



	Test	%+75mm	% GRAVEL	% SAND	% SILT	% CLAY
●	3	0.0	11.6	73.5	14.9	
▲	4	0.0	2.9	90.4	6.7	

	LL	PI	D_{85}	D_{60}	D_{50}	D_{30}	D_{15}	D_{10}	C_c	C_u
●			4.20	1.75	1.07	0.311	0.0764			
▲			3.46	2.19	1.71	0.477	0.1654	0.1118	0.93	19.5

MATERIAL DESCRIPTION	USCS	AASHTO
● SILTY SAND	SM	
▲ POORLY GRADED SAND WITH SILT	SP-SM	

Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING
● Location: 36IG032196
▲ Location: 36ING032196

Date: 4-29-95

Remarks:

GRAIN SIZE DISTRIBUTION TEST REPORT
RODNEY P. KINNEY ASSOCIATES

Figure No. 12

GRAIN SIZE DISTRIBUTION TEST DATA — Test No.: 5

Da--: 4-29-95
Pr ct No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: 36NIG032196
Sample Description: POORLY GRADED SAND WITH SILT
USCS Class: SP-SM — Liquid limit:
AASHTO Class: — Plasticity index:

Notes

Remarks:

Fig. No.: 13

Mechanical Analysis Data

Initial
Dry sample and tare= 1627.50
Tare = 169.60
Dry sample weight = 1457.90
Tare for cumulative weight retained= 169.6

eve	Cumul. Wt. retained	Percent finer
0.5 inches	169.60	100.0
0.375 inches	170.70	99.9
# 4	253.20	94.3
# 10	903.90	49.6
# 20	1122.70	34.6
# 40	1237.20	26.8
# 100	1455.40	11.8
# 140	1512.80	7.9
# 200	1548.00	5.5

Fractional Components

% + 75mm. = 0.0 % GRAVEL = 5.7 % SAND = 88.8
% FINES = 5.5

D85= 3.83 D60= 2.466 D50= 2.016
D30= 0.5364 D15= 0.18599 D10= 0.12868
Cc = 0.9068 Cu = 19.1646

GRAIN SIZE DISTRIBUTION TEST DATA   Test No.: 6

Da' :   4-29-95
Pr_ct No.:   1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: 36NING032196
Sample Description: POORLY GRADED SAND WITH SILT
USCS Class: SP-SM   Liquid limit:
AASHTO Class: Plasticity index:

Notes

Remarks:

Fig. No.:

Mechanical Analysis Data

Initial
Dry sample and tare= 1627.50
Tare = 168.10
Dry sample weight = 1459.40
Tare for cumulative weight retained= 169.6

NO GRAIN SIZE DATA

Sieve	Cumul. Wt. retained	Percent finer

Fractional Components

% + 75mm. = 0.0   % GRAVEL = 0.0   % SAND = 0.0

NO Data

GRAIN SIZE DISTRIBUTION TEST REPORT



	Test	%+75mm	% GRAVEL	% SAND	% SILT	% CLAY
●	5	0.0	5.7	88.8	5.5	
▲	6	0.0	0.0	0.0		

	LL	PI	D_{85}	D_{60}	D_{50}	D_{30}	D_{15}	D_{10}	C_c	C_u
●			3.83	2.47	2.02	0.536	0.1860	0.1287	0.91	19.2
▲										

MATERIAL DESCRIPTION	USCS	AASHTO
● POORLY GRADED SAND WITH SILT	SP-SM	
▲ POORLY GRADED SAND WITH SILT	SP-SM	

Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING
● Location: 36NIG032196
▲ Location: 36NING032196

Date: 4-29-95

Remarks:

GRAIN SIZE DISTRIBUTION TEST REPORT
RODNEY P. KINNEY ASSOCIATES

Figure No. 13

GRAIN SIZE DISTRIBUTION TEST DATA

Test No.: 9

Date: 4-29-95
Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: 36ING032196AQ
Sample Description: SILTY SAND
USCS Class: SM
AASHTO Class:
Liquid limit:
Plasticity index:

Notes

Remarks:

Fig. No.: 25

Mechanical Analysis Data

	Initial
Dry sample and tare=	741.20
Tare =	228.00
Dry sample weight =	513.20

Tare for cumulative weight retained= 227.2

Sieve	Cumul. Wt. retained	Percent finer
0.75 inches	227.20	100.0
0.375 inches	228.70	99.7
# 4	241.70	97.2
# 10	376.10	71.0
# 20	479.20	50.9
# 40	535.50	39.9
# 100	635.60	20.4
# 140	660.50	15.6
# 200	675.80	12.6

Fractional Components

% + 75mm. = 0.0 % GRAVEL = 2.8 % SAND = 84.6
% FINES = 12.6

D85= 3.02 D60= 1.332 D50= 0.793
D30= 0.2480 D15= 0.09874

GRAIN SIZE DISTRIBUTION TEST DATA   Test No.: 10

Date: 4-29-95
Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: 36NING032196AQ
Sample Description: POORLY GRADED SAND WITH SILT
USCS Class: SP-SM   Liquid limit:
AASHTO Class: Plasticity index:

Notes

Remarks:

Fig. No.:

Mechanical Analysis Data

Initial
Dry sample and tare= 548.50
Tare = 164.60
Dry sample weight = 383.90
Tare for cumulative weight retained= 228

Sieve	Cumul. Wt. retained	Percent finer
0.375 inches	228.00	100.0
# 4	262.10	91.1
# 10	429.10	47.6
# 20	483.00	33.6
# 40	507.30	27.2
# 100	566.00	12.0
# 140	580.00	8.3
# 200	588.00	6.2

Fractional Components

% + 75mm. = 0.0   % GRAVEL = 8.9   % SAND = 84.9
% FINES = 6.2

D85= 4.10 D60= 2.585 D50= 2.116
D30= 0.5254 D15= 0.18429 D10= 0.12604
Cc = 0.8472 Cu = 20.5116

GRAIN SIZE DISTRIBUTION TEST REPORT



	Test	%+75mm	% GRAVEL	% SAND	% SILT	% CLAY
●	9	0.0	2.8	84.6	12.6	
▲	10	0.0	8.9	84.9	6.2	

	LL	PI	D_{85}	D_{60}	D_{50}	D_{30}	D_{15}	D_{10}	C_c	C_u
●			3.02	1.33	0.79	0.248	0.0987			
▲			4.10	2.59	2.12	0.525	0.1843	0.1260	0.85	20.5

MATERIAL DESCRIPTION	USCS	AASHTO
● SILTY SAND	SM	
▲ POORLY GRADED SAND WITH SILT	SP-SM	

Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING
● Location: 36ING032196AQ
▲ Location: 36NING032196AQ

Date: 4-29-95

Remarks:

GRAIN SIZE DISTRIBUTION TEST REPORT

RODNEY P. KINNEY ASSOCIATES

Figure No. 25



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST DATA   Test No.: 7

Da+ : 4-29-95
'r :ct No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: DMIG032296
Sample Description: POORLY GRADED SAND WITH SILT
USCS Class: SP-SM   Liquid limit:
AASHTO Class: Plasticity index:

Notes

Remarks:

Fig. No.: 14

Mechanical Analysis Data

Initial
Dry sample and tare= 885.60
Tare = 169.00
Dry sample weight = 716.60
Tare for cumulative weight retained= 224.5

›ve	Cumul. Wt. retained	Percent finer
0.75 inches	224.50	100.0
0.375 inches	230.70	99.1
# 4	267.70	94.0
# 10	403.60	75.0
# 20	522.50	58.4
# 40	636.50	42.5
# 100	811.50	18.1
# 140	850.00	12.7
# 200	862.00	11.0

Fractional Components

% + 75mm. = 0.0   % GRAVEL = 6.0   % SAND = 82.9
% FINES = 11.1

D85= 3.05 D60= 0.902 D50= 0.569
D30= 0.2541 D15= 0.12445

GRAIN SIZE DISTRIBUTION TEST DATA   Test No.: 8

Date: 4-29-95
Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: DMING032296
Sample Description: WELL GRADED SAND WITH SILT
USCS Class: SW-SM   Liquid limit:
AASHTO Class: Plasticity index:

Notes

Remarks:

Fig. No.:

Mechanical Analysis Data

Initial
Dry sample and tare= 1788.70
Tare = 352.40
Dry sample weight = 1436.30
Tare for cumulative weight retained= 352.4

Sieve	Cumul. Wt. retained	Percent finer
0.5 inches	352.40	100.0
0.375 inches	354.10	99.9
# 4	455.00	92.9
# 10	1032.10	52.7
# 20	1320.30	32.6
# 40	1451.90	23.4
# 100	1618.90	11.8
# 140	1662.60	8.8
# 200	1688.90	6.9

Fractional Components

% + 75mm. = 0.0   % GRAVEL = 7.1   % SAND = 85.9
% FINES = 7.0

D85= 3.87 D60= 2.350 D50= 1.866
D30= 0.6934 D15= 0.20230 D10= 0.12190
Cc = 1.6788 Cu = 19.2752

GRAIN SIZE DISTRIBUTION TEST REPORT



	Test	%+75 mm	% GRAVEL	% SAND	% SILT	% CLAY
●	7	0.0	6.0	82.9	11.1	
▲	8	0.0	7.1	85.9	7.0	

	LL	PI	D_{85}	D_{60}	D_{50}	D_{30}	D_{15}	D_{10}	C_c	C_u
●			3.05	0.90	0.57	0.254	0.1245			
▲			3.87	2.35	1.87	0.693	0.2023	0.1219	1.68	19.3

MATERIAL DESCRIPTION	USCS	AASHTO
● POORLY GRADED SAND WITH SILT	SP-SM	
▲ WELL GRADED SAND WITH SILT	SW-SM	

Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING
● Location: DMIG032296
▲ Location: DMING032296

Date: 4-29-95

Remarks:

GRAIN SIZE DISTRIBUTION TEST REPORT
RODNEY P. KINNEY ASSOCIATES

Figure No. 14

GRAIN SIZE DISTRIBUTION TEST DATA

Test No.: 9

Da⁺ ⁻: 4-29-95
?ı ct No.: 1801.0441
Pro ject: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: EIG032796
Sample Description: POORLY GRADED SAND
USCS Class: SP
Liquid limit:
AASHTO Class:
Plasticity index:

Notes

Remarks:

Fig. No.: 15

Mechanical Analysis Data

	Initial
Dry sample and tare=	1962.50
Tare =	226.40
Dry sample weight =	1736.10

Tare for cumulative weight retained= 226.4

?eve	Cumul. Wt. retained	Percent finer
0.75 inches	226.40	100.0
0.375 inches	231.40	99.7
# 4	425.80	88.5
# 10	928.70	59.5
# 20	1170.00	45.6
# 40	1441.00	30.0
# 100	1722.30	13.8
# 140	1884.60	4.5
# 200	1899.10	3.7

Fractional Components

% + 75mm. = 0.0 % GRAVEL = 11.5 % SAND = 84.9
% FINES = 3.6

D85= 4.24 D60= 2.030 D50= 1.116
D30= 0.4188 D15= 0.15560 D10= 0.13077
Cc = 0.6607 Cu = 15.5239

GRAIN SIZE DISTRIBUTION TEST DATA

Test No.: 10

D : 4-29-95
Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: EING032796
Sample Description: POORLY GRADED SAND
USCS Class: SP
Liquid limit:
AASHTO Class:
Plasticity index:

Notes

Remarks:

Fig. No.:

Mechanical Analysis Data

Initial
Dry sample and tare= 250.80
Tare = 164.30
Dry sample weight = 86.50
Tare for cumulative weight retained= 230

Sieve	Cumul. Wt. retained	Percent finer
0.375 inches	230.00	100.0
# 4	232.30	97.3
# 10	259.80	65.5
# 20	290.70	29.8
# 40	305.50	12.7
# 100	315.70	0.9
# 140	316.50	0.0
# 200	316.50	0.0

Fractional Components

% + 75mm. = 0.0 % GRAVEL = 2.7 % SAND = 97.3

D85= 3.13 D60= 1.768 D50= 1.413
D30= 0.8414 D15= 0.47315 D10= 0.35481
Cc = 1.1285 Cu = 4.9831

GRAIN SIZE DISTRIBUTION TEST REPORT



	Test	%+75 mm	% GRAVEL	% SAND	% SILT	% CLAY
●	9	0.0	11.5	84.9	3.6	
▲	10	0.0	2.7	97.3	0.0	

	LL	PI	D_{85}	D_{60}	D_{50}	D_{30}	D_{15}	D_{10}	C_c	C_u
●			4.24	2.03	1.12	0.419	0.1556	0.1308	0.66	15.5
▲			3.13	1.77	1.41	0.841	0.4732	0.3548	1.13	5.0

MATERIAL DESCRIPTION	USCS	AASHTO
● POORLY GRADED SAND	SP	
▲ POORLY GRADED SAND	SP	

Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING
● Location: EIG032796
▲ Location: EING032796

Date: 4-29-95

Remarks:

GRAIN SIZE DISTRIBUTION TEST REPORT
RODNEY P. KINNEY ASSOCIATES

Figure No. 15

GRAIN SIZE DISTRIBUTION TEST DATA

Test No.: 11

Da· : 4-29-95
·r ·ct No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: ENIG032796
Sample Description: POORLY GRADED SAND WITH SILT
USCS Class: SP-SM
Liquid limit:
AASHTO Class:
Plasticity index:

Notes

Remarks:

Fig. No.: 16

Mechanical Analysis Data

Initial
Dry sample and tare= 1189.60
Tare = 223.30
Dry sample weight = 966.30
Tare for cumulative weight retained= 223.3

·eve	Cumul. Wt. retained	Percent finer
0.75 inches	223.30	100.0
0.375 inches	235.40	98.7
# 4	350.60	86.8
# 10	580.00	63.1
# 20	759.80	44.5
# 40	909.70	29.0
# 100	1081.90	11.1
# 140	1114.20	7.8
# 200	1122.90	6.9

Fractional Components

% + 75mm. = 0.0 % GRAVEL = 13.2 % SAND = 79.9
% FINES = 6.9

D85= 4.42 D60= 1.758 D50= 1.096
D30= 0.4365 D15= 0.19498 D10= 0.13490
Cc = 0.8035 Cu = 13.0317

GRAIN SIZE DISTRIBUTION TEST DATA

Test No.: 12

Da' 4-29-95
'r ct No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: ENING032796
Sample Description: POORLY GRADED SAND
JSCS Class: SP
Liquid limit:
AASHTO Class:
Plasticity index:

Notes

Remarks:

Fig. No.:

Mechanical Analysis Data

Initial
Dry sample and tare= 314.40
Tare = 237.50
Dry sample weight = 76.90
Tare for cumulative weight retained= 237.5

ve	Cumul. Wt. retained	Percent finer
0.375 inches	237.50	100.0
# 4	239.10	97.9
# 10	247.70	86.7
# 20	274.20	52.3
# 40	293.30	27.4
# 100	312.00	3.1
# 140	313.60	1.0
# 200	314.20	0.3

Fractional Components

% + 75mm. = 0.0 % GRAVEL = 2.1 % SAND = 97.7
% FINES = 0.2

D85= 1.88 D60= 1.007 D50= 0.791
D30= 0.4545 D15= 0.27384 D10= 0.22491
Cc = 0.9120 Cu = 4.4771

GRAIN SIZE DISTRIBUTION TEST REPORT



	Test	%+75 mm	% GRAVEL	% SAND	% SILT	% CLAY
●	11	0.0	13.2	79.9	6.9	
▲	12	0.0	2.1	97.7	0.2	

	LL	PI	D_{85}	D_{60}	D_{50}	D_{30}	D_{15}	D_{10}	C_c	C_u
●			4.42	1.76	1.10	0.437	0.1950	0.1349	0.80	13.0
▲			1.88	1.01	0.79	0.454	0.2738	0.2249	0.91	4.5

MATERIAL DESCRIPTION	USCS	AASHTO
● POORLY GRADED SAND WITH SILT	SP-SM	
▲ POORLY GRADED SAND	SP	

Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING
● Location: ENIG032796
▲ Location: ENING032796

Date: 4-29-95

Remarks:

GRAIN SIZE DISTRIBUTION TEST REPORT

RODNEY P. KINNEY ASSOCIATES

Figure No. 16

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST DATA   Test No.: 7

Date:	4-29-95
Project No.:	1801.0440
Project:	OGS ASSESSMENT

Sample Data

Location of Sample:	9500311201 WLts IG 032296		
Sample Description:	POORLY GRADED SAND		
USCS Class:	SP	Liquid limit:	
AASHTO Class:		Plasticity index:	

Notes

Remarks:

Fig. No.: 4

Mechanical Analysis Data

Initial
Dry sample and tare= 1891.20
Tare = 161.90
Dry sample weight = 1729.30
Tare for cumulative weight retained= 161.9

Sieve	Cumul. Wt. retained	Percent finer
0.5 inches	161.90	100.0
0.375 inches	211.10	97.2
# 4	340.40	89.7
# 10	697.30	69.0
# 20	1089.90	46.3
# 40	1422.20	27.1
# 100	1763.70	7.4
# 140	1821.30	4.0
# 200	1838.40	3.1

Fractional Components

% + 75mm. = 0.0   % GRAVEL = 10.3   % SAND = 86.6
% FINES = 3.1

D85= 3.72 D60= 1.411 D50= 0.961
D30= 0.4683 D15= 0.24294 D10= 0.18009
Cc = 0.8630 Cu = 7.8343

GRAIN SIZE DISTRIBUTION TEST DATA   Test No.: 8

Da~~:   4-29-95
Pr~ject No.:   1801.0440
Project: OGS ASSESSMENT

Sample Data

Location of Sample: 9500311202   NLH NIG 032296
Sample Description: SILTY SAND
USCS Class: SM   Liquid limit:
AASHTO Class: Plasticity index:

Notes

Remarks:

Fig. No.:

Mechanical Analysis Data

Initial
Dry sample and tare= 1676.00
Tare = 231.90
Dry sample weight = 1444.10
Tare for cumulative weight retained= 228

~eve	Cumul. Wt. retained	Percent finer
0.75 inches	228.00	100.0
0.375 inches	229.80	99.9
# 4	276.50	96.6
# 10	430.00	86.0
# 20	687.30	68.2
# 40	953.10	49.8
# 100	1326.20	24.0
# 140	1410.50	18.1
# 200	1455.30	15.0

Fractional Components

% + 75mm. = 0.0   % GRAVEL = 3.4   % SAND = 81.6
% FINES = 15.0

D85= 1.86 D60= 0.610 D50= 0.422
D30= 0.1950

GRAIN SIZE DISTRIBUTION TEST REPORT



	Test	%+75mm	% GRAVEL	% SAND	% SILT	% CLAY
●	7	0.0	10.3	86.6	3.1	
▲	8	0.0	3.4	81.6	15.0	

	LL	PI	D_{85}	D_{60}	D_{50}	D_{30}	D_{15}	D_{10}	C_c	C_u
●			3.72	1.41	0.96	0.468	0.2429	0.1801	0.86	7.8
▲			1.86	0.61	0.42	0.195				

MATERIAL DESCRIPTION	USCS	AASHTO
● POORLY GRADED SAND	SP	
▲ SILTY SAND	SM	

Project No.: 1801.0440
Project: OGS ASSESSMENT
● Location: 9500311201 (NLTSIG032296)
▲ Location: 9500311202 (NLTS NIG032296)

Date: 4-29-95

Remarks:

GRAIN SIZE DISTRIBUTION TEST REPORT
RODNEY P. KINNEY ASSOCIATES

Figure No. 4

GRAIN SIZE DISTRIBUTION TEST DATA

Test No.: 9

Da' : 4-29-95
P: ect No.: 1801.0440
Project: OGS ASSESSMENT

Sample Data

Location of Sample: 9500311203 NLHS ING 032296
Sample Description: POORLY GRADED SAND WITH SILT
USCS Class: SP-SM
Liquid limit:
AASHTO Class:
Plasticity index:

Notes

Remarks:

Fig. No.: 5

Mechanical Analysis Data

Initial
Dry sample and tare= 1166.00
Tare = 164.70
Dry sample weight = 1001.30
Tare for cumulative weight retained= 164.7

ve	Cumul. Wt. retained	Percent finer
0.5 inches	164.70	100.0
0.375 inches	166.10	99.9
# 4	177.10	98.8
# 10	280.70	88.4
# 20	576.40	58.9
# 40	796.40	36.9
# 100	1074.40	9.1
# 140	1084.40	8.1
# 200	1110.90	5.5

Fractional Components

% + 75mm. = 0.0 % GRAVEL = 1.2 % SAND = 93.3
% FINES = 5.5

D85= 1.76 D60= 0.867 D50= 0.635
D30= 0.3412 D15= 0.20989 D10= 0.16106
Cc = 0.8337 Cu = 5.3827

GRAIN SIZE DISTRIBUTION TEST DATA

Test No.: 10

Da' ': 4-29-95
P: ect No.: 1801.0440
Project: OGS ASSESSMENT

Sample Data

Location of Sample: 9500311204 NCHS NIWG 032276
Sample Description: WELL GRADED SAND
USCS Class: SW
AASHTO Class:
Liquid limit:
Plasticity index:

Notes

Remarks:

Fig. No.:

Mechanical Analysis Data

	Initial
Dry sample and tare=	363.60
Tare =	233.10
Dry sample weight =	130.50

Tare for cumulative weight retained= 233.1

eve	Cumul. Wt. retained	Percent finer
0.5 inches	233.10	100.0
0.375 inches	235.40	98.2
# 4	241.00	93.9
# 10	261.60	78.2
# 20	303.40	46.1
# 40	325.40	29.3
# 100	350.70	9.9
# 140	355.70	6.1
# 200	358.60	3.8

Fractional Components

% + 75mm. = 0.0 % GRAVEL = 6.1 % SAND = 90.1
% FINES = 3.8

D85= 2.57 D60= 1.223 D50= 0.939
D30= 0.4340 D15= 0.20535 D10= 0.14876
Cc = 1.0351 Cu = 8.2224

GRAIN SIZE DISTRIBUTION TEST REPORT



	Test	%+75 mm	% GRAVEL	% SAND	% SILT	% CLAY
●	9	0.0	1.2	93.3	5.5	
▲	10	0.0	6.1	90.1	3.8	

	LL	PI	D_{85}	D_{60}	D_{50}	D_{30}	D_{15}	D_{10}	C_c	C_u
●			1.76	0.87	0.64	0.341	0.2099	0.1611	0.83	5.4
▲			2.57	1.22	0.94	0.434	0.2054	0.1488	1.04	8.2

MATERIAL DESCRIPTION	USCS	AASHTO
● POORLY GRADED SAND WITH SILT	SP-SM	
▲ WELL GRADED SAND	SW	

Project No.: 1801.0440
Project: OGS ASSESSMENT
● Location: 9500311203
▲ Location: 9500311204

Date: 4-29-95

GRAIN SIZE DISTRIBUTION TEST REPORT

RODNEY P. KINNEY ASSOCIATES

Remarks:

Figure No. 5

GRAIN SIZE DISTRIBUTION TEST DATA   Test No.: 11

Date: 4-29-95
Pr ect No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: NLING032296AQ
Sample Description: WELL GRADED SAND WITH SILT
USCS Class: SW-SM   Liquid limit:
AASHTO Class: Plasticity index:

Notes

Remarks:

Fig. No.: 26

Mechanical Analysis Data

Initial
Dry sample and tare= 444.30
Tare = 176.30
Dry sample weight = 268.00
Tare for cumulative weight retained= 228

Sieve	Cumul. Wt. retained	Percent finer
0.375 inches	228.00	100.0
# 4	230.20	99.2
# 10	252.40	90.9
# 20	336.10	59.7
# 40	396.30	37.2
# 100	455.90	15.0
# 140	466.10	11.2
# 200	471.20	9.3

Fractional Components

% + 75mm. = 0.0   % GRAVEL = 0.8   % SAND = 89.9
% FINES = 9.3

D85= 1.62 D60= 0.847 D50= 0.640
D30= 0.3195 D15= 0.14774 D10= 0.08700
Cc = 1.3852 Cu = 9.7387

GRAIN SIZE DISTRIBUTION TEST DATA   Test No.: 12

Date: 4-29-95
Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: NLNING032296AQ
Sample Description: WELL GRADED SAND
USCS Class: SW   Liquid limit:
AASHTO Class: Plasticity index:

Notes

Remarks:

Fig. No.:

Mechanical Analysis Data

	Initial
Dry sample and tare=	263.50
Tare =	230.50
Dry sample weight =	33.00

Tare for cumulative weight retained= 230.8

Sieve	Cumul. Wt. retained	Percent finer
# 4	230.80	100.0
# 10	236.70	82.1
# 20	250.50	40.3
# 40	255.50	25.2
# 100	261.50	7.0
# 140	262.10	5.2
# 200	262.20	4.8

Fractional Components

% + 75mm. = 0.0   % GRAVEL = 0.0   % SAND = 95.2
% FINES = 4.8

D85= 2.16 D60= 1.272 D50= 1.046
D30= 0.5553 D15= 0.24803 D10= 0.18815
Cc = 1.2882 Cu = 6.7608

GRAIN SIZE DISTRIBUTION TEST REPORT



	Test	%+75mm	% GRAVEL	% SAND	% SILT	% CLAY
●	11	0.0	0.8	89.9	9.3	
▲	12	0.0	0.0	95.2	4.8	

	LL	PI	D_{85}	D_{60}	D_{50}	D_{30}	D_{15}	D_{10}	C_c	C_u
●			1.62	0.85	0.64	0.320	0.1477	0.0870	1.39	9.7
▲			2.16	1.27	1.05	0.555	0.2480	0.1881	1.29	6.8

MATERIAL DESCRIPTION	USCS	AASHTO
● WELL GRADED SAND WITH SILT	SW-SM	
▲ WELL GRADED SAND	SW	

Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING
● Location: NLING032296AQ
▲ Location: NLNING032296AQ

Date: 4-29-95

GRAIN SIZE DISTRIBUTION TEST REPORT
RODNEY P. KINNEY ASSOCIATES

Remarks:

Figure No. 26

GRAIN SIZE DISTRIBUTION TEST DATA   Test No.: 17

Dat··   4-29-95
r__ct No.:   1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: N.IG032696
Sample Description: WELL GRADED SAND WITH SILT
USCS Class: SW-SM   Liquid limit:
AASHTO Class: Plasticity index:

Notes

Remarks:

Fig. No.: 19

Mechanical Analysis Data

Initial
Dry sample and tare= 700.00
Tare = 164.10
Dry sample weight = 535.90
Tare for cumulative weight retained= 227

›ve	Cumul. Wt. retained	Percent finer
0.75 inches	227.00	100.0
0.375 inches	241.60	97.3
# 4	333.10	80.2
# 10	545.80	40.5
# 20	616.70	27.3
# 40	653.50	20.4
# 100	711.50	9.6
# 140	725.50	7.0
# 200	731.50	5.9

Fractional Components

% + 75mm. = 0.0   % GRAVEL = 19.8   % SAND = 74.3
% FINES = 5.9

D85= 5.41 D60= 3.108 D50= 2.526
D30= 1.1682 D15= 0.25556 D10= 0.15578
Cc = 2.8184 Cu = 19.9526

GRAIN SIZE DISTRIBUTION TEST DATA   Test No.: 18

Dat : 4-29-95
r ct No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: N.ING032696
Sample Description: POORLY GRADED SAND
USCS Class: SP   Liquid limit:
AASHTO Class: Plasticity index:

Notes

Remarks:

Fig. No.:

Mechanical Analysis Data

Initial
Dry sample and tare= 1594.80
Tare = 167.90
Dry sample weight = 1426.90
Tare for cumulative weight retained= 167.9

Sieve	Cumul. Wt. retained	Percent finer
0.5 inches	167.90	100.0
0.375 inches	170.60	99.8
# 4	348.80	87.3
# 10	1183.60	28.8
# 20	1443.00	10.6
# 40	1512.90	5.7
# 100	1571.70	1.6
# 140	1581.10	1.0
# 200	1586.20	0.6

Fractional Components

% + 75mm. = 0.0   % GRAVEL = 12.7   % SAND = 86.7
% FINES = 0.6

D85= 4.54 D60= 3.141 D50= 2.754
D30= 2.0417 D15= 1.31826 D10= 0.74131
Cc = 1.7906 Cu = 4.2364

GRAIN SIZE DISTRIBUTION TEST REPORT



	Test	%+75 mm	% GRAVEL	% SAND	% SILT	% CLAY
●	17	0.0	19.8	74.3	5.9	
▲	18	0.0	12.7	86.7	0.6	

	LL	PI	D_{85}	D_{60}	D_{50}	D_{30}	D_{15}	D_{10}	C_c	C_u
●			5.41	3.11	2.53	1.168	0.2556	0.1558	2.82	20.0
▲			4.54	3.14	2.75	2.042	1.3183	0.7413	1.79	4.2

MATERIAL DESCRIPTION	USCS	AASHTO
● WELL GRADED SAND WITH SILT	SW-SM	
▲ POORLY GRADED SAND	SP	

Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING
● Location: N.IG032696
▲ Location: N.ING032696

Date: 4-29-95

Remarks:

GRAIN SIZE DISTRIBUTION TEST REPORT
RODNEY P. KINNEY ASSOCIATES

Figure No. 19

GRAIN SIZE DISTRIBUTION TEST DATA   Test No.: 19

Dat-: 4-29-95
r ct No.: 1801.0441
Pr ct: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: N.NIG032696
Sample Description: POORLY GRADED SAND WITH SILT
USCS Class: SP-SM   Liquid limit:
AASHTO Class: Plasticity index:

Notes

Remarks:

Fig. No.: 20

Mechanical Analysis Data

	Initial
Dry sample and tare=	664.50
Tare =	163.70
Dry sample weight =	500.80

Tare for cumulative weight retained= 164.8

ve	Cumul. Wt. retained	Percent finer
0.75 inches	164.80	100.0
0.375 inches	201.10	92.8
# 4	262.90	80.4
# 10	346.70	63.7
# 20	410.00	51.0
# 40	459.80	41.1
# 100	581.30	16.8
# 140	615.20	10.1
# 200	617.70	9.6

Fractional Components

% + 75mm. = 0.0   % GRAVEL = 19.6   % SAND = 70.8
% FINES = 9.6

D85= 5.96 D60= 1.585 D50= 0.767
D30= 0.2512 D15= 0.13804 D10= 0.10351
Cc = 0.3846 Cu = 15.3109

GRAIN SIZE DISTRIBUTION TEST DATA   Test No.: 20

Date: 4-29-95
Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: N.NING032696
Sample Description: POORLY GRADED SAND
USCS Class: SP   Liquid limit:
AASHTO Class: Plasticity index:

Notes

Remarks:

Fig. No.:

Mechanical Analysis Data

Initial
Dry sample and tare= 980.70
Tare = 222.10
Dry sample weight = 758.60
Tare for cumulative weight retained= 222.1

Sieve	Cumul. Wt. retained	Percent finer
0.5 inches	222.10	100.0
0.375 inches	235.10	98.3
# 4	298.00	90.0
# 10	543.60	57.6
# 20	777.10	26.8
# 40	893.10	11.5
# 100	966.80	1.8
# 140	974.20	0.9
# 200	975.60	0.7

Fractional Components

% + 75mm. = 0.0   % GRAVEL = 10.0   % SAND = 89.3
% FINES = 0.7

D85= 3.98 D60= 2.113 D50= 1.656
D30= 0.9311 D15= 0.50582 D10= 0.37931
Cc = 1.0814 Cu = 5.5719

GRAIN SIZE DISTRIBUTION TEST REPORT



	Test	%+75mm	% GRAVEL	% SAND	% SILT	% CLAY
●	19	0.0	19.6	70.8	9.6	
▲	20	0.0	10.0	89.3	0.7	

	LL	PI	D_{85}	D_{60}	D_{50}	D_{30}	D_{15}	D_{10}	C_c	C_u
●			5.96	1.58	0.77	0.251	0.1380	0.1035	0.38	15.3
▲			3.98	2.11	1.66	0.931	0.5058	0.3793	1.08	5.6

MATERIAL DESCRIPTION	USCS	AASHTO
● POORLY GRADED SAND WITH SILT	SP-SM	
▲ POORLY GRADED SAND	SP	

Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING
● Location: N.NIG032696
▲ Location: N.NING032696

Date: 4-29-95

Remarks:

GRAIN SIZE DISTRIBUTION TEST REPORT
RODNEY P. KINNEY ASSOCIATES

Figure No. 20

GRAIN SIZE DISTRIBUTION TEST DATA

Test No.: 1

Da‸ ·: 4-29-95
ʼr‿ːct No.: 1801.0441
Pro‿ject: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: NSIG032096
Sample Description: SILTY SAND
USCS Class: SM
AASHTO Class:
Liquid limit:
Plasticity index:

Notes

Remarks:

Fig. No.: 21

Mechanical Analysis Data

Initial
Dry sample and tare= 1289.00
Tare = 227.70
Dry sample weight = 1061.30
Tare for cumulative weight retained= 238.1

ͤve	Cumul. Wt. retained	Percent finer
0.75 inches	238.10	100.0
0.375 inches	247.90	99.1
# 4	303.10	93.9
# 10	474.70	77.7
# 20	646.00	61.6
# 40	793.20	47.7
# 100	1065.20	22.1
# 140	1135.30	15.5
# 200	1166.00	12.6

Fractional Components

% + 75mm. = 0.0 % GRAVEL = 6.1 % SAND = 81.3
% FINES = 12.6

D85= 2.85 D60= 0.767 D50= 0.462
D30= 0.2065 D15= 0.10116

GRAIN SIZE DISTRIBUTION TEST DATA

Test No.: 2

Da... : 4-29-95
Pr...ct No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: NSING032096
Sample Description: WELL GRADED SAND WITH SILT
USCS Class: SW-SM
Liquid limit:
AASHTO Class:
Plasticity index:

Notes

Remarks:

Fig. No.:

Mechanical Analysis Data

Initial
Dry sample and tare= 1033.80
Tare = 227.70
Dry sample weight = 806.10
Tare for cumulative weight retained= 228

...eve	Cumul. Wt. retained	Percent finer
0.375 inches	228.00	100.0
# 4	259.20	96.1
# 10	435.00	74.3
# 20	668.60	45.3
# 40	795.10	29.6
# 100	938.20	11.9
# 140	966.70	8.4
# 200	981.70	6.5

Fractional Components

% + 75mm. = 0.0 % GRAVEL = 3.9 % SAND = 89.6
% FINES = 6.5

D85= 2.82 D60= 1.318 D50= 0.977
D30= 0.4266 D15= 0.18621 D10= 0.12589
Cc = 1.0965 Cu = 10.4713

GRAIN SIZE DISTRIBUTION TEST REPORT



	Test	%+75 mm	% GRAVEL	% SAND	% SILT	% CLAY
●	1	0.0	6.1	81.3	12.6	
▲	2	0.0	3.9	89.6	6.5	

	LL	PI	D_{85}	D_{60}	D_{50}	D_{30}	D_{15}	D_{10}	C_c	C_u
●			2.85	0.77	0.46	0.207	0.1012			
▲			2.82	1.32	0.98	0.427	0.1862	0.1259	1.10	10.5

MATERIAL DESCRIPTION	USCS	AASHTO
● SILTY SAND	SM	
▲ WELL GRADED SAND WITH SILT	SW-SM	

Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING
● Location: NSIG032096
▲ Location: NSING032096

Date: 4-29-95

GRAIN SIZE DISTRIBUTION TEST REPORT

RODNEY P. KINNEY ASSOCIATES

Remarks:

Figure No. 21

GRAIN SIZE DISTRIBUTION TEST DATA   Test No.: 3

Dat :   4-29-95
r ct No.:   1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: OSIG032196
Sample Description: POORLY GRADED SAND WITH SILT
USCS Class: SP-SM   Liquid limit:
AASHTO Class: Plasticity index:

Notes

Remarks:

Fig. No.: 22

Mechanical Analysis Data

	Initial
Dry sample and tare=	1562.20
Tare =	223.30
Dry sample weight =	1338.90

Tare for cumulative weight retained= 224.8

ve	Cumul. Wt. retained	Percent finer
0.375 inches	224.80	100.0
# 4	265.00	97.0
# 10	525.60	77.5
# 20	785.40	58.1
# 40	1013.70	41.1
# 100	1349.30	16.0
# 140	1423.00	10.5
# 200	1444.40	8.9

Fractional Components

% + 75mm. = 0.0   % GRAVEL = 3.0   % SAND = 88.1
% FINES = 8.9

D85= 2.66 D60= 0.912 D50= 0.596
D30= 0.2723 D15= 0.14125 D10= 0.09886
Cc = 0.8222 Cu = 9.2257

GRAIN SIZE DISTRIBUTION TEST DATA   Test No.: 4

Dat-: 4-29-95
r ct No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: OSING032196
Sample Description: POORLY GRADED SAND WITH SILT
JSCS Class: SP-SM   Liquid limit:
AASHTO Class: Plasticity index:

Notes

Remarks:

Fig. No.:

Mechanical Analysis Data

Initial
Dry sample and tare= 958.70
Tare = 168.30
Dry sample weight = 790.40
Tare for cumulative weight retained= 168.3

ve	Cumul. Wt. retained	Percent finer
0.375 inches	168.30	100.0
# 4	177.70	98.8
# 10	320.30	80.8
# 20	518.50	55.7
# 40	647.50	39.4
# 100	832.80	15.9
# 140	869.80	11.2
# 200	888.30	8.9

Fractional Components

% + 75mm. = 0.0   % GRAVEL = 1.2   % SAND = 89.9
% FINES = 8.9

D85= 2.32 D60= 0.984 D50= 0.665
D30= 0.2838 D15= 0.14060 D10= 0.08872
Cc = 0.9226 Cu = 11.0917

GRAIN SIZE DISTRIBUTION TEST REPORT



	Test	%+75mm	% GRAVEL	% SAND	% SILT	% CLAY
●	3	0.0	3.0	88.1	8.9	
▲	4	0.0	1.2	89.9	8.9	

	LL	PI	D_{85}	D_{60}	D_{50}	D_{30}	D_{15}	D_{10}	C_c	C_u
●			2.66	0.91	0.60	0.272	0.1413	0.0989	0.82	9.2
▲			2.32	0.98	0.67	0.284	0.1406	0.0887	0.92	11.1

MATERIAL DESCRIPTION	USCS	AASHTO
● POORLY GRADED SAND WITH SILT	SP-SM	
▲ POORLY GRADED SAND WITH SILT	SP-SM	

Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING
● Location: OSIG032196
▲ Location: OSING032196

Date: 4-29-95

Remarks:

GRAIN SIZE DISTRIBUTION TEST REPORT
RODNEY P. KINNEY ASSOCIATES

Figure No. 22

GRAIN SIZE DISTRIBUTION TEST DATA

Test No.: 5

Date: 4-29-95
Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: OSNIG032196
Sample Description: WELL GRADED SAND WITH SILT
USCS Class: SW-SM
Liquid limit:
AASHTO Class:
Plasticity index:

Notes

Remarks:

Fig. No.: 23

Mechanical Analysis Data

Initial
Dry sample and tare= 1314.70
Tare = 246.90
Dry sample weight = 1067.80
Tare for cumulative weight retained= 247.5

Sieve	Cumul. Wt. retained	Percent finer
0.75 inches	247.50	100.0
0.375 inches	252.00	99.6
# 4	267.10	98.2
# 10	397.60	85.9
# 20	614.30	65.6
# 40	811.60	47.2
# 100	1113.20	18.9
# 140	1180.00	12.7
# 200	1210.00	9.9

Fractional Components

% + 75mm. = 0.0 % GRAVEL = 1.8 % SAND = 88.3
% FINES = 9.9

D85= 1.91 D60= 0.675 D50= 0.465
D30= 0.2301 D15= 0.12218 D10= 0.07534
Cc = 1.0423 Cu = 8.9536

GRAIN SIZE DISTRIBUTION TEST DATA Test No.: 6

Dat- : 4-29-95
Pr ct No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: OSNING032196
Sample Description: POORLY GRADED SAND WITH SILT
JSCS Class: SP-SM Liquid limit:
AASHTO Class: Plasticity index:

Notes

Remarks:

Fig. No.:

Mechanical Analysis Data

	Initial
Dry sample and tare=	969.20
Tare =	176.70
Dry sample weight =	792.50

Tare for cumulative weight retained= 169.5

ve	Cumul. Wt. retained	Percent finer
0.375 inches	169.50	100.0
# 4	204.70	95.6
# 10	375.80	74.0
# 20	525.30	55.1
# 40	655.40	38.7
# 100	836.80	15.8
# 140	873.80	11.1
# 200	894.20	8.6

Fractional Components

% + 75mm. = 0.0 % GRAVEL = 4.4 % SAND = 87.0
% FINES = 8.6

D85= 2.99 D60= 1.059 D50= 0.668
D30= 0.2944 D15= 0.14093 D10= 0.09204
Cc = 0.8892 Cu = 11.5080

GRAIN SIZE DISTRIBUTION TEST REPORT



	Test	%+75mm	% GRAVEL	% SAND	% SILT	% CLAY
●	5	0.0	1.8	88.3	9.9	
▲	6	0.0	4.4	87.0	8.6	

	LL	PI	D_{85}	D_{60}	D_{50}	D_{30}	D_{15}	D_{10}	C_c	C_u
●			1.91	0.67	0.46	0.230	0.1222	0.0753	1.04	9.0
▲			2.99	1.06	0.67	0.294	0.1409	0.0920	0.89	11.5

MATERIAL DESCRIPTION	USCS	AASHTO
● WELL GRADED SAND WITH SILT	SW-SM	
▲ POORLY GRADED SAND WITH SILT	SP-SM	

Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING
● Location: OSNIG032196
▲ Location: OSNING032196

Date: 4-29-95

Remarks:

GRAIN SIZE DISTRIBUTION TEST REPORT
RODNEY P. KINNEY ASSOCIATES

Figure No. 23

GRAIN SIZE DISTRIBUTION TEST DATA Test No.: 13

Date: 4-29-95
Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: OSING032196AQ
Sample Description: POORLY GRADED SAND WITH SILT
USCS Class: SP-SM Liquid limit:
AASHTO Class: Plasticity index:

Notes

Remarks:

Fig. No.: 27

Mechanical Analysis Data

Initial
Dry sample and tare= 687.80
Tare = 231.10
Dry sample weight = 456.70
Tare for cumulative weight retained= 231.6

Sieve	Cumul. Wt. retained	Percent finer
0.375 inches	231.60	100.0
# 4	248.40	96.3
# 10	359.50	72.0
# 20	452.80	51.6
# 40	514.80	38.0
# 100	609.90	17.2
# 140	630.60	12.6
# 200	640.30	10.5

Fractional Components

% + 75mm. = 0.0 % GRAVEL = 3.7 % SAND = 85.8
% FINES = 10.5

D85= 3.02 D60= 1.256 D50= 0.774
D30= 0.2877 D15= 0.12853

GRAIN SIZE DISTRIBUTION TEST DATA   Test No.: 14

Date: 4-29-95
Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: OSNING032196AQ
Sample Description: WELL GRADED SAND WITH SILT
USCS Class: SW-SM   Liquid limit:
AASHTO Class: Plasticity index:

Notes

Remarks:

Fig. No.:

Mechanical Analysis Data

	Initial
Dry sample and tare=	222.90
Tare =	165.10
Dry sample weight =	57.80

Tare for cumulative weight retained= 228

Sieve	Cumul. Wt. retained	Percent finer
0.375 inches	228.00	100.0
# 4	228.90	98.4
# 10	235.80	86.5
# 20	257.70	48.6
# 40	269.20	28.7
# 100	278.80	12.1
# 140	280.00	10.0
# 200	280.90	8.5

Fractional Components

% + 75mm. = 0.0   % GRAVEL = 1.6   % SAND = 90.0
% FINES = 8.4

D85= 1.91 D60= 1.084 D50= 0.869
D30= 0.4446 D15= 0.19409 D10= 0.10304
Cc = 1.7701 Cu = 10.5196

GRAIN SIZE DISTRIBUTION TEST REPORT



	Test	%+75mm	% GRAVEL	% SAND	% SILT	% CLAY
●	13	0.0	3.7	85.8	10.5	
▲	14	0.0	1.6	90.0	8.4	

	LL	PI	D_{85}	D_{60}	D_{50}	D_{30}	D_{15}	D_{10}	C_c	C_u
●			3.02	1.26	0.77	0.288	0.1285			
▲			1.91	1.08	0.87	0.445	0.1941	0.1030	1.77	10.5

MATERIAL DESCRIPTION	USCS	AASHTO
● POORLY GRADED SAND WITH SILT	SP-SM	
▲ WELL GRADED SAND WITH SILT	SW-SM	

Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING
● Location: OSING032196AQ
▲ Location: OSNING032196AQ

Date: 4-29-95

Remarks:

GRAIN SIZE DISTRIBUTION TEST REPORT
RODNEY P. KINNEY ASSOCIATES

Figure No. 27

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash | Prepared by Montgomery Watson 9/20/96 | Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST DATA — Test No.: 13

Da‘ ·: 4-29-95
P1 ect No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: RVIG032796
Sample Description: POORLY GRADED SAND WITH SILT
USCS Class: SP-SM   Liquid limit:
AASHTO Class: Plasticity index:

Notes

Remarks:

Fig. No.: 17

Mechanical Analysis Data

Initial
Dry sample and tare= 1308.60
Tare = 164.40
Dry sample weight = 1144.20
Tare for cumulative weight retained= 169.2

eve	Cumul. Wt. retained	Percent finer
1 inches	169.20	100.0
0.75 inches	205.20	96.9
0.375 inches	256.80	92.3
# 4	543.70	67.3
# 10	1036.10	24.2
# 20	1108.00	18.0
# 40	1136.80	15.4
# 100	1210.00	9.0
# 140	1231.20	7.2
# 200	1239.20	6.5

Fractional Components

% + 75mm. = 0.0   % GRAVEL = 32.7   % SAND = 60.8
% FINES = 6.5

D85= 7.16 D60= 4.154 D50= 3.475
D30= 2.3442 D15= 0.38905 D10= 0.17378
Cc = 7.6120 Cu = 23.9056

GRAIN SIZE DISTRIBUTION TEST DATA — Test No.: 14

Date: 4-29-95
Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: RVING032796
Sample Description: POORLY GRADED SAND
USCS Class: SP — Liquid limit:
AASHTO Class: — Plasticity index:

Notes

Remarks:

Fig. No.:

Mechanical Analysis Data

Initial
Dry sample and tare= 1236.60
Tare = 161.90
Dry sample weight = 1074.70
Tare for cumulative weight retained= 224.6

Sieve	Cumul. Wt. retained	Percent finer
0.375 inches	224.60	100.0
# 4	343.70	88.9
# 10	930.00	34.4
# 20	1053.20	22.9
# 40	1107.90	17.8
# 100	1202.60	9.0
# 140	1235.40	5.9
# 200	1253.60	4.3

Fractional Components

% + 75mm. = 0.0 % GRAVEL = 11.1 % SAND = 84.7
% FINES = 4.2

D85= 4.40 D60= 3.006 D50= 2.612
D30= 1.7865 D15= 0.29648 D10= 0.16482
Cc = 6.4417 Cu = 18.2390

GRAIN SIZE DISTRIBUTION TEST REPORT



	Test	%+75mm	% GRAVEL	% SAND	% SILT	% CLAY
●	13	0.0	32.7	60.8	6.5	
▲	14	0.0	11.1	84.7	4.2	

	LL	PI	D_{85}	D_{60}	D_{50}	D_{30}	D_{15}	D_{10}	C_c	C_u
●			7.16	4.15	3.48	2.344	0.3890	0.1738	7.61	23.9
▲			4.40	3.01	2.61	1.786	0.2965	0.1648	6.44	18.2

MATERIAL DESCRIPTION	USCS	AASHTO
● POORLY GRADED SAND WITH SILT	SP-SM	
▲ POORLY GRADED SAND	SP	

Project No.: 1801.0441

Project: STREET SEDIMENT SAMPLING

● Location: RVIG032796

▲ Location: RVING032796

Date: 4-29-95

Remarks:

GRAIN SIZE DISTRIBUTION TEST REPORT

RODNEY P. KINNEY ASSOCIATES

Figure No. 17

GRAIN SIZE DISTRIBUTION TEST DATA Test No.: 15

Dat~: 4-29-95
'r ct No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: RVNIG032796
Sample Description: POORLY GRADED SAND
USCS Class: SP Liquid limit:
AASHTO Class: Plasticity index:

Notes

Remarks:

Fig. No.: 18

Mechanical Analysis Data

Initial
Dry sample and tare= 747.40
Tare = 227.60
Dry sample weight = 519.80
Tare for cumulative weight retained= 228

~ve	Cumul. Wt. retained	Percent finer
0.75 inches	228.00	100.0
0.375 inches	288.40	88.4
# 4	461.00	55.2
# 10	693.70	10.4
# 20	716.20	6.1
# 40	721.10	5.1
# 100	734.70	2.5
# 140	737.50	2.0
# 200	737.80	1.9

Fractional Components

% + 75mm. = 0.0 % GRAVEL = 44.8 % SAND = 53.3
% FINES = 1.9

D85= 8.61 D60= 5.164 D50= 4.365
D30= 3.1153 D15= 2.28297 D10= 1.96562
Cc = 0.9561 Cu = 2.6272

GRAIN SIZE DISTRIBUTION TEST DATA — Test No.: 16

Date: 4-29-95
Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: RVNING032796
Sample Description: WELL GRADED SAND
USCS Class: SW — Liquid limit:
AASHTO Class: — Plasticity index:

Notes

Remarks:

Fig. No.:

Mechanical Analysis Data

	Initial
Dry sample and tare=	802.20
Tare =	223.00
Dry sample weight =	579.20

Tare for cumulative weight retained= 223

Sieve	Cumul. Wt. retained	Percent finer
0.5 inches	223.00	100.0
0.375 inches	224.70	99.7
# 4	261.70	93.3
# 10	507.40	50.9
# 20	651.50	26.0
# 40	702.10	17.3
# 100	759.20	7.4
# 140	774.60	4.8
# 200	781.20	3.6

Fractional Components

% + 75mm. = 0.0 % GRAVEL = 6.7 % SAND = 89.7
% FINES = 3.6

D85= 3.83 D60= 2.391 D50= 1.961
D30= 1.0411 D15= 0.33304 D10= 0.19838
Cc = 2.2856 Cu = 12.0504

GRAIN SIZE DISTRIBUTION TEST REPORT



	Test	%+75mm	% GRAVEL	% SAND	% SILT	% CLAY
●	15	0.0	44.8	53.3	1.9	
▲	16	0.0	6.7	89.7	3.6	

	LL	PI	D_{85}	D_{60}	D_{50}	D_{30}	D_{15}	D_{10}	C_c	C_u
●			8.61	5.16	4.37	3.115	2.2830	1.9656	0.96	2.6
▲			3.83	2.39	1.96	1.041	0.3330	0.1984	2.29	12.1

MATERIAL DESCRIPTION	USCS	AASHTO
● POORLY GRADED SAND	SP	
▲ WELL GRADED SAND	SW	

Project No.: 1801.0441

Project: STREET SEDIMENT SAMPLING

● Location: AVNIG032796

▲ Location: AVNING032796

Date: 4-29-95

Remarks:

GRAIN SIZE DISTRIBUTION TEST REPORT

RODNEY P. KINNEY ASSOCIATES

Figure No. 18

GRAIN SIZE DISTRIBUTION TEST DATA   Test No.: 1

Date: 4-29-95
Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: RVING032796AQ
Sample Description: POORLY GRADED SAND WITH SILT
USCS Class: SP-SM   Liquid limit:
AASHTO Class: Plasticity index:

Notes

Remarks:

Fig. No.: 28

Mechanical Analysis Data

Initial
Dry sample and tare= 1089.00
Tare = 229.20
Dry sample weight = 859.80
Tare for cumulative weight retained= 228

Sieve	Cumul. Wt. retained	Percent finer
0.5 inches	228.00	100.0
0.375 inches	232.00	99.5
# 4	297.40	91.9
# 10	664.50	49.2
# 20	777.30	36.1
# 40	834.10	29.5
# 100	950.40	16.0
# 140	988.20	11.6
# 200	1011.70	8.9

Fractional Components

% + 75mm. = 0.0   % GRAVEL = 8.1   % SAND = 83.1
% FINES = 8.8

D85= 4.01 D60= 2.518 D50= 2.039
D30= 0.4360 D15= 0.13788 D10= 0.08700
Cc = 0.8680 Cu = 28.9401

GRAIN SIZE DISTRIBUTION TEST DATA   Test No.: 16

Date: 4-29-95
Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING

Sample Data

Location of Sample: RVNING032796AQ
Sample Description: WELL GRADED SAND WITH SILT
USCS Class: SW-SM   Liquid limit:
AASHTO Class: Plasticity index:

Notes

Remarks:

Fig. No.:

Mechanical Analysis Data

Initial
Dry sample and tare= 497.80
Tare = 168.40
Dry sample weight = 329.40
Tare for cumulative weight retained= 224.5

Sieve	Cumul. Wt. retained	Percent finer
0.375 inches	224.50	100.0
# 4	252.10	91.6
# 10	381.10	52.5
# 20	457.00	29.4
# 40	484.50	21.1
# 100	521.20	9.9
# 140	530.30	7.2
# 200	534.80	5.8

Fractional Components

% + 75mm. = 0.0   % GRAVEL = 8.4   % SAND = 85.8
% FINES = 5.8

D85= 3.96 D60= 2.358 D50= 1.884
D30= 0.8710 D15= 0.24266 D10= 0.14962
Cc = 2.1503 Cu = 15.7580

GRAIN SIZE DISTRIBUTION TEST REPORT



	Test	%+75 mm	% GRAVEL	% SAND	% SILT	% CLAY
●	1	0.0	8.1	83.1	8.8	
▲	16	0.0	8.4	85.8	5.8	

	LL	PI	D_{85}	D_{60}	D_{50}	D_{30}	D_{15}	D_{10}	C_c	C_u
●			4.01	2.52	2.04	0.436	0.1379	0.0870	0.87	28.9
▲			3.96	2.36	1.88	0.871	0.2427	0.1496	2.15	15.8

MATERIAL DESCRIPTION	USCS	AASHTO
● POORLY GRADED SAND WITH SILT	SP-SM	
▲ WELL GRADED SAND WITH SILT	SW-SM	

Project No.: 1801.0441
Project: STREET SEDIMENT SAMPLING
● Location: RVING032796AQ
▲ Location: RVNING032796AQ

Date: 4-29-95

Remarks:

GRAIN SIZE DISTRIBUTION TEST REPORT

RODNEY P. KINNEY ASSOCIATES

Figure No. 28

Round 2 Particle Size Distribution (Sieve Analysis) Plots

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/20/96

Project #1801.0442

Round 3 Particle Size Distribution (Sieve Analysis) Plots

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 2/13/97

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

GRAIN SIZE DISTRIBUTION TEST REPORT
Street Sediment Loads Project



Method ASTM C136 with wet wash

Prepared by Montgomery Watson 9/11/96

Project #1801.0442

CHAIN OF CUSTODY REPORTS

JTm 13024

Return Cooler # ____ to:
MONTGOMERY WATSON
4000 Credit Union Drive, Suite 600
Anchorage, Alaska 99503
(907) 561-5829

MONTGOMERY WATSON
Anchorage, Alaska

P 1/4

CHAIN OF CUSTODY FORM

PROJ. NO.: 1801.0441

LABORATORY NAME: Rodney P. Kinney & Assoc.

SAMPLERS: (Signature) [illegible]

DATE	TIME	GRAB	STATION NUMBER/LOCATION	TOTAL NO. OF CONTAINERS	Particle Size Analysis Wet Sieve	Particle Size Analysis Dry Sieve	Homogenize and Split ~~Sample~~ (HEPA)	Weigh Filter (HEPA)		REMARKS
3/20	3:30	✓	NSIG032096	1	1					Rand 1
3/20	3:30	✓	NSING032096	1	1					
3/21	2:00	✓	OSIG032196	1	1					
3/21	2:00	✓	OSING032196	1	1					
3/21	2:00	✓	OSNIG032196	1	1					
3/21	2:00	✓	OSNING032196	1	1					
3/21	2:00	✓	36IG032196	1	1					
3/21	2:00	✓	36ING032196	1	1					
3/21	2:00	✓	36NIG032196	1	1					
3/21	2:00	✓	36NING032196	1	1					
3/21	2:00	✓	OSING032196AQ	1	1		1	1		Return filter & ½ of sample
3/21	2:00	✓	OSNING032196AQ	1	1		1	1		
3/21	2:00	✓	36ING032196AQ	1	1		1	1		
3/21	2:00	✓	36NING032196AQ	1	1		1	1		
3/22	2:00	✓	DMIG032296	1	1					
3/22	2:00	✓	DMING032296	1	1					
3/26	10:00	✓	12IG032696	1	1					Rand 1

Relinquished by:	Date/Time	Received by:	Relinquished by:	Date/Time	Received by:
[illegible]	3/27/96 15:30				

Received for Laboratory by: MM   Date: 3-27-96   Time: 15:30

P 2/4 13C 24

MONTGOMERY WATSON
Anchorage, Alaska

CHAIN OF CUSTODY FORM

Return Cooler # ____ to:
MONTGOMERY WATSON
4000 Credit Union Drive, Suite 600
Anchorage, Alaska 99503
(907) 561-5829

PROJ. NO. 1801.0441

LABORATORY NAME Rodney P. Kinney & Assoc.

SAMPLERS: (Signature) Culert

DATE	TIME	GRAB	STATION NUMBER/LOCATION	TOTAL NO. OF CONTAINERS	Partical Size Analysis Wet Seive	Partical Size Analysis Dry Seive	Homogenize and Split Sample (HEPA)	Weigh Filter (HEPA)		REMARKS
3/26	10:00	✓	12ING032696	1	1					Rand 1
3/26	10:00	✓	12NIG032696	1	1					
3/26	10:00	✓	12NING032696	1	1					
3/26	10:00	✓	N.IG032696	1	1					
3/26	10:00	✓	N.ING032696	1	1					
3/26	10:00	✓	N.NIG032696	1	1					
3/26	10:00	✓	N.NING032696	1	1					
3/27	3:00	✓	SIG032796	1	1					
3/27	3:00	✓	SING032796	1	1					
3/27	3:00	✓	SNIG032796	1	1					
3/27	3:00	✓	SNING032796	1	1					
3/27	3:00	✓	RVIG032796	1	1					
3/27	3:00	✓	RVING032796	1	1					
3/27	3:00	✓	RVNIG032796	1	1					
3/27	3:00	✓	RVNING032796	1	1					
3/27	3:00	✓	SING032796AQ	1	1		1	1		Return filter and ½ of Sample
3/27	3:00	✓	SNING032796AQ	1	1		1	1		Rand 1 ↓

Relinquished by:	Date/Time	Received by:	Relinquished by:	Date/Time	Received by:
Chris R	3/27/96 15:30				

Received for Laboratory by: MM Date: 3-27-96 Time: 15:30

1302

P 3/4

MONTGOMERY WATSON
Anchorage, Alaska

Return Cooler # ____ to:
MONTGOMERY WATSON
4000 Credit Union Drive, Suite 600
Anchorage, Alaska 99503
(907) 561-5829

CHAIN OF CUSTODY FORM

PROJ. NO. 1801.0441

LABORATORY NAME Rodney P. Kinney & Assoc.

SAMPLERS: (Signature) [signature]

DATE	TIME	GRAB	STATION NUMBER/LOCATION	TOTAL NO. OF CONTAINERS	Particle Size Analysis Wet Seive	Particle Size Analysis Dry Seive	Homogenize and Split Sample (HEPA)	Weigh Filter (HEPA)		Round 1 REMARKS
3/27	3:00	✓	RVING032796AQ	1	1		1	1		Return filter & ½ of Sample
3/27	3:00	✓	RVNING032796AQ	1	1		1	1		
3/27	9:00	✓	EIG032796	1	1					
3/27	9:00	✓	EING032796	1	1					
3/27	9:00	✓	ENIG032796	1	1					
3/27	9:00	✓	ENING032796	1	1					
3/27	9:00	✓	15IG032796	1	1					
3/27	9:00	✓	15ING032796	1	1					
3/27	9:00	✓	15NIG032796	1	1					
3/27	9:00	✓	15NING032796	1	1					
3/22	2:00	✓	9500311202 (NIG) NLT	1	1					
3/22	2:00	✓	NLING032296AQ	1	1		1	1		Return filter & ½ of Sample
3/22	2:00	✓	NLNING032296AQ	1	1		1	1		
		✓	Test Samp	1		1				Combine into 1 sample
3/22	2:00	✓	9500311204 NLT: NING	1	1					
3/22	2:00	✓	9500311203 NLT: ING	1	1					
3/22	2:00	✓	9500311201 NLT: IG	1	1					Round 1

Relinquished by:	Date/Time	Received by:	Relinquished by:	Date/Time	Received by:
[signature]	3/27/96 15:30				

Received for Laboratory by: MM Date: 3-27-96 Time: 15:30

5/6

MONTGOMERY WATSON
Anchorage, Alaska

Return Cooler # ____ to:
MONTGOMERY WATSON
4000 Credit Union Drive, Suite 600
Anchorage, Alaska 99503
(907) 561-5829

CHAIN OF CUSTODY FORM

PROJ. NO. 1801.0441

LABORATORY NAME RPK

SAMPLERS: (Signature) Bill [signature]

DATE	TIME	GRAB	STATION NUMBER/LOCATION	TOTAL NO. OF CONTAINERS	Particle Size Analysis wet Sieve					REMARKS
4/2			16IG040296	1	1					Round 1
4/2			16ING040296	1	1					
4/2			16NING040296	1	1					
4/2			16NIG040296	1	1					
4/2			COIG040296	1	1					
4/2			COING040296	1	1					
4/2			CONIG040296	1	1					
4/2			CONING040296	1	1					Round #1

Relinquished by:	Date/Time	Received by:	Relinquished by:	Date/Time	Received by:
Bill [signature]	4/17 5:15pm				

Received for Laboratory by: [signature] Date: 4/17 Time: 5:15pm

4/6

MONTGOMERY WATSON
Anchorage, Alaska

Return Cooler # ____ to:
MONTGOMERY WATSON
4000 Credit Union Drive, Suite 600
Anchorage, Alaska 99503
(907) 561-5829

CHAIN OF CUSTODY FORM

PROJ. NO.: 1801.0441
LABORATORY NAME: RPK
SAMPLERS: (Signature) [signature]

DATE	TIME	GRAB	STATION NUMBER/LOCATION	TOTAL NO. OF CONTAINERS	Particle Size Analysis wet sieve					REMARKS
4/16			NSING 041696	1	1					Round 2
4/16			36BING041696 ✓	1	1					Round 2
4/16			OSDNIG041696 ✓	1	1					Round 1
4/16			36B NIG 041696 ✓	1	1					Round 2
4/16			NSNING 041696	1	1					Round 2
4/16			OSD NING 041696 ✓	1	1					Round 1
4/16			NS IG 041696 ✓	1	1					Round 2
4/16			36B IG 041696 ✓	1	1					
4/16			36B NING 041696 ✓	1	1					
4/16		B.S.	NS NIG 041696 ✓	1	1					Round 2
4/16		5/96	OSD BS NIG 041696 ✓	1	1					Bus Stop 2 transects @ 200' & 150' Round 1
4/16			OSD NIG 041696 ✓	1	1					all Gullies except Bus Stop Round 1
4/16			OSD IG 041696 ✓	1	1					Round 1
4/16			OSD ING 041696 ✓	1	1					
4/5			13 NING 040596 ✓	1	1					
4/5			KB ING 040596 ✓	1	1					
4/5			KB NING 040596 ✓	1	1					Round 1

Relinquished by:	Date/Time	Received by:	Relinquished by:	Date/Time	Received by:
[signature]	4/17 5:15				

Received for Laboratory by: Mark Date: 4/17 Time: 5:15

5/6

MONTGOMERY WATSON
Anchorage, Alaska

Return Cooler # ____ to:
MONTGOMERY WATSON
4000 Credit Union Drive, Suite 600
Anchorage, Alaska 99503
(907) 561-5829

CHAIN OF CUSTODY FORM

PROJ. NO.: 1801.0441

LABORATORY NAME: Rodney P. Kenney + Ass

SAMPLERS: (Signature) Bill [signature]

DATE	TIME	GRAB	STATION NUMBER/LOCATION	TOTAL NO. OF CONTAINERS	Partical Size Analysis wet Sieve		Homogenize + Split Sample (HEPA)	weigh Filter (HEPA)		REMARKS
4/5			13 ING 040596 ✓		1					Rand 1
4/5			[illegible] ING040596 ✓		1					
4/5			9th NING 040596 ✓		1					
4/5			[illegible] NING 040596 ✓		1					
4/5			9th ING 040596 ✓		1					
4/9			ISA NING 041096 AQ ✓		1		1	1		
4/9			COL NING 041096 AQ ✓		1		1	1		
4/16			OSD NING 041696 AQ ✓		1		1	1		
4/16			OSD ING 041696 AQ ✓		1		1	1		
4/9			COL ING 041096 AQ ✓		1		1	1		
4/9			ISA ING 041096 AQ ✓		1		1	1		Rand 1

Relinquished by:	Date/Time	Received by:	Relinquished by:	Date/Time	Received by:
Bill [signature]	4/17 5:15				

Received for Laboratory by: Mark | Date: 4/17 | Time: 5:15

6/6

MONTGOMERY WATSON
Anchorage, Alaska

Return Cooler # ____ to:
MONTGOMERY WATSON
4000 Credit Union Drive, Suite 600
Anchorage, Alaska 99503
(907) 561-5829

CHAIN OF CUSTODY FORM

PROJ. NO.: 1801.0441

LABORATORY NAME: RPK

SAMPLERS: (Signature) Bill Spencer

DATE	TIME	GRAB	STATION NUMBER/LOCATION	TOTAL NO. OF CONTAINERS	Particle Size Analysis wet sieve					REMARKS
4/9			Col NIG 040996 ✓	2	1					Round 1 2 bags, 1 wet, 1 damp (combine bags)
4/9			15A IG 040996 ✓	1	1					
4/9			COL IG 040996 ✓	1	1					
4/9			15A NIG 040996 ✓	1	1					
4/5			KA IG 040596 ✓	1	1					
4/5			13 NIG 040596 ✓	1	1					
4/5			KA NIG 040596 ✓	1	1					
4/5			KB NIG 040596 ✓	1	1					
4/5			KB IG 040596 ✓	1	1					
4/5			9th IG 040596 ✓	1	1					
4/5			9th NIG 040596 ✓	1	1					
4/5			13 IG 040596 ✓	1	1					Round 1
4/9			COL NING 040996 ✓	1	1					Telephone conv. Bill Spencer
4/9			15A NING 040996 ✓	1	1					w/ Mark Alder
4/9			COL ING 040996 ✓	1	1					5/9/96
4/9			15A ING 040996 ✓	1	1			WGR 4/3/96		

Round 1

Rnd

Relinquished by:	Date/Time	Received by:	Relinquished by:	Date/Time	Received by:
Bill Spencer	4/17 5:15pm				

Received for Laboratory by: Mark

Date: 4/17

Time: 5:15

MONTGOMERY WATSON

Anchorage, Alaska

Return Cooler # ____ to:
MONTGOMERY WATSON
4000 Credit Union Drive, Suite 600
Anchorage, Alaska 99503
(907) 561-5829

CHAIN OF CUSTODY FORM

PROJ. NO. [illegible]

LABORATORY NAME

SAMPLERS: (*Signature*) [illegible]

DATE	TIME	GRAB	STATION NUMBER/LOCATION	TOTAL NO. OF CONTAINERS						REMARKS
[illegible]		✓	5 [illegible] 03 [illegible] 96AQ Dup. entry	1						Round 1
[illegible]		✓	[illegible] 03 [illegible] 96AQ Dup entry	1						Round 1
[illegible]		✓	15A [illegible] 0410 [illegible] AQ Dup entry	1						Round 1
[illegible]		✓	15A [illegible] 04109 [illegible] AQ Dup entry	1						Round 1
[illegible]		✓	15A [illegible] 04 [illegible] 96AQ Dup. Entry	1						Round 2
[illegible]		✓	15A [illegible] 0425 [illegible] AQ Dup. Entry	1						Round 2
[illegible]		✓	16 [illegible] 04 [illegible] 96AQ Dup Entry	1						Round 2
[illegible]		✓	16NINK [illegible] 042396AQ Dup Entry	1						Round 2
[illegible]		✓	36IW6032196AQ Dup Entry	1						Round 1
[illegible]		✓	36NIW6032196AQ Dup Entry	1						Round 1
[illegible]		✓	36IW6042596AQ " "	1						Round 2
4/25		✓	36NIW6042 [illegible] AQ " "	1						Round 2
[illegible]		✓	COIW6042396AQ " "	1						Round 2
[illegible]			CONIW6042 [illegible] 96AQ " "	1						Round 2
[illegible]		✓	COIW604109 [illegible] " "	1						Round 1
[illegible]		✓	CONIW6 [illegible] 4109 [illegible] AQ " "	1						Round 1

Relinquished by:	Date/Time	Received by:	Relinquished by:	Date/Time	Received by:
[illegible]	[illegible]	[illegible]			

Received for Laboratory by: Date: Time:

MONTGOMERY WATSON
Anchorage, Alaska

Return Cooler # ____ to:
MONTGOMERY WATSON
4000 Credit Union Drive, Suite 600
Anchorage, Alaska 99503
(907) 561-5829

P. 2/2

CHAIN OF CUSTODY FORM

PROJ. NO:	LABORATORY NAME
1601.0141	[illegible]

SAMPLERS: (Signature) [illegible signature]

DATE	TIME	GRAB	STATION NUMBER/LOCATION	TOTAL NO. OF CONTAINERS						REMARKS
4/26		✓	COLING042696AQ Dup. Entry	1						ROUND 2
4/26		✓	COLVING042696AQ " "	1						ROUND 2
4/19		✓	DMING041996AQ " "	1						ROUND 2
4/19		✓	DMVING041996AQ " "	1						ROUND 2
4/25		✓	KIING042596AQ " "	1						ROUND 2
4/25		✓	KIVING042596AQ " "	1						ROUND 2
3/22		✓	NLING032296AQ " "	1						ROUND 1
3/22		✓	NLVING032296AQ " "	1						ROUND 1
4/16		✓	OSDING041696AQ " "	1						Round 1
4/16		✓	OSDVING041696AQ " "	1						Round 1
3/21		✓	OSING032196AQ " "	1						ROUND 1
3/21		✓	OSVING032196AQ " "	1						ROUND 1
4/25			OSING042596AQ " "	1						ROUND 2
4/25		✓	OPVING042596AQ " "	1						ROUND 2
3/27		✓	RVING032796AQ " "	1						ROUND 1
3/27		✓	RVVING032796AQ " "	1						ROUND 1

Relinquished by:	Date/Time	Received by:	Relinquished by:	Date/Time	Received by:
[illegible signature]	[illegible]	[illegible signature]			

Received for Laboratory by: Date: Time:

MONTGOMERY WATSON

Anchorage, Alaska

Return Cooler # ____ to:
MONTGOMERY WATSON
4000 Credit Union Drive, Suite 600
Anchorage, Alaska 99503
(907) 561-5829

CHAIN OF CUSTODY FORM

PROJ. NO.	LABORATORY NAME
1801.0441	RPK

SAMPLERS: (Signature) Bill [signature]

DATE	TIME	GRAB	STATION NUMBER/LOCATION	TOTAL NO. OF CONTAINERS	Wet Wash Particle size	Total & Sub 100 microns	Sample Volume	Split Sample		REMARKS
			ISAIG 042596		✓					Rnd 2
			ISANIG 042596		✓					
			ISAING 042596		✓					
			ISAING 042596 AQ		✓		✓			
			ISANING 042596		✓					
			ISANING 042596 AQ		✓		✓			
			COLIG 042596		✓					
			COLING 042596		✓					
			COLING 042596 AQ		✓		✓			
			COLNIG 042596		✓					
			COLNING 042596		✓					
			COLNING 042596 AQ		✓		✓			
			KIIG 042596		✓					
			KIING 042596		✓					
			KIING 042596 AQ		✓		✓			
			KINIG 042596		✓					
			KINING 042596		✓					Rnd 2

Relinquished by:	Date/Time	Received by:	Relinquished by:	Date/Time	Received by:
[signature]	4/30/96 17:45				

Received for Laboratory by: Mark [signature] Date: 4/30/96 Time: 17:45

MONTGOMERY WATSON

Anchorage, Alaska

Return Cooler # ____ to:
MONTGOMERY WATSON
4000 Credit Union Drive, Suite 600
Anchorage, Alaska 99503
(907) 561-5829

CHAIN OF CUSTODY FORM

PROJ. NO.	LABORATORY NAME
1801.0441	RPK

SAMPLERS: (Signature) Bill [signature]

DATE	TIME	GRAB	STATION NUMBER/LOCATION	TOTAL NO. OF CONTAINERS	Wet Wash Partial Size	Split Sample				REMARKS
			12IG042696 ✓		✓					Rnd 2
			12ING042696 ✓		✓					
			12NIG042696 ✓		✓					
			12NING042696 ✓		✓					
			NIG042696 ✓		✓					
			NNIG042696 ✓		✓					
			NING042696 ✓		✓					
			NNING042696 ✓		✓					
			15IG042596 ✓		✓					
			15ING042596 ✓		✓					
			15NIG042696 ✓		✓					
			15NING042596 ✓		✓					
			EIG042596 ✓		✓					
			EING042596 ✓		✓					
			ENIG042596 ✓		✓					
			ENING042596 ✓		✓					
			KINING042596 AQ ✓		✓	✓				RND 2

Relinquished by:	Date/Time	Received by:	Relinquished by:	Date/Time	Received by:
[signature]	4/29/96 17:15				

Received for Laboratory by: [signature] Date: 4/30 Time: 17:45

MONTGOMERY WATSON
Anchorage, Alaska

Return Cooler # _____ to:
MONTGOMERY WATSON
4000 Credit Union Drive, Suite 600
Anchorage, Alaska 99503
(907) 561-5829

CHAIN OF CUSTODY FORM

PROJ. NO.: 1801.0441
LABORATORY NAME: RPK
SAMPLERS: (Signature) [signature]

DATE	TIME	GRAB	STATION NUMBER/LOCATION	TOTAL NO. OF CONTAINERS	Portable Site wet wash	Split Sample				REMARKS
			KDNIG041896 ✓		✓					Round 2
			KDNING041896 ✓		✓					
			9th IG041896 ✓		✓					
			9 ING041896 ✓		✓					
			9 NIG041896 ✓		✓					
			9 NING041896 ✓		✓					
			SIG041996 ✓		✓					
			SING041996 ✓		✓					
			SNIG041996 ✓		✓					
			SNING041996 ✓		✓					
			RVIG041996 ✓		✓					
			RVING041996 ✓		✓					
			RV NIG041996 ✓		✓					
			RV NING041996 ✓		✓					
			DM IG041996 ✓		✓					
			DM ING041996 ✓		✓					
			DM ING041996AQ ✓		✓	✓				Round 2

Relinquished by:	Date/Time	Received by:	Relinquished by:	Date/Time	Received by:
[signature]	4/30/96 17:45				

Received for Laboratory by: [signature] Date: 4/30/96 Time: 17:45

MONTGOMERY WATSON
Anchorage, Alaska

Return Cooler # ____ to:
MONTGOMERY WATSON
4000 Credit Union Drive, Suite 600
Anchorage, Alaska 99503
(907) 561-5829

CHAIN OF CUSTODY FORM

PROJ. NO. 1801.0441

LABORATORY NAME: RPK

SAMPLERS: (Signature) Bill [illegible]

DATE	TIME	GRAB	STATION NUMBER/LOCATION	TOTAL NO. OF CONTAINERS	Particle Size Analysis wet sieve	Split Sample				REMARKS
			KA ING 042496	1	✓					Round 2
			KA NIG 042496	1	✓					
			KA NING 042496	1	✓					
			16 IG 042396	1	✓					
			16 ING 042396	1	✓					
			16 ING 042396 AQ	1	✓	✓				
			16 NIG 042396	1	✓					
			16 NING 042396	1	✓					
			16 NING 042396 AQ	1	✓	✓				
			60 IG 042396	1	✓					
			60 ING 042396	1	✓					
			60 ING 042396 AQ	1	✓	✓				
			60 NIG 042396	1	✓					
			60 NING 042396	1	✓					
			60 NING 042396 AQ	1	✓	✓				
			KB IG 041896	1	✓					
			KB ING 041896	1	✓					Round 2

Relinquished by:	Date/Time	Received by:	Relinquished by:	Date/Time	Received by:
[illegible]	4/30/96 17:45				

Received for Laboratory by: Mark [illegible] Date: 4/30 Time: 17:45

MONTGOMERY WATSON

Anchorage, Alaska

Return Cooler # _____ to:
MONTGOMERY WATSON
4000 Credit Union Drive, Suite 600
Anchorage, Alaska 99503
(907) 561-5829

CHAIN OF CUSTODY FORM

PROJ. NO. 1801.0441

LABORATORY NAME RPK

SAMPLERS: (Signature) Bill [illegible]

DATE	TIME	GRAB	STATION NUMBER/LOCATION	TOTAL NO. OF CONTAINERS	Particle Size Analysis Wet Wash	Split Sample				REMARKS
			36IG042496 ✓		✓					Round 2
			36ING042496 ✓		✓					
			36ING042596 AQ ✓		✓	✓				
			36NIG042496 ✓		✓					
			36NING042496 ✓		✓					
			36NING042596 AQ ✓		✓	✓				
			05IG042496 ✓		✓					
			05ING042496 ✓		✓					
			05ING042596 AQ ✓		✓	✓				
			05NIG042496 ✓		✓					
			05NING042496 ✓		✓					
			05NING042596 AQ ✓		✓	✓				
			13IG042496 ✓		✓					
			13ING042496 ✓		✓					
			13NIG042496 ✓		✓					
			13NING042496 ✓		✓					
			KAIG042496 ✓		✓					Round 2

Relinquished by:	Date/Time	Received by:	Relinquished by:	Date/Time	Received by:
[illegible]	4/30/96 17:45				

Received for Laboratory by: Mark Alder Date: 4/30/96 Time: 17:45

MONTGOMERY WATSON
Anchorage, Alaska

Return Cooler # _____ to:
MONTGOMERY WATSON
4000 Credit Union Drive, Suite 600
Anchorage, Alaska 99503
(907) 561-5829

CHAIN OF CUSTODY FORM

PROJ. NO.	LABORATORY NAME

SAMPLERS: (Signature)

DATE	TIME	GRAB	STATION NUMBER/LOCATION	TOTAL NO. OF CONTAINERS	Wet Wash Particle Size	Split Sample				REMARKS
			DM NTG041996 /		/					Rand 2
			DM NIWG041996 /		/					
			DM NING041996 AQ /		/	/				
			36EIG042496 /		/					
			36EING042496 /		/					
			36ENIG042496 /		/					
			36ENING042496 /		/					Rand 2

Relinquished by:	Date/Time	Received by:	Relinquished by:	Date/Time	Received by:
[signature]	17:45 4/30/96				

Received for Laboratory by: Mark [signature] Date: 4/30/96 Time: 17:45

MC OMERY WATSON

Department c ıblic Works
Street Sediment Load Sampling
Phase 2

RETURN COOLERS TO:
MONTGOMERY WATSON
4100 Spenard Road
Anchorage, Alaska 99517
(907)248-8883

CHAIN OF CUSTODY FORM

PROJ. NO. 1801.0442

TO: DHHS - AQ

SAMPLERS: (Signature)

DATE	TIME	S/W	SAMPLE ID	TOTAL NO. OF CONTAINERS	Split Sample								REMARKS
1996 5/30			OSDING053096AQ	1	X								Rond 2
5/30			OSDNING053096AQ	1	X								Rond 2
7/17			36ING071796AQ	1	X								Rond 3
7/17			36NING071796AQ	1	X								Rnd 3
7/17			OSING071796AQ	1	X								"
7/17			OSNING071796AQ	1	X								"
7/17			OSDING071796AQ	1	X								"
7/17			OSDNING071796AQ	1	X								"
7/26			ATONG072696AQ	1	X								"
7/26			ANTONG072696AQ	1	X								"
7/26			NLTING072696AQ	1	X								"
7/26			NLTNING072696AQ	1	X								"

Relinquished by:	Date/Time:	Shipped via:	Notified:	Date/Time:	Received by:
	9/20/96 9:40				

Received for Laboratory by:	Date:	Time:

Revision Date:8/8/95

M OMERY WATSON

Department ublic Works
Street Sediment Load Sampling
Phase 2

CHAIN OF CUSTODY FORM

RETURN COOLERS TO:
MONTGOMERY WATSON
4100 Spenard Road
Anchorage, Alaska 99517
(907)248-8883

PROJ. NO. 1801.0442	TO: DHHS - AQ
SAMPLERS: (Signature)	

DATE	TIME	S/W	SAMPLE ID	TOTAL NO. OF CONTAINERS	Split Sample								REMARKS
1996 8/6			COLING080696AQ	1	X								Run 3
8/6			COLNING080696AQ	1	X								"
8/6			15AING080696AQ	1	X								"
8/6			15ANING080696AQ	1	X								"
8/6			15ATONG080696AQ	1	X								1.5 transects
8/6			15ANTONG080696AQ	1	X								3 transects
			LAST SAMPLE										

Relinquished by:	Date/Time: 9/20/96 9:40	Shipped via:	Notified:	Date/Time:	Received by:
Received for Laboratory by:				Date:	Time:

Revision Date:5/8/96

MONTGOMERY WATSON

Anchorage, Alaska

Return Cooler # ____ to:
MONTGOMERY WATSON
4000 Credit Union Drive, Suite 600
Anchorage, Alaska 99503
(907) 561-5829

CHAIN OF CUSTODY FORM

PROJ. NO. 1801.0440

LABORATORY NAME RPK & Dsr.

SAMPLERS: (Signature) Bill [signature]

DATE	TIME	GRAB	STATION NUMBER/LOCATION	TOTAL NO. OF CONTAINERS	Sieve Analysis wet sieve					REMARKS
8/23			WL+A 0823 Sed Trap	1	1					
↓			WL+B 0823 Sed Trap (OGS)	1	1					
			21 A 0823 Sed Trap	1	1					
↓			21 B 0823 Sed Trap	1	1					
5/22			21 IG052296	1	1					Rnd 3 Added on
↓			21 ING052296	1	1					9-30-96 by
			21 NIG052296	1	1					WCN as per
↓			21 NING052296	1	1					phone Convs. on
5/30			OSD IG053096							Rand2 8-19-96
↓			OSD ING053096	1	1					Bill Eganer with
			OSD NIG 053096	1	1					Mark Alden
			OSD NING053096	1	1					
			OSD ING 053096 AQ	1	1					
↓			OSD NING053096 AQ	1	1					Round 2
7/17			OSD NING071796 AQ							Round 3
7/17			OSD ING071796 AQ							" "

Relinquished by:	Date/Time	Received by:	Relinquished by:	Date/Time	Received by:
Bill [signature]	8/29 6:30 pm				

Received for Laboratory by: Mark Alden   Date: 8/29 6:30 pm   Time:

MONTGOMERY WATSON

Anchorage, Alaska

Return Cooler # ____ to:
MONTGOMERY WATSON
4000 Credit Union Drive, Suite 600
Anchorage, Alaska 99503
(907) 561-5829

P 1/10

CHAIN OF CUSTODY FORM

PROJ. NO.	LABORATORY NAME
1801.0442	RPK

SAMPLERS: (Signature)

DATE	TIME	GRAB	STATION NUMBER/LOCATION	TOTAL NO. OF CONTAINERS	Particle Size Analysis wet sieve					REMARKS
7/8			12IG070896 ✓	1	1					Rnd 3
7/8			12ING070896 ✓	1	1					
7/8			12NIG070896 ✓	1	1					
7/8			12NING070896 ✓	1	1					
7/8			WIG070896 ✓	1	1					
7/8			WING070896 ✓	1	1					
7/8			WNIG070896 ✓	1	1					
7/8			WNING070896 ✓	1	1					
7/9			13IG070996 ✓	1	1					
7/9			13ING070996 ✓	1	1					
7/9			13NIG070996 ✓	1	1					
7/9			13NING070996 ✓	1	1					
7/9			KAIG070996 ✓	1	1					
7/9			KAING070996 ✓	1	1					
7/9			KANIG070996 ✓	1	1					
7/9			KANING070996 ✓	1	1					
										Rnd 3

Relinquished by:	Date/Time	Received by:	Relinquished by:	Date/Time	Received by:
[signature]	8/14 8:00am				

Received for Laboratory by: [signature] Date: 8/14/96 Time: 8:00am

MONTGOMERY WATSON
Anchorage, Alaska

Return Cooler # ____ to:
MONTGOMERY WATSON
4000 Credit Union Drive, Suite 600
Anchorage, Alaska 99503
(907) 561-5829

p 2/10

CHAIN OF CUSTODY FORM

PROJ. NO.	LABORATORY NAME
1801.0442	RPK

SAMPLERS: (Signature)

DATE	TIME	GRAB	STATION NUMBER/LOCATION		TOTAL NO. OF CONTAINERS	particle size Anal. wet sieve					REMARKS
7/16			OMIG 071696	✓	1	1					Rnd 3
			OMING	✓	1	1					
			OMNIG	✓	1	1					
			OMNING	✓	1	1					
			KIIG	✓	1	1					
			KIING	✓	1	1					
			KINIG	✓	1	1					
			KINING	✓	1	1					
			NSIG 071696	✓	1	1					
			NSING	✓	1	1					
			NSNIG	✓	1	1					
			NSNING	✓	1	1					
			36BIG	✓	1	1					
			36BING	✓	1	1					
			36BNIG	✓	1	1					
			36BNING	✓	1	1					
											Rnd 3

Relinquished by:	Date/Time	Received by:	Relinquished by:	Date/Time	Received by:
	8/14 8:00am				

Received for Laboratory by: Date: 8/14/96 Time: 8:00am

MONTGOMERY WATSON

Anchorage, Alaska

Return Cooler # ____ to:
MONTGOMERY WATSON
4000 Credit Union Drive, Suite 600
Anchorage, Alaska 99503
(907) 561-5829

P 3/10

CHAIN OF CUSTODY FORM

PROJ. NO.	LABORATORY NAME											
1801.0442	RPK											

SAMPLERS: (Signature) Bill [signature]

DATE	TIME	GRAB	STATION NUMBER/LOCATION		TOTAL NO. OF CONTAINERS	particle size Anal. wet sieve					REMARKS
7/17			OSDIG 071796	/	1	1					RND 3
↓			OSDING	✓	1	1					↓
			OSDNIG	✓	1	1					
↓			OSDNING ↓	✓	1	1					
↓			OSIG 071796	✓	↓	↓					
			OSING 071796	✓							
			OSNIG 071796	✓							
			OSNING 071796	✓							
			OS ING 071796 AQ	✓							
			OSNING 071796 AQ	✓							
			36 IG 071796	✓							
			36ING 071796	✓							
			36ING 071796 AQ	✓							
			36 NIG 071796	✓							
			36 NING 071796	✓							
			36 NING 071796 AQ	✓	↓	↓					RND-3
↓											

Relinquished by:	Date/Time	Received by:	Relinquished by:	Date/Time	Received by:
B. [signature]	8/14 800am				

Received for Laboratory by: [signature] Date: 8/14/96 Time: 8:00 am

MONTGOMERY WATSON

Anchorage, Alaska

Return Cooler # ____ to:
MONTGOMERY WATSON
4000 Credit Union Drive, Suite 600
Anchorage, Alaska 99503
(907) 561-5829

P 4/10

CHAIN OF CUSTODY FORM

PROJ. NO.	LABORATORY NAME	TOTAL NO. OF CONTAINERS	Particle Size Anal wet sieve					REMARKS
1801.0442	RPK							

SAMPLERS: (Signature) [signature]

DATE	TIME	GRAB	STATION NUMBER/LOCATION	TOTAL NO. OF CONTAINERS	Particle Size Anal wet sieve					REMARKS
7/17			S IG 071796 ✓	1	1					Rnd 3
↓			S ING ✓	↓	↓					↓
			S NIG ✓							
			S NING ✓							
			RUIG ✓							
			RUING ✓							
			RUNIG ✓							
↓			RUNING ✓							
7/24			MULIG 072496 ✓							
↓			MUL NIG ✓							
			DEBIG ✓							
↓			DEBNIG ✓							
7/24			SPIG 072496 ✓							
↓			SP NIG ✓							
			TOW IG ✓							
↓			TOW NIG ✓	↓	↓					Rnd 3

Relinquished by:	Date/Time	Received by:	Relinquished by:	Date/Time	Received by:
[signature]	8/14 8:00am				

Received for Laboratory by: [signature] Date: 8/14/96 Time: 8:00am

p 5/10

MONTGOMERY WATSON

Anchorage, Alaska

Return Cooler # ____ to:
MONTGOMERY WATSON
4000 Credit Union Drive, Suite 600
Anchorage, Alaska 99503
(907) 561-5829

CHAIN OF CUSTODY FORM

PROJ. NO. 1806.0442

LABORATORY NAME: RPK

SAMPLERS: (Signature) [illegible]

DATE	TIME	GRAB	STATION NUMBER/LOCATION	TOTAL NO. OF CONTAINERS	Particle Size Anal. wet Sieve	Hold Before Anal. for Verification				REMARKS
7/24			6IG 072496	1	1					Bud 3
7/24			6NIG072496							
7/26			AIG 072696							
			ANIG 072696							
			ATOG 072696							
			ANTONG 072696							
			ANTOG 072696							
			ANTONG 072696							
			ATONG072696 AQ							
			ANTONG072696 AQ							
			ATOAlly 072696			X				
			ATo Ally 072696 AQ			X				
7/26			DENIG 072696							
			DENNIG072696							
			NLTBIG072696							
			NLTB NIG072696							Bud 3

Relinquished by:	Date/Time	Received by:	Relinquished by:	Date/Time	Received by:
B. [illegible]	8/14 8:00am				

Received for Laboratory by: [illegible] Date: 8/14/96 Time: 8:00am

P 6/10

MONTGOMERY WATSON
Anchorage, Alaska

Return Cooler # _____ to:
MONTGOMERY WATSON
4000 Credit Union Drive, Suite 600
Anchorage, Alaska 99503
(907) 561-5829

CHAIN OF CUSTODY FORM

PROJ. NO.	LABORATORY NAME
	RPK

SAMPLERS: (Signature) Bill [signature]

DATE	TIME	GRAB	STATION NUMBER/LOCATION	TOTAL NO. OF CONTAINERS	Particle Size Anal. w/ sieve					REMARKS
7/26			NL+IG 072696 ✓	1	1					Rnd 3
↓			NL+NIG 072696 ✓							
			NL+ING 072696 ✓							
			NL+ING 072696 AQ ✓							
			NL+NING 072696 ✓							
↓			NL+NING 072696 AQ ✓							Rnd 3
7/30			NL+A SEDTR 073096	1						
↓			21A SEDTR 073096	1						
			21B SEDTR 073096	1						
↓			NL+B SEDTR 073096 OGS	1						
7/15			21A SEDTR 071596	1						
↓			21B SEDTR 071596	2						
			NLTA SEDTR 071596	1						
↓			NLTB SEDTR 071596	2	↓					

Relinquished by:	Date/Time	Received by:	Relinquished by:	Date/Time	Received by:
[signature]	8/14 8:00am				

Received for Laboratory by: [signature] Date: 8/14/96 Time: 8:00am

P 7/10

MONTGOMERY WATSON
Anchorage, Alaska

Return Cooler # _____ to:
MONTGOMERY WATSON
4000 Credit Union Drive, Suite 600
Anchorage, Alaska 99503
(907) 561-5829

CHAIN OF CUSTODY FORM

PROJ. NO.: 1801.0442
LABORATORY NAME: RPK
SAMPLERS: (Signature) Bill [signature]

DATE	TIME	GRAB	STATION NUMBER/LOCATION	TOTAL NO. OF CONTAINERS	Particle Size Anal wet Sieve					REMARKS
8/6/96			ISAIG080696	1	1					Rud 3
			ISAING080696AQ							
			ISAING080696							
			ISANIG080696							
			ISANING080696							
			ISANING080696AQ							
			COLIG080696							
			COLING080696							
			COLING080696 AQ							
			COLNIG080696							
			COLNING080696							
			COLNING080696AQ							
			ISATOG080696							
			ISATONG080696							
			ISATONG080696AQ							
			ISANTOG080696							Rud 3
			ISANTONG080696							

Relinquished by:	Date/Time	Received by:	Relinquished by:	Date/Time	Received by:
8/14 B. [signature] 8:00am	8/14 8:00am				

Received for Laboratory by: [signature] Date: 8/14 Time: 8:00am

MONTGOMERY WATSON

Anchorage, Alaska

Return Cooler # ____ to:
MONTGOMERY WATSON
4000 Credit Union Drive, Suite 600
Anchorage, Alaska 99503
(907) 561-5829

P 8/10

CHAIN OF CUSTODY FORM

PROJ. NO. 1801.0442

LABORATORY NAME RPK

SAMPLERS: (Signature) Bill [signature]

DATE	TIME	GRAB	STATION NUMBER/LOCATION	TOTAL NO. OF CONTAINERS	Particle Size Anal. wet sieve	Hold for Verification				REMARKS
8/6/96			15A NTONG080696 AQ ✓	1	1					Rnd. 3
↓			15A To Alley 080696			X				
↓			15A To Alley 080696 AQ							
			16 IG 080696 ✓							
			16 ING 080696 ✓							
			16 WIG 080696 ✓							
			16 NING 080696 ✓							
			COIG 080696 ✓							
			COING 080696 ✓							
			CONIG 080696 ✓							
			CONING 080696 ✓							
			16 TOG 080696 ✓							
			16 TONG 080696 ✓							
			16 NTOG 080696 ✓							
			16 NTONG 080696							
↓			16 To Alley 080696	↓	↓	X				Rnd. 3

@ 9/4/96

Relinquished by:	Date/Time	Received by:	Relinquished by:	Date/Time	Received by:
B [signature]	8/14 8:00am				

Received for Laboratory by: [signature] Date: 8/14/96 Time: 8:00am

MONTGOMERY WATSON

Anchorage, Alaska

Return Cooler # ____ to:
MONTGOMERY WATSON
4000 Credit Union Drive, Suite 600
Anchorage, Alaska 99503
(907) 561-5829

P 9/10

CHAIN OF CUSTODY FORM

PROJ. NO. 1801.0442

LABORATORY NAME RPK

SAMPLERS: (Signature) Bill [signature]

DATE	TIME	GRAB	STATION NUMBER/LOCATION	TOTAL NO. OF CON-TAINERS	Particle Size Anal. wet sieve	Hold for Verification				REMARKS
8/7/96			1SIG 080796	1	1					Rnd 3
			1SING 080796							
			1SNIG 080796							
			1SNING 080796							
			EIG 080796							
			EIWG 080796							
			ENIG 080796							
			ENING 080796							
			20IG 080796							
			20NIG 080796							
			LkOtIG 080796							
			LkOTNIG 080796							
8/8/96			13TOG 080896							
			13TONG 080896							
			13NTOG 080896							
			13NTONG 080896							
			13 TOAlley 080896			X				Rnd 3

Relinquished by:	Date/Time	Received by:	Relinquished by:	Date/Time	Received by:
[signature]	8/14 8:00am				

Received for Laboratory by: [signature] Date: 8/14/96 Time: 8:00am

P 10/10

MONTGOMERY WATSON
Anchorage, Alaska

Return Cooler # ____ to:
MONTGOMERY WATSON
4000 Credit Union Drive, Suite 600
Anchorage, Alaska 99503
(907) 561-5829

CHAIN OF CUSTODY FORM

PROJ. NO.	LABORATORY NAME
1801.0442	RPK

SAMPLERS: (Signature) Bill [signature]

DATE	TIME	GRAB	STATION NUMBER/LOCATION	TOTAL NO. OF CONTAINERS	Particle Size Anal. Wet Sieve	Hold for Verification				REMARKS
8/8/96			KBIG080896	1	1					Rnd 3
			KBING080896							
			KBNIG080896							
			KBNING080896							
			9IG080896							
			9ING080896							
			9NIG080896							
			9NING080896							
			KB ~~IG~~ TOG 080896							
			KB ~~ING~~ TONG080896							
			KB ~~NIG~~ NTOG080896							
			KB ~~NING~~ NTONG080896							
			KB ~~IG~~ TO Alley 080896			X				
8/12/96			21 ~~[illegible]~~ IG 081296							
			21 ~~A~~ ING 081296							
			21 NIG081296							
			21 NING081296							Rnd 3

Relinquished by:	Date/Time	Received by:	Relinquished by:	Date/Time	Received by:
B [signature]	8/14 8:00am				

Received for Laboratory by: [signature] Date: 8/14/96 Time: 8:00am